



This is a digital copy of a book that was preserved for generations on library shelves before it was carefully scanned by Google as part of a project to make the world's books discoverable online.

It has survived long enough for the copyright to expire and the book to enter the public domain. A public domain book is one that was never subject to copyright or whose legal copyright term has expired. Whether a book is in the public domain may vary country to country. Public domain books are our gateways to the past, representing a wealth of history, culture and knowledge that's often difficult to discover.

Marks, notations and other marginalia present in the original volume will appear in this file - a reminder of this book's long journey from the publisher to a library and finally to you.

Usage guidelines

Google is proud to partner with libraries to digitize public domain materials and make them widely accessible. Public domain books belong to the public and we are merely their custodians. Nevertheless, this work is expensive, so in order to keep providing this resource, we have taken steps to prevent abuse by commercial parties, including placing technical restrictions on automated querying.


We also ask that you:

- + *Make non-commercial use of the files* We designed Google Book Search for use by individuals, and we request that you use these files for personal, non-commercial purposes.
- + *Refrain from automated querying* Do not send automated queries of any sort to Google's system: If you are conducting research on machine translation, optical character recognition or other areas where access to a large amount of text is helpful, please contact us. We encourage the use of public domain materials for these purposes and may be able to help.
- + *Maintain attribution* The Google "watermark" you see on each file is essential for informing people about this project and helping them find additional materials through Google Book Search. Please do not remove it.
- + *Keep it legal* Whatever your use, remember that you are responsible for ensuring that what you are doing is legal. Do not assume that just because we believe a book is in the public domain for users in the United States, that the work is also in the public domain for users in other countries. Whether a book is still in copyright varies from country to country, and we can't offer guidance on whether any specific use of any specific book is allowed. Please do not assume that a book's appearance in Google Book Search means it can be used in any manner anywhere in the world. Copyright infringement liability can be quite severe.

About Google Book Search

Google's mission is to organize the world's information and to make it universally accessible and useful. Google Book Search helps readers discover the world's books while helping authors and publishers reach new audiences. You can search through the full text of this book on the web at <http://books.google.com/>

B 465298



Engin. Library

TG

270

.H826e

ELEMENTS OF GRAPHIC STATICS.



THE
ELEMENTS OF GRAPHIC STATICS

A Text-Book for Students of Engineering

BY
L. M. Hoskins
L. M. HOSKINS

PROFESSOR OF PURE AND APPLIED MECHANICS IN THE LELAND
STANFORD JUNIOR UNIVERSITY; FORMERLY PROFESSOR
OF MECHANICS IN THE UNIVERSITY OF WISCONSIN

New York
MACMILLAN AND CO.
AND LONDON
1892

All rights reserved

COPYRIGHT, 1892,
By MACMILLAN AND CO.

TYPOGRAPHY BY J. S. CUSHING & Co., BOSTON, U.S.A.
PRESSWORK BY BERWICK & SMITH, BOSTON, U.S.A.

PREFACE.

THE present work is designed as an elementary text-book for the use of students of engineering. In preparing it, a chief aim has been simplicity of presentation. The matter treated has been limited to the development of fundamental principles, and their application to the solution of typical problems. The method of the force and funicular polygons is deduced purely from statical principles, with very little consideration of the geometrical theory of reciprocal figures. Since the book is designed to embrace only what can profitably be taken in an elementary course by the student of engineering, it has not been thought best to include a discussion of problems involving the theory of elasticity. For similar reasons, the discussion of curves of inertia has been limited to simple cases; a more general treatment being of interest to few besides the student of pure mathematics. No effort has been made to secure novelty in the matter treated, but it is believed that in a few cases it has been found possible to simplify, and perhaps thereby improve, the methods usually adopted.

Attention is invited to the method adopted for lettering corresponding lines in force and space diagrams. It will be seen that this is merely an extension of Bow's well-known notation. This notation is, however, capable of a much wider use than has usually been given it. It is believed that its use, wherever applicable, will be found of great value, both in facilitating the work of the student, and in guarding the draughtsman against mistakes.

There is an unfortunate diversity of usage among writers in regard to the technical terms of mechanics,—a diversity especially noticeable in engineering literature. In this book the endeavor has been made in all cases to comply with the usage to which the highest authorities are tending.


L. M. H.

MADISON, WIS., July, 1892.

v

134942

1
111
6-1942
Revised



CONTENTS.



PART I.—GENERAL THEORY.

CHAPTER I. DEFINITIONS.—CONCURRENT FORCES.

	PAGE
§ 1. Preliminary Definitions	1
2. Composition of Concurrent Forces	5
3. Equilibrium of Concurrent Forces	6
4. Resolution of Concurrent Forces	8

CHAPTER II NON-CONCURRENT FORCES.

§ 1. Composition of Non-concurrent Forces Acting on the Same Rigid Body	11
2. Equilibrium of Non-concurrent Forces	18
3. Resolution into Non-concurrent Systems	28
4. Moments of Forces and of Couples	30
5. Graphic Determination of Moments	35
6. Summary of Conditions of Equilibrium	37

CHAPTER III. INTERNAL FORCES AND STRESSES.

§ 1. External and Internal Forces	40
2. External and Internal Stresses	42
3. Determination of Internal Stresses	46

PART II.—STRESSES IN SIMPLE STRUCTURES.

CHAPTER IV. INTRODUCTORY.

§ 1. Outline of Principles and Methods	53
--	----

CHAPTER V. ROOF TRUSSES.—FRAMED STRUCTURES SUSTAINING STATIONARY LOADS.

	PAGE
§ 1. Loads on Roof Trusses	58
2. Roof Truss with Vertical Loads	61
3. Stresses Due to Wind Pressure	67
4. Maximum Stresses	71
5. Cases Apparently Indeterminate	74
6. Three-hinged Arch	80
7. Counterbracing	88

CHAPTER VI. SIMPLE BEAMS.

§ 1. General Principles	94
2. Beam Sustaining Fixed Loads	98
3. Beam Sustaining Moving Loads	101

CHAPTER VII. TRUSSES SUSTAINING MOVING LOADS.

§ 1. Bridge Loads	112
2. Truss Regarded as a Beam	115
3. Truss with Parallel Chords Sustaining Concentrated Loads	117
4. Parallel Chords—Uniformly Distributed Moving Load	130
5. Truss with Curved Chords—Uniform Panel Loads	132
6. Truss with Curved Chords—Concentrated Loads	137

PART III.—CENTROIDS AND MOMENTS OF INERTIA.

CHAPTER VIII. CENTROIDS.

§ 1. Centroid of Parallel Forces	144
2. Center of Gravity—Definitions and General Principles	149
3. Centroids of Lines and of Areas	152

CHAPTER IX. MOMENTS OF INERTIA.

§ 1. Moments of Inertia of Forces	159
2. Moments of Inertia of Plane Areas	169

CHAPTER X. CURVES OF INERTIA.

§ 1. General Principles	179
2. Inertia-Ellipses for Systems of Forces	182
3. Inertia-Curves for Plane Areas	187

GRAPHIC STATICS.

PART I.

GENERAL THEORY.

CHAPTER I.—DEFINITIONS. CONCURRENT FORCES.

§ 1. *Preliminary Definitions.*

1. **Dynamics** treats of the action of forces upon bodies. Its two main branches are Statics and Kinetics.

Statics treats of the action of forces under such conditions that no change of motion is produced in the bodies acted upon.

Kinetics treats of the laws governing the production of motion by forces.

2. **Graphic Statics** has for its object the deduction of the principles of statics, and the solution of its problems, by means of geometrical figures.

3. **A Force** is that which tends to change the state of motion of a body. We conceive of a force as a *push* or a *pull* applied to a body at a definite point and in a definite direction. Such a push or pull *tends* to give motion to the body, but this tendency may be neutralized by the action of other forces. The effect of a force is completely determined when three things are given, — its *magnitude*, its *direction*, and its *point of application*. The line parallel to the direction of the force and containing its point of application, is called its *line of action*.

Every force acting upon a body is exerted *by some other body*. But the problems of statics usually concern only the body *acted upon*. Hence, frequently, no reference is made to the bodies exerting the forces.

4. **Unit Force.** — The *unit force* is a force of arbitrarily chosen magnitude, in terms of which forces are expressed. Several different units are in use. The one employed in this work is the *pound*, which will now be defined.

A *pound force* is a force equal to the weight of a pound mass at the earth's surface. A *pound mass* is the quantity of matter contained in a certain piece of platinum, arbitrarily chosen, and established as the standard by act of the British Parliament.

The pound force, as thus defined, is not perfectly definite, since the weight of any given mass (that is, the attraction of the earth upon it) is not the same for all positions on the earth's surface. The variations are, however, unimportant for most of the requirements of the engineer.

In its fundamental meaning, the word "pound" refers to the unit mass, and it is unfortunate that it is also applied to the unit force. The usage is, however, so firmly established that it will be here followed.

5. **Concurrent and Non-concurrent Forces.** — Forces acting on the same body are *concurrent* when they have the same point of application. When applied at different points they are non-concurrent.

6. **Complanar Forces** are those whose lines of action are in the same plane. In this work, only complanar systems will be considered unless otherwise specified.

7. **A Couple** is the name given to a system consisting of two forces, equal in magnitude, but opposite in direction, and having different lines of action. The perpendicular distance between the two lines of action is called the *arm* of the couple.

8. **Equivalent Systems of Forces.** — Two systems of forces are *equivalent* when either may be substituted for the other without change of effect.

9. **Resultant.** — A single force that is equivalent to a given system of forces is called the *resultant* of that system. It will be shown subsequently that a system of forces may not be equivalent to any single force. When such is the case, the simplest system equivalent to the given system may be called its resultant. Any forces having a given force for their resultant are called *components* of that force.

10. **Composition and Resolution of Forces.** — Having given any system of forces, the process of finding an equivalent system is called the *composition of forces*, if the system determined contains fewer forces than the given system. If the reverse is the case, the process is called the *resolution of forces*.

The process of finding the resultant of any given forces is the most important case of *composition*; while the process of finding two or more forces, which together are equivalent to a single given force, is the most common case of *resolution*.

11. **Representation of Forces Graphically.** — The *magnitude* and *direction* of a force can both be represented by a line; the length of the line representing the magnitude of the force, and its direction the direction of the force.

In order that the length of a line may represent the magnitude of a force, a certain length must be chosen to denote the unit force. Then a force of any magnitude will be represented by a length which contains the assumed length as many times as the magnitude of the given force contains that of the unit force.

In order that the direction of a force may be represented by a line, there must be some means of distinguishing between the two opposite directions along the line. The usual method is to place an arrow-head on the line, pointing in the direction toward

which the force acts. If the line is designated by letters placed at its extremities, the order in which these are read may indicate the direction of the force. Thus, AB and BA represent two forces, equal in magnitude but opposite in direction.

The *line of action* of a force can also be represented by a line drawn on the paper.


In solving problems in statics, it is usually convenient to draw two separate figures, in one of which the forces are represented in *magnitude and direction* only, and in the other in *line of action* only.

These two species of diagrams will be called *force diagrams* and *space diagrams*, respectively.

12. Notation. — The use of graphic methods is much facilitated by the adoption of a convenient system of notation in the figures drawn.

There will generally be two figures (the force diagram and the space diagram) so related that for every line in one there is a corresponding line in the other.

In the force diagram each line represents a force in *magnitude and direction*; in the space diagram the corresponding line represents the *line of action* of the force. These lines will usually be designated in the following manner: The line



denoting the magnitude and direction of the force will be marked by two capital letters, one at each extremity; while the action-line will be marked by the corresponding small letters, one being placed at each side of the line designated. Thus, in Fig. 1, AB represents a force in magni-

tude and direction, while its action-line is marked by the letters ab , placed as shown.

§ 2. *Composition of Concurrent Forces.*

13. **Resultant of Two Concurrent Forces.**—If two concurrent forces are represented in magnitude and direction by two lines AB and BC , their resultant is represented in magnitude and direction by AC . (Fig. 2.) Proofs of this proposition are given in all elementary treatises on





Fig. 2

mechanics, and the demonstration will be here omitted. The *point of application* of the resultant is the same as that of the given force. Thus if O (Fig. 2) is the given point of application, then ab , bc , and ac , drawn parallel to AB , BC , and AC respectively, are the lines of action of the two given forces and their resultant. The figure marked (A) is a *force diagram*, and (B) is the corresponding *space diagram* (Art. 11).

14. **Resultant of Any Number of Concurrent Forces.**—If any number of concurrent forces are represented in magnitude and direction by lines AB , BC , CD , . . . , their resultant is represented in magnitude and direction by the line AN , where N is the extremity of the line representing the last of the given forces.

This proposition follows immediately from the preceding one; for the resultant of the forces represented by AB and BC is a force represented by AC ; the resultant of AC and CD is AD , and so on. By continuing the process we shall arrive at the result stated. It is






Fig. 3

readily seen that the order in which the forces are taken does not affect the magnitude or direction of the resultant as thus

determined. The point of application of the resultant is the same as that of the given forces. Figure 3 shows the force diagram and space diagram for a system of four forces represented by AB , BC , CD , DE , and their resultant represented by AE , applied at the point O .

It is evident that every system of concurrent forces has for its resultant some single force (Art. 9); though in particular cases its magnitude may be zero.

15. Force Polygon. — The figure formed by drawing in succession lines representing in magnitude and direction any number of forces is called a *force polygon* for those forces. Thus Fig. 4 is a force polygon for any four forces represented in magnitude and direction by the lines AB , BC , CD , and DE , whatever their lines of action. It may happen that the point E coincides with A , in which case the polygon is said to be *closed*. It is evident that the order in which the forces are taken does not affect the relative positions of the initial and final points.



§ 3. *Equilibrium of Concurrent Forces.*

16. Definition. — A system of forces acting on a body is in *equilibrium* if the motion of the body is unchanged by its action.

17. Condition of Equilibrium. — In order that no motion may result from the action of any system of concurrent forces, the magnitude of the resultant must be zero; and conversely, if the magnitude of the resultant is zero, no motion can result. But (Arts. 14 and 15) the condition that the resultant is zero is identical with the condition that the force polygon closes. Hence, the following proposition:

If any system of concurrent forces is in equilibrium, the force polygon for the system must close. And conversely, If the force

polygon is closed for any system of concurrent forces, the system is in equilibrium.

The comparison of this with the analytical conditions of equilibrium is given in Art. 22.

18. Method of Solving Problems in Equilibrium. — If a system of concurrent forces in equilibrium be partially unknown, we may in certain cases determine the unknown elements by applying the principles of Art. 17.

The most usual case is that in which two forces are unknown except as to lines of action. Thus, suppose a system of five forces in equilibrium, three being fully known, represented in magnitude and direction by AB , BC , CD (Fig. 5), and in lines of action by ab , bc , cd ,




Fig. 5

while concerning the other two we know only their lines of action de , ea . To determine these two in magnitude and direction, it is necessary only to complete the force polygon of which $ABCD$ is the known part. The remaining sides must be parallel respectively to de and ea . From D draw a line parallel to de , and from A a line parallel to ea , prolonging them till they intersect at E . Then DE and EA represent the required forces in magnitude and direction, and the complete force polygon is $ABCDEA$. It is evident that $ABCDEA$ is an equally legitimate form of the force polygon, and gives the same result for the magnitude and direction of each of the unknown forces. This problem occurs constantly in the construction of stress diagrams by the method described in Part II.

The student will find little difficulty in treating other problems in the equilibrium of concurrent forces.

19. Problems in Equilibrium. — (1) A particle is in equilibrium under the action of five forces, three of which are

completely known, while of the remaining two, one is known in direction only, and the other in magnitude only. To determine the unknown forces.

(2) Suppose two forces known in magnitude but not in direction, the remaining forces being wholly known.

(3) Suppose one force wholly unknown, the others being known.

§ 4. *Resolution of Concurrent Forces.*

20. To Resolve a Given Force into Any Number of Components having the same point of application, we have only to draw a closed polygon of which one side shall represent the magnitude and direction of the given force; then the remaining sides will represent, in magnitude and direction, the required components. This problem is, in general, indeterminate, unless the components are required to satisfy certain specified conditions.

[NOTE. — A problem is said to be *indeterminate* if its conditions can be satisfied in an infinite number of ways. It is *determinate* if it admits of only one solution. Thus, the problem, to determine the values of x and y which shall satisfy the equation $x + y = 10$, is indeterminate; while the problem, given $2x + 3 = 7$, to find the value of x , is determinate. The case in which a finite number of solutions is possible may be called *incompletely determinate*. Thus, the problem, given $x^2 + x - 6 = 0$, to find x , admits of two solutions, and therefore is incompletely determinate. All these classes of problems may be met with in statics.]

21. To Resolve a Given Force into Two Components. — This problem is indeterminate unless additional data are given. For if the given force be represented in magnitude and direction by a line, any two lines which with the given line form a triangle may represent forces which are together equivalent to the given force. But an infinite number of such triangles may be drawn. The solution of the following four cases of this problem will form exercises for the student. In each case the *force diagram* and *space diagram* should be completely drawn, and the student should notice whether the problem is determinate, partially determinate, or indeterminate.

(1) Let the lines of action of the required components be given.

(2) Let the two components be given in magnitude only.

(3) Let the line of action of one component and the magnitude of the other be given.

(4) Let the magnitude and direction of one component be given.

It will be noticed that these four cases correspond to four cases of the solution of a plane triangle.

22. Resolved Part of a Force.—If a force is conceived as replaced by two components at right angles to each other, each is called the *resolved part*,* in its direction, of the given force.

It is readily seen that the resolved part of a force represented by AB (Fig. 6) in the direction of any line XX , is represented in magnitude and direction by $A'B'$, the orthographic projection of AB upon XX . It follows that the resolved part (in any given direction) of the resultant of any concurrent forces is equal to the algebraic sum of the resolved parts of its components in that direction; signs plus and minus being given to the resolved parts to distinguish the two opposite directions which they may have. Thus (Fig. 7) the resolved parts of the forces AB , BC , CD , in a direction parallel to XX , are $A'B'$, $B'C'$, $C'D'$; and their algebraic sum is $A'D'$, which is the resolved part of the resultant AD .

If the resultant is zero, D' coincides with A' ; hence,

(1) For the equilibrium of any concurrent forces, the sum of their resolved parts in any direction must be zero.




Fig. 6




Fig. 7

* The term "resolute" has been proposed by J. B. Lock ("Elementary Statics") to denote what is here defined as the *resolved part* of a force.

Again, if D' coincides with A' , then either D coincides with A , or else AD is perpendicular to XX ; hence,

(2) If the sum of the resolved parts of any concurrent forces in a given direction is zero, their resultant (if any) is perpendicular to that direction. And if the sum of the resolved parts is zero for each of two directions, the resultant is zero, and the system is in equilibrium.

Propositions (1) and (2) state the conditions of equilibrium for concurrent forces usually deduced in treatises employing algebraic methods.

CHAPTER II. — NON-CONCURRENT FORCES.

§ 1. *Composition of Non-concurrent Forces Acting on the Same Rigid Body.*

23. **Definition of Rigid Body.** — A *rigid body* is one whose particles do not change their positions relative to each other under any applied forces. No known body is perfectly rigid, but for the purposes of statics, most solid bodies may be considered as such ; and any body which has assumed a form of equilibrium under applied forces, may, for the purposes of statics, be treated as a rigid body without error.

24. **Change of Point of Application.** — The effect of a force upon a rigid body will be the same, at whatever point in its line of action it is applied, if only the particle upon which it acts is rigidly connected with the body.

This proposition is fundamental to the development of the principles of statics, and is amply justified by experience.* In applying the principle, we are at liberty to assume a point of application outside the actual body, the latter being ideally extended to any desired limits.

25. **Resultant of Two Non-Parallel Forces.** — If two coplanar forces are not parallel, their lines of action must intersect, and the point of intersection may be taken as the point of application of each force. Hence, they may be treated as

* This proposition may be proved analytically by deducing the equations of motion of a rigid body, and showing that the effect of any force on the motion of the body depends only upon its magnitude, direction, and line of action. But such a proof is, of course, outside the scope of this work.

concurrent forces, and their resultant may be determined as in Art. 13. The following proposition may therefore be stated :

If two forces acting in the same plane on a rigid body are represented in magnitude and direction by AB and BC , their resultant is represented in magnitude and direction by AC , and its line of action passes through the point of intersection of the lines of action of the given forces. Its point of application may be any point of this line.

It may happen that the point of intersection of the two given lines of action falls outside the limits available for the drawing. In such a case it will be most convenient to find the resultant by the method to be explained in Art. 27. The same remark applies to the case of two parallel forces.

26. Resultant of Any Number of Non-concurrent Forces — First Method. — The method of the preceding article may be extended to the determination of the resultant of any number of forces acting on the same rigid body. Let AB, BC, CD, DE




Fig. 8

(Fig. 8), represent in magnitude and direction four forces, and let ab, bc, cd, de represent their lines of action. To find their resultant, we may proceed as follows: The resultant of AB and BC is represented

in magnitude and direction by AC , and in line of action by ac drawn parallel to AC through the point of intersection of ab and bc . Combining this resultant with CD , we get as *their* resultant a force represented in magnitude and direction by AD , and in line of action by ad drawn parallel to AD through the point of intersection of ac and cd . This is evidently the resultant of AB, BC , and CD . In the same way, this resultant

combined with DE gives for *their* resultant a force whose magnitude and direction are represented by AE , and whose line of action is ae , parallel to AE and passing through the point in which ad intersects de . This last force is the resultant of the four given forces.

The process may evidently be extended to the case of any number of forces.

As in the case discussed in the preceding article, this method will become inapplicable or inconvenient in case any of the points of intersection fall outside the limits available for the drawing. For this reason it is usually most convenient to employ the method described in Art. 27.

The student should bear in mind that the length and direction AE and the line ae are not the magnitude, direction, and line of action of any actual force applied to the body. By the resultant is meant an ideal force, which, if it acted, would produce the same effect upon the motion of the body as is produced by the given forces. It is a force which may be conceived to replace the actual forces, and may be assumed to be applied to any particle in its line of action, provided that particle is conceived as rigidly connected with the given body. The line of action may in reality fail to meet the given body. (See Art. 24.)

27. Resultant of Non-concurrent Forces — Second Method. —

This method will be described by reference to an example. Referring to Fig. 9, let AB, BC, CD, DE represent in magnitude and direction four forces whose lines of action are ab, bc, cd, de ; and let it be required to find their resultant. Draw the force polygon $ABCDE$, and from any point O in the force diagram draw lines OA, OB, OC, OD, OE . These lines may represent, in magnitude and direction, components into which the given forces may be resolved. Thus AB is equivalent to forces represented by AO and OB acting in any lines parallel to AO, OB , whose point of intersection falls upon ab ; BC is

equivalent to forces represented by BO , OC , acting in any lines parallel to BO , OC , which intersect on bc ; and so for each of the given forces. The four given forces may, therefore, be replaced by eight forces given in magnitude and direction by




Fig. 9

AO , OB , BO , OC , CO , OD , DO , OE , with proper lines of action. Now, it is possible to make the lines of action of the forces represented by OB and BO coincide; and the same is true of each pair of equal and opposite forces, OC , CO ; OD , DO . To accomplish this, let AO , OB act in lines ao , ob , intersecting at any assumed point of ab . Prolong ob to intersect bc , and take the point thus determined as the point of intersection of the lines of action of BO , OC ; these lines are then bo , oc . Similarly prolong oc to intersect cd , and let the point of intersection be taken as the point at which CD is resolved into CO and OD ; the lines of action of these forces are then co and od . In like manner choose do , oe , intersecting on de , as the lines of action of DO , OE . If this is done, the forces OB , BO will neutralize each other and may be omitted from the system; also the pairs OC , CO , and OD , DO . Hence, there remain only the two forces represented in magnitude and direction by AO , OE , and in lines of action by ao , oe . Their resultant is given in magnitude and direction by AE , and its line of action is ae , drawn parallel to AE through the

point of intersection of oa and oe ; and this is also the resultant of the given system.

By carefully following through this construction the student will be able to reduce it to a mechanical method, which can be readily applied to any system.

28. Funicular Polygon. — The polygon whose sides are oa , ob , oc , od , oe , is called a *funicular polygon** for the given forces.

Since the point at which the two components of AB are assumed to act may be taken anywhere on the line ab , there may be any number of funicular polygons with sides parallel to oa , ob , etc. Again, if O is taken at a different point, there may be drawn a new funicular polygon starting at any point of ab ; and by changing the starting point any number of funicular polygons may be drawn with sides parallel to the new directions of OA , OB , etc. Moreover, different force and funicular polygons may be obtained by changing the order in which the forces are taken.

It may be proved geometrically that for every possible funicular polygon drawn for the same system of forces, the last vertex, determined by the above method, will lie on the same line parallel to the closing side of the force polygon (as ae , Fig. 9). Such a proof is outside the scope of this work. The truth of the proposition may, however, be shown from the principles of statics. For if it were not true, it would be possible by the above method to find two or more forces, *having different lines of action*, which are equivalent to each other, because each is equivalent to the given system. But this is impossible.

29. Examples. — 1. Choose five forces, assigning the magnitude, direction, and line of action of each, and find their resultant by constructing the force and funicular polygons.

2. Draw a second funicular polygon, using the same point O in the force diagram.

* Also called equilibrium polygon.

3. Draw a third funicular polygon, choosing a new point O .
4. Solve the same problem, taking the forces in a different order.

30. **Definitions.** — The point O (Fig. 9) is called the *pole* of the force polygon. The lines drawn from the pole to the vertices of the force polygon may be called *rays*. The sides of the funicular polygon are sometimes called *strings*.

Each *ray* in the force diagram is parallel to a corresponding *string* in the space diagram. As a mechanical rule, it should be remembered that *the two rays drawn to the extremities of the line representing any force are respectively parallel to the two strings which intersect on the line of action of that force*.

The rays terminating at the extremities of any side of the force polygon represent in magnitude and direction two components that may replace the force represented by that side; while the corresponding strings represent the lines of action of these components. Thus (Fig. 9) the force represented by BC may be replaced by two forces represented by BO , OC , acting in the lines bo , oc .

The *pole distance* of any force is the perpendicular distance from the pole to the line representing that force in the force diagram. It may evidently be considered as representing the resolved part, perpendicular to the given force, of either of the components represented by the corresponding rays. Thus, OM (Fig. 9) is the pole distance of AB ; and OM represents the resolved part, perpendicular to AB , of either OA or OB . The student should notice particularly that the pole distance represents a *force magnitude* and not a length.

31. **Forces not Possessing a Single Resultant.** — It may happen that the first and last sides of the funicular polygon are parallel, so that the above construction fails to give the line of action of the resultant. This will be the case if the pole is chosen on the line AE (Fig. 9), because the first and last sides of the funicular polygon are respectively parallel to OA and

OE. The difficulty will, in this case, be avoided by taking the pole at some point not on the line *AE*. But in one particular case *OA* and *OE* will be parallel, *wherever the pole be taken*. By inspection of the force diagram it is seen that this can occur only when the point *E* coincides with *A*. In this case *AO* and *OE* represent equal and opposite forces; and unless their lines of action coincide, they cannot be combined into a simpler system. If their lines of action are coincident, the forces neutralize each other and the resultant is zero; if not, the system reduces to a *couple* (Art. 7). If the lines of action of *AO* and *OE* coincide, they may still be regarded as forming a couple, its arm being zero. Therefore,

If the force polygon for any system of forces closes, the resultant is a couple.

Now, it is evident that by shifting the starting point for the funicular polygon, the lines of action of *AO* and *OE* will be shifted; and by taking a new pole, their magnitude, or direction, or both, may be changed. Hence, there may be found any number of couples, each equivalent to the same system of forces, and therefore equivalent to each other. The relation between equivalent couples is discussed in Art. 52.

Example. — Assume five forces whose force polygon closes, the lines of action being taken at random. Draw two funicular polygons, using the same pole, and a third, using a different pole; thus reducing the given system to an equivalent couple in three different ways.

32. Resultant Force and Resultant Couple. — From the above discussion (Arts. 27 and 31), it is evident that any system of coplanar forces, acting on the same rigid body, is equivalent either to a single force or to a couple. In other words, *every system of coplanar forces possesses either a resultant force or a resultant couple.* (See Art. 9.)

33. Comparison of Methods. — Of the methods given in Arts. 26 and 27, for finding the resultant of a system of non-concur-

rent forces, the first is a special case of the second. For if the pole in Fig. 9 be chosen at the point A , and the first string be made to pass through the point of intersection of ab and bc , the construction becomes identical with that of Fig. 8. If the first method is employed, we are liable to meet the difficulty mentioned in Arts. 25 and 26, that some of the required points of intersection do not fall within convenient limits.

In the second method, since the pole may be chosen at pleasure, the rays may generally be caused to make convenient angles with the given forces. It will rarely be necessary that the rays intersect the corresponding force lines at acute angles, and will never be necessary that a ray shall be parallel to the force of which it represents a component. Hence the pole may generally be so chosen that all intersections shall fall within convenient limits. The difficulty above mentioned may therefore usually be avoided by using the method last described. This method is especially convenient in the case of parallel forces.

Example. — Choose six parallel forces and find their resultant by constructing the force and funicular polygons.

34. Closing of the Funicular Polygon. — Let the force polygon be drawn for any given forces, and let A and E be the initial and final points. Suppose the funicular polygon drawn, corresponding to any pole O . The given system is equivalent to two forces represented in magnitude and direction by AO , OE , their lines of action being the first and last sides of the funicular polygon. In general, these lines of action will not be parallel; but, as explained in Art. 31, it may happen that they *are* parallel. And if parallel, it may happen that they coincide. In this case, the funicular polygon is said to be *closed*.

§ 2. *Equilibrium of Non-concurrent Forces.*

35. Conditions of Equilibrium. — From the preceding articles it follows that, in order that a system of coplanar forces may be in equilibrium, the following conditions must be satisfied:

(a) *The force polygon must close*; otherwise the construction of Art. 27 will always lead to a resultant force of finite magnitude.

(b) *Every funicular polygon must close*; otherwise, by the method of Art. 27, the system can be reduced to two forces with different lines of action; the resultant cannot, therefore, be zero.

Conversely, *if the force polygon is closed and one funicular polygon also closes, the system is in equilibrium*. For, the closing of the force polygon shows that the system may be reduced to two equal and opposite forces (Art. 31); and the closing of the funicular polygon shows that these have the same line of action, and therefore balance each other.

It follows that if the force polygon and one funicular polygon are closed, all funicular polygons will close.

36. Auxiliary Conditions of Equilibrium. — If any system of forces in equilibrium be divided into two groups, the resultants of the two groups are equal and opposite and have the same line of action.

Particular case. — If three forces are in equilibrium, their lines of action must meet in a point, or be parallel. For, if the lines of action of two of the forces intersect, their resultant must act in a line passing through the point of intersection. But this resultant must be equal and opposite to the third force and have the same line of action.

37. General Method of Solving Problems in Equilibrium. — The principles of Art. 35 furnish a general method of solving, graphically, problems relating to the equilibrium of coplanar forces acting on a rigid body. The problems to be solved will always be of the following kind:

A body is in equilibrium under the action of forces, some of which are completely known, and others wholly or partly unknown. It is required to determine the unknown elements. The required elements may be either the magnitudes or the lines of action of the forces.

The general method of procedure is as follows: First, draw the force polygon and funicular polygon so far as possible from the given data; then complete them, subject to the condition that both polygons must close.

This general method will be illustrated by the solution of several problems of frequent occurrence. We may here meet with both determinate and indeterminate problems (Art. 20). In order that a problem may be determinate, the given data, together with the condition that the force polygon and funicular polygon are to close, must be just sufficient to fully determine these figures. There are many possible cases furnishing determinate problems. Some of these cannot readily be solved graphically. In the following articles are treated three important cases to which the general method above outlined is well adapted.

38. Problems in Equilibrium. I. — A rigid body is in equilibrium under the action of a system of parallel forces, all known except two, these being unknown in magnitude and direction, but having known lines of action. It is required to fully determine the unknown forces.

Let the known lines of action of five forces in equilibrium be ab , bc , cd , de , ea (Fig. 10), and let AB , BC , CD represent the known forces in magnitude and direction, while DE and EA are at first unknown. The force polygon, so far as it can be drawn from the given data, is the straight line $ABCD$. Choose a pole O and draw rays OA , OB , OC , OD . Parallel to these draw in the space diagram the strings oa , ob , oc , od , four successive sides of the funicular polygon. This much can be drawn from the data given. We must now complete the





FIG. 10



two polygons and cause both to close. In the funicular polygon, but one side remains to be drawn; and in the force polygon but one vertex remains unknown. If the forces are taken in the order AB, BC, CD, DE, EA , the unknown vertex in the force polygon is the one to be marked E ; the unknown side of the funicular polygon is oe , and is to be parallel to the line OE . But the string oe must pass through the intersection of od with de , and also through the intersection of oa with ae . Hence, since these intersections are both known, oe can be drawn at once as shown in the figure; and then OE can be drawn parallel to oe . This fixes the point E ; and DE and EA represent, in magnitude and direction, the required forces whose lines of action are de, ea .

39. Problems in Equilibrium. II. — A rigid body is in equilibrium under the action of a system of non-parallel forces, all known, except two; of these, the line of action of one and the point of application of the other are given. It is required to completely determine the unknown forces.

Let the system consist of five forces to be represented in the usual way; in magnitude and direction by lines marked AB, BC, CD, DE, EA ; and in lines of action by ab, bc, cd, de, ea . Of these lines let bc, cd, de, ea (Fig. 11), be given, and let L be a given point of ab . Also let BC, CD , and DE be known, while EA, AB are unknown. First, draw the force polygon as far as possible, giving B, C, D, E , four consecutive vertices of the force polygon. The side EA must be parallel to ea , but its length is unknown, hence the vertex A of the force polygon cannot be fixed. Next, draw the funicular polygon so




Fig. 11

far as possible from the given data. Choose the pole O , and draw the rays OB , OC , OD , OE . The remaining ray, OA , cannot yet be drawn. Now, in the funicular polygon, the sides ob , oc must intersect on bc ; oc and od must intersect on cd ; od and oe must intersect on de ; oe and oa must intersect on ea ; and oa and ob must intersect on ab . Since L is the only known point of the line ab , let this point be taken as the point of intersection of oa and ob . Now draw ob through L parallel to OB , and successively oc , od , oe , parallel to OC , OD , OE . We may now draw oa , joining L with the point in which oe intersects ea . This completes the funicular polygon. The force polygon can now be completed as follows: From O draw a line parallel to oa and from E a line in the known direction of EA ; their intersection determines A . This determines both EA and AB , and the force polygon is completely known. The line of action ab may now be drawn through L parallel to AB , and the forces are completely determined.

40. Problems in Equilibrium. III.—A rigid body is in equilibrium under the action of any number of forces, of which three are known only in line of action; the remaining forces being completely known. It is required to determine the unknown forces.

Let the given forces be six in number, their lines of action being represented by ab , bc , cd , de , ef , fa (Fig. 12), and let AB , BC , and CD be known, while the remaining three forces are unknown in magnitude and direction. The known data make it possible to draw at once three sides of the force polygon, namely, AB , BC , CD ; and the four rays OA , OB , OC , OD , from any assumed pole O . Also, four sides of the funicular polygon, oa , ob , oc , od , may be drawn at once. But oe and of are unknown; also DE , EF , and FA in the force polygon.

Since any side of the funicular polygon can be drawn through any chosen point, let the polygon be started by drawing oa .

through the intersection of ef and fa . We may then draw successively ob , oc , od . Now, of is unknown in direction; but it is to be drawn through the intersection of oa and fa , hence, whatever its direction, it intersects ef in the same point (since oa was drawn through the intersection of ef and fa). Hence, the two vertices of the funicular polygon falling on ef and fa coincide at the intersection of these two lines. We may there-




Fig. 12

fore draw oe through this point and also through the point already found by the intersection of od and de . Now draw a line from O parallel to oe , and from D a line parallel to de ; their intersection is E . Draw from E a line parallel to ef , and from A a line parallel to fa ; their intersection determines F . The force polygon is now completely drawn, and DE , EF , FA represent, in magnitude and direction, the required forces. The remaining ray OF and the corresponding string of may now be drawn, but are not needed.

The construction might have been made equally well by choosing the intersection of de and ef as the starting point, since two vertices of the funicular polygon may be made to coincide at that point. Or, the point of intersection of de and af might be chosen; but in that case, the order of the forces should be so changed as to make de and af consecutive. If this were done the figures should be relettered to agree with

the order in which the forces were taken. It may be noticed that the *direction* of the string first drawn may be chosen arbitrarily and the pole so taken as to correspond to the direction chosen. This is important in the treatment of the following special case.

Case of inaccessible points of intersection. — It may happen that the lines of action de , ef , and fa have no point of intersection within convenient limits. When this is the case, the method just given may still be applied, but involves the geometrical problem of drawing a line through an inaccessible point. For example, if ef and fa intersect beyond the limits of the drawing, as shown in Fig. 13, we may proceed as follows: Choose some point of ab and from it draw a line through the point of intersection of ef and fa . (This can be done by a method to be explained presently.) Let this line be oa . From the known point A of the force polygon draw a line parallel to




Fig. 13

oa and choose a pole upon it. Draw the rays OB , OC , OD ; then the corresponding strings in the order ob , oc , od . From the point in which od intersects de draw a line to the inaccessible point of intersection of ef and fa ; this will be oe . The force polygon can now be completed just as in the preceding case.

A line may be drawn through the inaccessible point of intersection of two given lines by the following method: Let AC ,

BD (Fig. 14), be the given lines, and let it be required to draw a line through their point of intersection from some point P . Draw PA intersecting AC and BD , and from C , any point of AC , draw a line CQ parallel to PA . From E , a point of BD , draw EA , EP ; also draw CF parallel to AE , and FQ parallel to EP . Then PQ is the line required. For, by the similar triangles, it is easily shown that




Fig. 14

$\frac{AB}{BP} = \frac{CG}{GQ}$; which proves that AC , BG , and PQ meet in a point.

Exception. — If the lines of action of the three unknown forces meet in a point (or are parallel), the problem is impossible of solution, unless it happens that the resultant of the known forces acts in a line through the point of intersection of those three lines of action (or parallel to them); in which case the problem is indeterminate. These cases will not be discussed here.

Remark. — In the problems treated in this and the two preceding articles, it will be noticed that the forces should be taken in such an order that those which are completely known are consecutive. Otherwise the number of unknown lines in the force and funicular polygons will be increased. [For another method of solving this problem, see Lévy's "Statique Graphique."]

41. **Examples.** — 1. A rigid beam AB rests horizontally upon supports at A and B , and sustains loads as follows: Its own weight of 100 lbs. acting at its middle point; a load of 50 lbs. at C ; a load of 60 lbs. at D ; and a load of 80 lbs. at E . The successive distances between A , C , D , E , and B are 4 ft., 6 ft., 7 ft., and 10 ft. Required the upward pressures on the beam at the supports.

2. A rigid beam AB is hinged at A , and rests horizontally with the end B upon a smooth horizontal surface. The beam sustains loads as in Example 1, and an additional force of 40 lbs. is applied at the middle point at an angle of 45° with the bar in an upward direction. Required the pressures upon the beam at A and B . [The pressure at A may have any direction, while the pressure at B must be vertically upward, *i.e.*, at right angles to the supporting surface. Hence, this is a particular case of Problem II.]

3. Let the end B of the bar rest against a smooth surface making an angle of 30° with the horizontal; the remaining data being as in Example 2.

4. A rigid bar 2 ft. long weighs 10 lbs., its center of gravity being 8 inches from one end. The bar rests inside a smooth hemispherical bowl of 15 inches radius. What weight must be applied at the middle point in order that the bar may rest when making an angle of 15° with the horizontal? Also, what are the reactions at the ends?

5. A uniform bar 20 inches long, weighing 10 lbs., rests with one end against a smooth vertical wall and the other end overhanging a smooth peg 10 inches from the wall. A weight P is suspended from the end so that the bar is in equilibrium when making an angle of 30° with the horizontal. Find P , and the pressures exerted on the bar by the wall and peg.

42. **Special Methods.** — Certain problems can be treated more simply by other methods than by the general method of constructing the force and funicular polygons. This is sometimes true of the following:

Problem. — A rigid body is held in equilibrium by four forces acting in known lines, only one being known in magnitude and direction. It is required to completely determine the three remaining forces. (See Fig. 15.)

Let the four forces have lines of action ab , bc , cd , da , and let

AB be drawn representing the magnitude and direction of the known force. Now the resultant of the forces whose lines of action are da and ab must act in a line passing through M , the point of intersection of these lines; and the resultant of the other two forces must act in a line passing through N , the point of intersection of bc and cd . But the two




Fig. 15

resultants must be equal and opposite and have the same line of action, else there could not be equilibrium. (Art. 36.) Hence, each must act in the line MN . Draw BD parallel to MN , and AD parallel to ad ; the point D being determined by their intersection. Then DA represents in magnitude and direction the force acting in da , and DB the resultant of DA and AB . But BD must represent the resultant of the two remaining forces; hence these two forces are represented by BC and CD drawn from B and D parallel respectively to bc and cd .

This problem is a special case of that treated in Art. 40. But the construction here given will in many cases be the simpler one.

Example.—A rigid body has the form of a square $ABCD$, the side AB being horizontal, and BC vertical. The weight of the body is 100 lbs., its center of gravity being at the intersection of the diagonals. It is held in equilibrium by three forces as follows: P_1 acting at C in the line AC ; P_2 acting at D in the line AD ; and P_3 applied at B and acting in the line joining B with the middle point of AD . Required to completely determine P_1 , P_2 , and P_3 .

§ 3. *Resolution into Non-concurrent Systems.*

43. To Replace a Force by Two Non-concurrent Forces. — This may be done in an infinite number of ways. The lines of action of the two components must intersect at a point on the line of action of the given force, and they must further satisfy the same conditions as concurrent forces. (Art. 21.)

44. To Replace a Force by More Than Two Non-concurrent Forces. — This may be done by first resolving the given force into two forces by the preceding article, and then resolving one or both of its components in the same way. This problem and that of Art. 43 are indeterminate. (See note, Art. 20.) To make such a problem determinate, something must be specified regarding the magnitudes and lines of action of the required components. We shall consider some of the particular cases which are of frequent use in the treatment of practical problems.

45. Resolution of a Force into Two Parallel Components. — Let it be required to resolve a force into two components having given lines of action parallel to its own.

If the given force be reversed in direction, it will form with the required components a system in equilibrium. The components may then be determined by the method of Art. 38.

Example. — Let the student solve two particular cases of this problem, taking the line of action of the given force (1) between those of the components, (2) outside those of the components.

46. Resolution of a Force into Three Components. — *Problem.* — To resolve a force into three components having known lines of action.

If the given force be reversed in direction, it will form, with the required forces, a system in equilibrium. Hence these forces may be determined by either of the two methods given

in Arts. 40 and 42. Or, the following reasoning may be employed, leading to the same construction as that of Art. 42.

Let AD (Fig. 16) represent the given force in magnitude and direction, and ad its line of action; the lines of action of the components being given as ab , bc , cd . Since the given force may be assumed to act at any point in the line ad , let its point of application be taken at M , the point of intersection of




Fig. 16

ad and cd . Resolve it into two components acting in the lines cd and MN , N being the point of intersection of ab and bc . These components are represented in magnitude and direction by AC , CD . Let AC , acting in the line MN (also marked ac), be resolved into components having lines of action ab , bc . These components are given in magnitude and direction by AB , BC , drawn parallel respectively to ab , bc . Hence, the given force, acting in ad , is equivalent to the three forces represented in magnitude and direction by AB , BC , CD , acting in the lines ab , bc , cd .

If the line of action of the given force does not intersect any one of the given lines ab , bc , cd , within the limits of the drawing, it may be replaced by two components; then each may be resolved in accordance with the above method, and the results combined. If the three lines ab , bc , cd , are all parallel to ad , or if the four lines intersect in a point, the problem is indeterminate. This is evident from the preceding articles, since, by methods already given, a part of AD can be replaced by two components acting in any two of the given lines, as ab , bc ; and the remaining part by two components acting in ab , cd ;

or in *bc*, *cd*. This construction evidently admits of infinite variation.

For another method of solving the above problem, see Clarke's "Graphic Statics," p. 16.

§ 4. *Moments of Forces and of Couples.*

47. Moment of a Force. — *Definition.* — The moment of a force with respect to a point is the product of the magnitude of the force into the perpendicular distance of its line of action from the given point. The moment of a force with respect to an axis perpendicular to the force is the product of the magnitude of the force by the perpendicular distance from the axis to the line of action of the force.

If the moment is taken with respect to a point, that point is called the *origin of moments*. The perpendicular distance from the origin, or axis, to the line of action of the force is called the *arm*.

Rotation tendency of a force. — The moment of a force measures its tendency to produce rotation about the origin, or axis. Thus, if a rigid body is fixed at a point, but free to turn about that point in a given plane, any force acting upon it in that plane will tend to cause it to rotate about the fixed point. The amount of this tendency will be proportional both to the magnitude of the force and to the distance of its line of action from the given point; that is, to the moment of the force with respect to the point, as above defined.

Rotation in any plane may have either of two opposite directions, which may be distinguished from each other by signs plus and minus. Rotation with the hands of a watch supposed placed face upward in the plane of the paper will be called negative, and the opposite kind positive. It would be equally legitimate to adopt the opposite convention, but the method here adopted agrees with the usage of the majority of writers.

The sign of the moment of a force is regarded as the same as that of the rotation it tends to produce about the origin.

Moment represented by the area of a triangle. — If a triangle be constructed having for its vertex the origin of moments, and for its base a length in the line of action of a force, numerically equal to its magnitude, then the moment of the force is numerically equal to double the area of the triangle. This follows at once from the definition of moment.

48. Moment of Resultant of Two Non-parallel Forces. — *Proposition.* — The moment of the resultant of two non-parallel forces with reference to a point in their plane is equal to the algebraic sum of their separate moments with reference to the same point.

In Fig. 17, let AB , BC , and AC represent in magnitude and direction two forces and their resultant; and let ab , bc , ac be their lines of action, intersecting in a point N . Choose any point M as the origin of moments. Lay off $NP = AB$; $NQ = BC$; and $NR = AC$. Then the moments of the three forces are respectively equal to double the areas of the triangles MNP , MNQ , MNR . These three triangles have a common side MN , which may be considered the base; hence their areas are proportional to their altitudes measured from that side. These altitudes are PP' , QQ' , RR' , perpendicular to MN . Now, if PP'' is parallel to MN , $P'R'$ is equal to PP' ; also RP'' equals QQ' (since they are homologous sides of the equal triangles NQQ' , PRP''). Hence $RR' = PP' + QQ'$, and therefore




Fig. 17

$$\text{Area } MNR = \text{area } MNP + \text{area } MNQ;$$

which proves the proposition.

If the origin of moments is so taken that the moments of AB and BC have opposite signs, the demonstration needs modification. The student should attempt the proof of this case for himself.

49. **Moment of a Couple.** — *Definition.* — The moment of a couple about any point in its plane taken as an origin is the algebraic sum of the moments of the two forces composing it with reference to the same origin.

Proposition. — The moment of a couple is the same for every origin in its plane, and is numerically equal to the product of the magnitude of either force into the arm of the couple. (Art. 7.)

The proof of this proposition can readily be supplied by the student.

50. **Moment of the Resultant of Any System.** — *Proposition.* — The algebraic sum of the moments of any given coplanar forces, with reference to any origin in their plane, is equal to the moment of their resultant force or resultant couple with reference to the same origin.

The construction employed in proving this proposition is similar to that used in Art. 27, which the student may profitably review at this point. Referring to Fig. 9, let the given forces be represented in magnitude and direction by AB, BC, CD, DE , and in lines of action by ab, bc, cd, de . Let the origin of moments be any point in the space diagram. As in Art. 27, replace AB by AO, OB , acting in lines ao, ob ; replace BC by BO, OC , acting in lines bo, oc ; replace CD by CO, OD , acting in lines co, od ; and replace DE by DO, OE , acting in lines do, oe . (For brevity, we refer to a force as AB , meaning "the force represented in magnitude and direction by AB .")

Now by Art. 48, we have, whatever the origin,

Moment of AB = moment of AO + moment of OB ;

" " BC = " " BO + " " OC ;

" " CD = " " CO + " " OD ;

" " DE = " " DO + " " OE .

Since the forces represented by BO and OB have the same line of action, their moments are numerically equal but have

opposite signs; and similar statements are true of CO and OC , and of DO and OD . Hence, the addition of the above four equations shows that the sum of the moments of AB , BC , CD , DE , is equal to the sum of the moments of AO and OE . Now the given system has either a resultant force or a resultant couple. In the first case the resultant of the system is the resultant of AO and OE , and its moment is equal to the algebraic sum of their moments, by Art. 48. In the second case (which occurs only when E coincides with A), the resultant couple is composed of AO and OE (which in this case are equal and opposite forces), and the moment of the couple is, by definition, equal to the algebraic sum of the moments of AO and OE . Hence, in either case, the proposition is true.

It should be noticed that the proof here given applies to systems of parallel forces, as well as to non-parallel systems. The proposition of Art. 48 could be extended to the case of any number of forces, by considering first the resultant of two forces, then combining this resultant with the third force, and so on; but the method would fail if, in the process, it became necessary to combine parallel forces. The method here adopted is not subject to this failure.

51. Condition of Equilibrium.—It follows from what has preceded, that *if a given system is in equilibrium, the algebraic sum of the moments must be zero, whatever the origin.* For, in case of equilibrium, AO and OE (Fig. 9) are equal and opposite and have the same line of action; hence, the sum of their moments (which is the same as the sum of the moments of the given forces) is equal to zero. Conversely, *If the algebraic sum of the moments is zero for every origin, the system must be in equilibrium.* For, if it is not, there is either a resultant force or a resultant couple. But the moment of a force is not zero for any origin not on its line of action; and the moment of a couple is not zero for any

origin. For a fuller discussion of the conditions of equilibrium, see Arts. 58 and 59.

52. Equivalent Couples. — Proposition. — If a system has for its resultant a couple, it is equivalent to any couple whose moment is equal to the sum of the moments of the forces of the system.

For, as already seen (Art. 31), when the resultant is a couple, the force polygon is closed. Let the initial and final points of the force polygon coincide at some point A , and let O be the pole. Then the forces of the resultant couple are represented in magnitude and direction by AO , OA . Since the position of O is arbitrary, the force AO (or OA) may be made anything whatever in magnitude and direction. Also the line of action of the force AO may be taken so as to pass through any chosen point. Hence, the resultant couple may have for one of its forces any force whatever in the plane of the given system; and the other force will have such a line of action that the moment of the couple will be equal to the sum of the moments of the given forces.

This reasoning is equally true if the given system is a couple. Hence, a couple is equivalent to any other couple having the same moment. In other words, *all couples whose moments are equal are equivalent*; and conversely, *all equivalent couples have equal moments*.

[NOTE. — The construction above discussed fails if all forces of the given system are parallel to the direction chosen for the forces of the resultant couple. For then the force polygon is a straight line, and if the pole is chosen in that line, the strings of the funicular polygon are parallel to the lines of action of the forces, and the polygon cannot be drawn. But in this case, the system may first be reduced to a couple whose forces have some other direction, and this couple may be reduced to one whose forces have the direction first chosen. Hence, the proposition stated holds in all cases.]

53. Moment of a System. — Definition. — The moment of a system of forces is the algebraic sum of the moments of the forces of the system.

54. **Moments of Equivalent Systems.** — *Proposition.* — The moments of any two equivalent systems of coplanar forces with respect to the same origin are equal.


This follows immediately from the preceding articles. For, if the two systems are equivalent, each is equivalent to the same resultant force or resultant couple, and the moments of the two systems are therefore each equal to the moment of this resultant and hence to each other.

§ 5. *Graphic Determination of Moments.*

55. **Proposition.** — If, through any point in the space diagram a line be drawn parallel to a given force, the distance intercepted upon it by the two strings corresponding to that force, multiplied by the pole distance of the force, is equal to the moment of the force with respect to the given point.

By the strings “corresponding to” a given force are meant the two strings which intersect at a point on its line of action.

Let AB (Fig. 18) represent the magnitude and direction of a force whose line of action is ab , and let M be the origin of moments. Let O be the pole, and $OK (=H)$ the pole distance of the given force. Draw the strings oa , ob , and through M draw a line parallel to ab , intersecting oa and ob in P and Q . Then it is to be proved that the moment of the given force with respect to M is equal to $H \times PQ$.



Let h equal the perpendicular distance of M from ab . Then the required moment is $AB \times h$. But since the similar triangles OAB and RPQ have bases AB , PQ , and altitudes H , h , respectively, it follows that

$$\frac{AB}{PQ} = \frac{H}{h}; \text{ hence, } AB \times h = PQ \times H,$$

which proves the proposition.

It should be noticed that PQ represents a *length*, while H represents a *force magnitude*. Hence, the moment of the given force with respect to M is equal to the moment of a force H with an arm PQ . [It may, in fact, be shown that the given force is equivalent to an equal force acting in the line PQ (whose moment about M is therefore zero), and a couple with forces of magnitude H , and arm PQ . For AB acting in ab is equivalent to AO and OB acting in ao and ob respectively. Also, AO acting in ao is equivalent to forces represented by AK and KO acting respectively in PQ and in a line through P at right angles to PQ ; and OB may be replaced by forces represented by OK and KB , the former acting in a line through Q perpendicular to PQ , and the latter in PQ . But AK and KB are equivalent to AB ; hence, the proposition is proved.]

56. Moment of the Resultant of Several Forces. — The moment of the resultant of any number of consecutive forces in the force and funicular polygons may be found by a method similar to that just described. Thus, let Fig. 19 represent the




Fig. 19

force polygon and the funicular polygon for six forces, and let it be required to find the moment of the resultant of the four forces represented in the force polygon by BC , CD , DE , and EF , with respect to any point M . The resultant of the four forces is represented by BF , and

acts in a line through the intersection of ob and of . Through M draw a line parallel to BF , intersecting ob and of in P and Q respectively. Then PQ multiplied by OK , the pole distance of BF , gives the required moment. This method does not apply to the determination of the moment of the resultant of several forces *not* consecutive in the force polygon.

57. Moments of Parallel Forces. — The method of Arts. 55 and 56 is especially useful when it is desired to find the moments of any or all of a system of parallel forces; since with such a system the pole distance is the same for all forces, and the moments are therefore proportional to the intercepts found by the above method.

Example. — Assume five parallel forces at random; choose an origin, and determine their separate moments, also the moment of their resultant, by the method of Arts. 55 and 56.

§ 6. *Summary of Conditions of Equilibrium.*

58. Graphical and Analytical Conditions of Equilibrium Compared. — It has been shown (Art. 35) that the conditions of equilibrium for a system of coplanar forces acting on a rigid body are two in number:

(I) The force polygon must close.

(II) Any funicular polygon must close.

The analytical conditions* are the following:

(1) The algebraic sum of the resolved parts of the forces in any direction must be zero.

(2) The algebraic sum of their moments for any origin must be zero.

The condition (1) is readily seen to be equivalent to (I). For if the sides of the force polygon be orthographically projected upon any line, their projections will represent in magnitude and direction the resolved parts of the several forces parallel to the line; and, if the force polygon is closed, the algebraic sum of these projections is zero, whatever the direction of the assumed line. (See Art. 22.) It may also be seen that condition (II) carries with it (2). For, if every funicular polygon closes, the system is equivalent to two equal and opposite forces having the same line of action (Arts. 31,

* See *Minchin's Statics*, Vol. I, p. 114.

35, and 50); and the sum of the moments of these two forces must be zero.

A further comparison may be made. The analytical condition (2) carries (1) with it; and similarly the graphical condition (II) carries with it the condition (I). That (2) includes (1) may be seen as follows: If the sum of the moments is zero for one origin M_1 , there can be no resultant couple, neither can there be a resultant force unless with a line of action passing through M_1 . If the sum of the moments is zero for two origins, M_1 and M_2 , the resultant force, if one exists, must act in the line M_1M_2 . If the sum of the moments is zero also for a third origin M_3 , not on the line M_1M_2 , there can be no resultant force. It follows at once that condition (1) must hold.

That (II) includes (I) may be shown as follows: Let A and E be the first and last points of the force polygon, and choose a pole O_1 . Then, if the funicular polygon closes, O_1A and O_1E are parallel. Choose a second pole O_2 , and, if the funicular polygon again closes, O_2A and O_2E are parallel. AE must then be parallel to O_1O_2 , unless A and E coincide. Now, choose a third pole O_3 , not on O_1O_2 ; if the funicular polygon for this pole closes, O_3A and O_3E must be parallel. But this is impossible unless A and E coincide; that is, unless condition (I) holds.

The last result may be reached in another way. With any pole O draw a funicular polygon and suppose it to close. The system is thus reduced to two forces acting in the same line oa . Hence, there is no resultant couple, and if there is a resultant force, its line of action is oa . With the same pole draw a second funicular polygon, the first side being $o'a'$, parallel to oa . If this polygon closes, there can be no resultant force, for if one existed it would act in the line $o'a'$; and there would thus be two resultant forces, acting in different lines oa and $o'a'$, which is impossible.

59. **Summary.** — It is now evident that the conditions necessary to *insure* equilibrium may be stated in several different ways, both analytically and graphically. To summarize :

A. Analytically : There will be equilibrium if either of the following conditions is satisfied :

(1) The sum of the moments is zero for each of three points not in the same line.

(2) The sum of the moments is zero for each of two points, and the sum of the resolved parts is zero for a line not perpendicular to the line joining those two points.

(3) The sum of the moments is zero for one point, and the sum of the resolved parts is zero for each of two directions.

B. Graphically : There will be equilibrium if either of these three conditions is satisfied :

(1) A funicular polygon closes for each of three poles not in the same line.

(2) Two funicular polygons close for the same pole.

(3) One funicular polygon closes and the force polygon closes.

CHAPTER III. INTERNAL FORCES AND STRESSES.

§ 1. *External and Internal Forces.*

60. **Definitions.**—It was stated in Art. 3 that every force acting upon any body is exerted by some other body. In what precedes, we have been concerned only with the effects produced by forces upon the bodies to which they are applied. It has therefore not been needful to consider the bodies which exert the forces. It is now necessary to consider forces in another aspect.

The forces applied to any particle of a body may be either *external* or *internal*.

An *external force* is one exerted upon the body in question by some other body.

An *internal force* is one exerted upon one portion of the body by another portion of the same body.

It is important to note, however, that the same force may be internal from one point of view, and external from another. Thus, if a given body be conceived as made up of two parts, *X* and *Y*, a force exerted *upon X by Y* is internal as regards the whole body, but external as regards the part *X*. Thus, let




Fig. 20

AB (Fig. 20) represent a bar, acted upon by two forces of equal magnitude applied at the ends paral-

lel to the length of the bar, in such a way as to tend to pull it apart. These two forces are exerted upon *AB* by some other

bodies not specified. If the whole bar be considered, the external forces acting upon it are simply the two forces named.

But suppose the body under consideration is AC , a portion of AB . The external forces acting upon this body are (1) a force at A , already mentioned, and (2) a force at C , exerted upon AC by CB . This latter force is *internal* to the bar AB , but external to AC .

61. Conditions of Equilibrium Apply to External Forces. — In applying the conditions of equilibrium deduced in previous articles, it must be remembered that only external forces are referred to. It is also important to notice that the principles apply to *any body* or *any portion of a body* in equilibrium; and the system of forces in every case must include all forces that are external to the body or portion of a body in question.

Thus, if the bar AB (Fig. 20) be in equilibrium under the action of two opposite forces P and Q , applied at A and B respectively, as shown in the figure, the principles of equilibrium may be applied either to the whole bar, or to any part of it, as AC .

(a) For the equilibrium of the whole bar AB , we must have $P=Q$, these being supposed the only *external* forces acting on the bar.

(b) For the equilibrium of AC , the force exerted upon AC by CB must be equal and opposite to P . This latter force is *external* to AC , though *internal* to the whole bar.

The method just illustrated is of frequent use in the investigation of engineering structures. It is often desired to determine the internal forces acting in the members of a structure, and the general method is this: Direct the attention to such a portion of the whole structure or body considered that the internal forces which it is desired to determine shall be external to the portion in question. (See Art. 67.)

§ 2. *External and Internal Stresses.*

62. **Newton's Third Law.** — Let X and Y be any two portions of matter ; then if X acts upon Y with a certain force, Y acts upon X with a force of equal magnitude in the opposite direction. This is the principle stated in Newton's third law of motion, — that “to every action there is an equal and contrary reaction.” It is justified by universal experience.

63. **Stress.** — *Definition.* — Two forces exerted by two portions of matter upon each other in such a way as to constitute an action and its reaction, make up a *stress*.

Illustrations. — The earth attracts the moon with a certain force, and the moon attracts the earth with an equal and opposite force. The two forces constitute a stress.

Two electrified bodies attract (or repel) each other with equal and opposite forces. These two forces constitute a stress.

Any two bodies in contact exert upon each other equal and opposite pressures (forces), constituting a stress.

By the *magnitude of a stress* is meant the magnitude of either of its forces.

64. **External and Internal Stresses.** — It has been seen that two portions of matter are concerned in every stress. Now the two portions may be regarded either as separate bodies, or as parts of a body or system of bodies which include both.

A stress acting between two parts of the same body (or system of bodies) is an *internal stress* as regards that body or system.

A stress acting between two distinct bodies is an *external stress* as regards either body.

It is important to notice that the same stress may be internal from one point of view, and external from another. Thus, if a given body be considered as made up of two parts X and Y , a stress exerted between X and Y is *internal* to the whole body, but external to either X or Y .

Illustration. — Consider a body AB (Fig. 21) resting upon a second body Y , and supporting another body X , as shown. If the weight of the body AB be disregarded, the forces acting upon it are (1) the downward pressure (say P) exerted by X at the surface A , and the upward pressure (say Q) exerted by Y at B ; these forces being equal and opposite, since the body is in equilibrium. Now the body X is acted upon by AB with a force equal and opposite to P , and these




Fig. 21

two forces constitute a stress which is external to AB . There is also an external stress exerted between AB and Y at B . But let AB be considered as made up of two parts, AC and CB . Then (Art. 60) CB exerts upon AC a force upward, and AC exerts upon CB a force downward. These two forces are an action and its reaction, and constitute a stress which is internal to the body AB . This same stress is, however, external to either AC or CB . An equivalent stress evidently exists at every section between A and B . (When we refer to the force acting upon CB at C , we mean the *resultant* of all forces exerted upon the particles of CB by the particles of AC . This resultant is made up of very many forces acting between the particles. Also the stress at C means the stress made up of the two resultants of the forces exerted by AC and CB upon each other.)

65. Three Kinds of Internal Stress. — It is evident that the internal stress at C in the body AB (Fig. 20) depends upon the external forces applied to the body. If the forces at A and B cease to act, the forces exerted by AC and CB upon each other become zero. If the forces at A and B are reversed in direction, so also are those at C . (As a matter of fact, the particles of AC exert forces upon those of CB , even if the external forces do not act. But if the external forces applied to CB are balanced, the resultant of the forces exerted on CB by AC is zero.)

The nature of the internal stress at any point in a body is thus seen to depend upon the external forces applied to the body.

Now, if we consider two adjacent portions of a body (as the parts X and Y , Fig. 22) separated by a plane surface, the



Fig. 22

external forces may have either of three tendencies: (1) to pull X and Y apart in a direction perpendicular to the plane of separation; (2) to push them together

in a similar direction; (3) to slide each over the other along the plane of separation. Corresponding to these three tendencies, the stress between X and Y may be of either of three kinds: *tensile*, *compressive*, or *shearing*.

A *tensile stress* is such as comes into action to resist a tendency of the two portions of the body to be pulled apart in the direction of the normal to their surface of separation.

A *compressive stress* is such as comes into action to resist a tendency of X and Y to move toward each other along the normal to the surface.

A *shearing stress* is such as acts to resist a tendency of X and Y to slide over each other along the surface between them.

In case of a tensile stress, the force exerted by X upon Y has the direction from Y toward X ; and the force exerted by Y upon X has the direction from X toward Y .

In case of a compressive stress, the force exerted by X upon Y has the direction from X toward Y ; and the force exerted by Y upon X has the direction from Y toward X .

In the case of a shearing stress, the force exerted by X upon Y may have any direction in the plane of separation; the force exerted by Y upon X having the opposite direction.

If X and Y are separate bodies, instead of parts of one body, a similar classification may be made of the kinds of stress between them; but with these we shall have no occasion to deal. The terms *tensile stress*, *compressive stress*, and *shearing stress* (or *tension*, *compression*, and *shear*) are usually applied only to internal stresses.


66. **Strain.** — In what has preceded, the bodies dealt with have been regarded as *rigid*; that is, the relative positions of the particles of any body have been regarded as remaining unchanged. But, as remarked heretofore, no known body is perfectly rigid. If no external forces act upon a body, its particles take certain positions relative to each other, and the body has what is called its *natural* shape and size. If external forces are applied, the shape and size will generally be changed; the body is then said to be in a *state of strain*. The deformation produced by any system of applied forces is called the *strain* due to those forces. The nature of this strain in any case depends upon the way in which the forces are applied. It is unnecessary to treat this subject further at this point, since we shall at present be concerned only with problems in the treatment of which it will be sufficiently correct to regard the bodies as rigid.

[NOTE. — There is a lack of uniformity among writers in regard to the meanings attached to the words *stress* and *strain*. It may, therefore, be well to explain again at this point the way in which these words are used in the following pages. The word *stress* should be employed only in the sense above defined, as consisting of two equal and opposite forces constituting an action and its reaction. The two forces are exerted respectively by two bodies or portions of matter upon each other. An *internal stress* is a stress between two parts of the same body. An *internal force* is one of the forces of an internal stress. It is intended in what follows to use the words "internal stress" (or simply "stress") only when *both* the constituent forces are referred to; and when only one of the forces is meant, to use the words "internal force" (or simply "force"). It will be noticed, therefore, that in the following pages the words "*force* in a bar" are frequently used where many writers would say "*stress*." This departure from the usage of many high authorities seems justified by the following considerations: (1) It agrees with the usage which is being adopted by the highest authorities in pure mechanics. (2) It is desirable that the nomenclature of technical mechanics shall agree with that of pure mechanics, so far as they deal with the same conceptions. The definition of strain above given is in conformity with the usage of the majority of the more recent text-books. But it is not rare to find in technical literature the word *strain* used in the sense of *internal stress* as above defined. Such use of the word should be avoided.]

§ 3. *Determination of Internal Stresses.*

67. **General Method.** — The stresses exerted between the parts of a body may or may not be completely determinate by means of the principles already deduced. But in all cases these principles suffice for their partial determination. The general method employed is always the same, and will now be illustrated. As heretofore we deal only with complanar forces.

Let XY (Fig. 23) represent a body in equilibrium under the action of any known external forces as shown. Now conceive the body to be divided into two parts as X and Y , separated by any surface. The particles of X near the surface exert upon those of Y certain forces, and are in return acted



upon by forces exerted by the particles of Y . These forces are internal as regards the whole body. In order to determine them so far as possible, we proceed

as follows: Let the resultant of all the forces exerted by Y upon X be called T ; then T is either a single force or a couple. Now apply the conditions of equilibrium to the body X . The external forces acting on X are P_1 , P_2 , P_3 , and T . Since P_1 , P_2 , and P_3 are supposed known, T can be determined. In fact, T is equal and opposite to the resultant of P_1 , P_2 , and P_3 .

So much can always be determined. But T is the resultant of a great number of forces acting on the various particles of X ; and these separate forces cannot in general be determined by methods which lie within the scope of this work.

The general principle just illustrated may be stated as follows:

If a body in equilibrium under any external forces be conceived as made up of two parts X and Y , then the internal forces exerted by X upon Y , together with the external forces acting on Y , form a system in equilibrium.

As an immediate consequence, we may state that *the resultant of the forces exerted by X upon Y is equivalent to the resultant of the external forces acting on X; and is equal and opposite to the resultant of the external forces acting upon Y.*

Example.— Assume a bar of known dimensions, and the magnitudes, directions, and points of application of five forces acting on it. Then (1) determine a sixth force which will produce equilibrium; and (2) assume the bar divided into two parts and find the resultant of the forces exerted by each part on the other.

68. **Jointed Frame.**— In certain ideal cases (corresponding more or less closely to actual cases), the internal forces may be more completely determined. The most important of these cases is that which will be now considered. Conceive a rigid body made up of straight rigid bars hinged together at the ends. Assume the following conditions:

(1) The hinges are without friction.

(2) All external forces acting on the body are applied at points where the bars are joined together.

The meaning of these conditions will be seen by reference to Fig. 24. The three bars *X*, *Y*, and *Z* are connected by a "pin joint," the end of each bar having a hole or "eye" into which is fitted a pin. (Of course the three bars cannot be in the same plane, but they may be nearly so, and will be so assumed in what follows.) Condition (1) is satisfied if the pin is assumed frictionless. The effect of this is that the force exerted upon the pin by any bar (and the equal and opposite reaction exerted upon the bar by the pin) acts in the normal to the surfaces of these bodies at the point of contact; and, therefore, through the centers of the pin and the hole. Condition (2) means that any external force (that is, external to the




Fig. 24

whole body) applied to any bar is applied to the end and in a line through the center of the pin.

With the connection as shown, the bars do not exert forces upon each other directly. But each exerts a force upon the pin, and any force exerted by Y or Z upon the pin causes an equal force to be exerted upon X . (This is seen by applying the condition of equilibrium to the pin.) Hence, in considering the forces acting upon any bar as X , we may disregard the pin and assume that each of the other bars acts directly upon X . By what has been said, all such forces exerted upon X by the other bars meeting it at the joint may be regarded as acting at the same point — the center of the pin. We therefore treat the bars as mere "material lines," and regard all forces exerted on any bar (whether by the other bars or by outside bodies) as applied at the ends of this "material line."

Since, with these assumptions, all forces acting on any bar MN (Fig. 25) are applied either at M or N , the forces applied at M must balance those applied at N . The resultants of the two sets must therefore be equal and opposite, and have the same line of action — namely MN . Further, it follows that the stress in the bar, acting across any plane perpendicular to its length, is a direct tension or compression.

69. Internal Stresses in a Jointed Frame. — Let Fig. 25 represent a jointed frame such as above described, in equilibrium




Fig. 25

under any known external forces. Let us apply the general method of Art. 67 to this case. Divide the body into two parts, X and Y , by the surface AB as shown. Now apply the conditions of equilibrium to the body X . The system of

forces acting upon this body consists of P_1 , P_2 , P_6 , and the forces exerted by Y upon X in the three members cut by the surface AB . By Art. 68 the lines of action of these forces are known,

being coincident with the axes of the members cut. Hence, the system in equilibrium consists of six forces, three completely known, and three known only in lines of action. The determination of the unknown forces in magnitude and direction is then a case under the general problem discussed in Art. 40.

Nature of the stresses.—As soon as the direction of the force acting upon X in any one of the members cut is known, the nature of the stress in that member (whether tension or compression) is known. For a force *toward* X denotes compression; while a force *away from* X denotes tension. (Art. 65.)

If a section can be taken cutting only two members, the forces in these may be found by the force polygon alone. The same is true, if any number of members are cut, but the stresses in all but two are known.

The methods described in the last three articles will find frequent application in the chapters on roof and bridge trusses, Part II.

Example.—Assume a jointed frame similar to the one shown in Fig. 25, and let external forces act at all the joints. Then (1) assume all but three of the forces known in magnitude and direction and determine the remaining three so as to produce equilibrium. (2) Take a section cutting three members and determine the stresses in those members.

70. Indeterminate Cases.—If, in dividing the frame, more than three members are cut, the number of unknown forces is too great to admit of the determination of their magnitudes. In such a case, it may happen that a section elsewhere through the body will cut but three members; and that after the determination of the stresses in these three, another section can be taken cutting but three members whose stresses are unknown. So long as this can be continued, the determination of the

internal stresses can proceed. Thus, in Fig. 26, if a section be first taken at AB , there are four unknown forces to be determined. But, if the section $A'B'$ be first taken, the stresses in the three members cut may be determined; after which the section AB will introduce but three unknown stresses.




Fig. 26

There may, however, be cases in which the stresses cannot all be determined by any method. With such

actually indeterminate cases we shall not usually have to deal. It should be noticed, also, that even when only three members are cut, the problem is indeterminate *if these three intersect in a point*. As in the case just discussed, this indeterminateness may be either actual or only apparent; in the latter case it may be treated as above indicated.

No attempt is here made to develop all methods that are applicable or useful in the determination of stresses in jointed frames. Some of these are best explained in connection with the actual problems giving rise to them. We have sought here only to explain and clearly illustrate *general principles*.

71. **Funicular Polygon Considered as Jointed Frame.** — Let ab, bc, cd, da (Fig. 27) be the lines of action of four forces in equilibrium, the force polygon being $ABCD$. Choosing a





Fig. 27



pole, draw any funicular polygon, as the one shown. Now let the body upon which the forces act be replaced by a jointed

frame whose bars coincide with the sides of the funicular polygon. If at the joints of this frame the given forces be applied, the frame will be in equilibrium; and each bar will sustain a tension or compression whose magnitude is represented by the corresponding ray of the force diagram.

To prove this, we apply the "general method" of Art. 67. Consider any joint (as the intersection of oa and ob), and let the frame be divided by a plane cutting these two members. Then the portion of the frame about the joint is acted upon by three forces: AB , acting in the line ab , and forces acting in the bars cut, their lines of action being oa , ob . If the bar oa sustains a compression and ob a tension, their magnitudes being represented by OA and BO respectively, the portion of the frame about the joint will be in equilibrium. Hence, the tendency of the force AB is to produce the stresses mentioned in the bars oa , ob . In the same way it may be shown that the tendency of the force BC is to produce in ob and oc tensile stresses of magnitudes OB and CO , respectively. Applying the same reasoning to each joint, it is seen that every part of the frame will be in equilibrium if the bars sustain stresses as follows: The bar oa must sustain a compression OA ; ob a tension OB ; oc a tension OC ; and od a compression OD . Hence, if the bars are able to sustain these stresses, the frame will be in equilibrium.

If the stress in any member of the frame is a tension, that member may be replaced by a flexible string. This is the origin of the name string as applied to the sides of the funicular polygon. This name is retained for convenience, but, as just shown, it is not always appropriate.

72. Outline of Subject.—The foregoing pages, embracing Part I, have been devoted to a development of the principles of pure statics. We pass next to the application of these principles to special classes of problems.

Part II treats of the determination of internal stresses in

engineering structures. Only "simple" structures are considered, — that is, those whose discussion does not involve the theory of elasticity. The structures considered include roof trusses, beams, and bridge trusses.

Part III develops the graphic methods of determining centroids (centers of gravity) and moments of inertia of plane areas, including a short discussion of "inertia-curves."

PART II.

STRESSES IN SIMPLE STRUCTURES.



CHAPTER IV. INTRODUCTORY.

§ 1. *Outline of Principles and Methods.*

73. **The Problem of Design.** — When any structure is subjected to the action of external forces, there are brought into action certain *internal stresses* in the several parts of the structure. The nature and magnitudes of these stresses depend upon the external forces acting (Art. 65). In designing the structure, each part must be so proportioned that the stresses induced in it will not become such as to break or injure the material.

To determine these internal stresses, when the external forces are wholly or partly given, is the problem of design, so far as it will be here treated.

74. **External Forces.** — The external forces acting on a structure must generally be completely known before the internal stresses can be determined. These external forces are usually only partly given, and the first thing necessary is to determine them fully.

The external forces include (1) the *loads* which the structure is built to sustain, and (2) the *reactions* exerted by other bodies upon the structure at the points where it is supported. The former are known or assumed at the outset and the latter are to be determined.

75. **Two Classes of Structures.** — Structures may be divided into two classes, according as they may or may not be treated as rigid bodies in determining the reactions. This may be illustrated as follows:

Let a bar AB (Fig. 28) be supported in a horizontal position at two points A and B , the supports being smooth so that the




Fig. 28

pressures on the bar at A and B are vertical.

Let a known load P be applied to the beam at a given point, and let it be required to determine the reactions at A and B .

This is a determinate problem; for there are three parallel forces in equilibrium, two being known only in line of action. This problem was solved in Art. 38.

But let AC (Fig. 29) be a rigid bar supported at three points, A , B , and C , the reactions at those points being vertical.




Fig. 29

Let any known loads be applied at given points, and let it be required to determine the three reactions.

This problem is indeterminate; for any number of sets of values of the three reactions may be found, which, with the applied loads, would produce equilibrium if acting on a rigid body. (See Art. 40.)

Since, however, an actual bar is not a perfectly rigid body, such a problem as the one just stated is, in reality, determinate. But it cannot be solved without making use of the elastic properties of the material of which the body is composed.

The two classes of problems are, therefore, the following: (1) those in which the reactions can be determined by treating the structure as a rigid body, and (2) those in which the determination of the reactions involves the theory of elasticity. We shall at present deal only with the former class of prob-

lems. Structures coming under this class will be called *simple* structures.

76. Truss. — A truss is a structure made up of straight bars with ends joined together in such a manner that the whole acts as a single body. The ends of the bars are, in practice, joined in various ways; but in determining the internal stresses, the connections are assumed to be such that no resistance is offered by a joint to the rotation of any member about it. Such a structure to be indeformible must be made up of triangular elements; for more than three bars hinged together in the form of a polygon cannot constitute a rigid whole. If the external forces are applied to the truss only at the points where the bars are joined, the internal stress at any section of a member will be a simple tension or compression, directed parallel to the length of the bar. (See Art. 68.)

The most important classes of trusses are roof trusses and bridge trusses. The methods used in discussing these classes are, of course, applicable to any framed structures under similar conditions.

77. Loads on a Truss. — The loads sustained by a truss may be either *fixed* or *moving*. A fixed (or *dead*) load is one whose point of application and direction remain constant. A moving (or *live*) load is one whose point of application passes through a series of positions. Fixed loads may be either *permanent* or *temporary*.

The loads on a roof truss are usually all fixed, but are of various kinds, viz., the weight of the truss itself and of the roof covering, which is a permanent load; the weight of snow lodging on the roof, and the pressure of wind, both of which are temporary loads.

A bridge truss supports both fixed and moving loads. The former include the weight of the truss itself, of the roadway, of all lateral and auxiliary bracing (permanent loads); and of snow (a temporary load). The latter consist of moving trains

in the case of railway bridges, and of teams or crowds of animals or people in the case of highway bridges.

78. Combination of Stresses Due to Different Causes. — When a truss is subject to a variety of external loads, it is often convenient to consider the effect of a part of them separately. If tensile and compressive stresses are distinguished by signs plus and minus, the stress in any member due to the combined action of any number of loads is equal to the algebraic sum of the stresses due to the loads acting separately.

A proof of this proposition might be given; but it may be accepted as sufficiently evident without formal demonstration.

79. Beams. — Another class of bodies to be treated is included under the name *beam*.

A beam may be defined as a bar (usually straight) resting on supports and carrying loads. The loads and reactions are commonly applied in a direction transverse to the length of the bar; but this is not necessarily the case.

The internal stresses in any section of a beam are less simple than those in the bars of an ideal jointed frame such as a truss is assumed to be. A discussion of beams is given in Chap. VI.

80. Summary of Principles Needed. — It will be well to summarize at this point the main principles and methods which will be employed in the discussion of the problems that follow.

The general problem presented by any structure consists of two parts: (*a*) the determination of the unknown external forces (or reactions) and (*b*) the determination of the internal stresses.

(*a*) In the case of simple structures the unknown reactions are usually two in number, and the cases most commonly presented are the following:

1st. — Their lines of action are known and parallel.

2nd. — The line of action of one and the point of application of the other are known.

Since all the external forces form a system in equilibrium, these two cases fall under the general problems discussed in Arts. 38 and 39.

(b) In the case of a jointed frame or truss, the lines of action of all internal forces are known, since they coincide with the axes of the truss members. (Art. 68.) In determining their magnitudes we may have to deal with the following problems in equilibrium:

1st. — The system in equilibrium may be completely known, except the magnitudes of two forces.

2nd. — The magnitudes of three forces may be unknown.

The first case may be solved by simply making the force polygon close. (See Art. 35.)

The second case may be solved by the method of Art. 40, which consists in making the force and funicular polygons close; or by the method of Art. 42; or by the principle of moments (Art. 51).

The student should be thoroughly familiar with the problems and principles here referred to. In the following chapters we proceed to their application.

81. Division of the Subject. — The subject of the design of structures, so far as here dealt with, will be treated in three divisions. The first relates to framed structures sustaining only stationary loads; the second to beams sustaining both fixed and moving loads; the third to framed structures sustaining both fixed and moving loads. Among structures of the first class, the most important are roof trusses; hence, these are chiefly referred to in the next chapter. For a similar reason, the chapter devoted to the third class of structures refers principally to bridge trusses. The chapter on beams precedes that on bridge trusses, for the reason that the methods used in dealing with a beam under moving loads form a useful introduction to those employed in treating certain classes of truss problems.

CHAPTER V. ROOF TRUSSES. — FRAMED STRUCTURES SUSTAINING STATIONARY LOADS.

§ 1. *Loads on Roof Trusses.*

82. Weights of Trusses. — Among the loads to be sustained by a roof truss is the weight of the truss itself. Before the structure is designed, its weight is unknown. But, since it is necessary to know the weight in order that the design may be correctly made, the method of procedure must be as follows :

Make a preliminary estimate of the weight, basing it upon knowledge of similar structures ; or, in the absence of such knowledge, upon the best judgment available. Then design the various truss members, compute their weight, and compare the actual weight of the truss with the assumed weight. If the difference is so great as to materially affect the design of the truss members, a new estimate of weight must be made, and the computations repeated or revised. No more than one or two such trials will usually be needed.

As a guide in making the preliminary estimate of weight, the following formulas may be used. They are taken from Meriman's "Roofs and Bridges," being intended to represent approximately the data for actual structures, as compiled by Ricker in his "Construction of Trussed Roofs."

Let l = span in feet ; a = distance between adjacent trusses in feet ; W = total weight of one truss in pounds. Then for wooden trusses

$$W = \frac{1}{2} al \left(1 + \frac{1}{10} l \right) ;$$

and for wrought iron trusses

$$W = \frac{3}{4} al \left(1 + \frac{1}{10} l \right).$$

83. Weight of Roof Covering. — The weight of roof covering can be correctly estimated beforehand from the known weights of the materials. The following data may be employed, in the absence of information as to the specific material to be used. (See Merriman's "Roofs and Bridges," p. 4.) The numbers denote the weight in pounds per square foot of roof surface.

Shingling : Tin, 1 lb. ; wooden shingles, 2 to 3 lbs. ; iron, 1 to 3 lbs. ; slate, 10 lbs. ; tiles, 12 to 25 lbs.

Sheathing : Boards 1 in. thick, 3 to 5 lbs.

Rafters : 1.5 to 3 lbs.

Purlins : Wood, 1 to 3 lbs. ; iron, 2 to 4 lbs.

Total roof covering, from 5 to 35 lbs. per square foot of roof surface.

84. Snow Loads. — The weight of snow that may have to be borne will differ in different localities. For different sections of the United States the following may be used as the maximum snow loads likely to come upon roofs.

Maximum for northern United States, 30 lbs. per square foot of horizontal area covered.

For latitude of New York or Chicago, 20 lbs. per square foot.

For central latitudes in the United States, 10 lbs. per square foot.

The above weights are given in Merriman's "Roofs and Bridges." They are in excess of those used by some Bridge and Roof companies.

85. Wind Pressure Loads. — The intensity of wind pressure against any surface depends upon two elements : (a) the velocity of the wind, and (b) the angle between the surface and the direction of the wind.

Theory indicates that the intensity of wind pressure upon a surface perpendicular to the direction of the wind should be proportional to the square of the velocity of the wind relative to the surface. As an approximate law this is borne out by experiment. If p denotes the pressure per unit area, and v the velocity of the wind, the law is expressed by the formula

$p = kv^2$. Here k is proportional to the density of air. Its numerical value may be taken as 0.0024, if the units of force, length, and time are the pound, foot, and second respectively.

If the wind strikes a surface obliquely, experiment shows that the resulting pressure has a direction practically normal to the surface. The tangential component is inappreciable, owing to the very slight friction between air and any fairly smooth surface. The intensity of the normal pressure depends upon the angle at which the wind meets the surface.

For a given velocity of wind let p_a denote the normal pressure per unit area, when the direction of wind makes an angle a with the surface, and p_n the pressure per unit area due to the same wind striking a surface perpendicularly. Then the following formula * has been given :

$$p_a = \frac{2 \sin a}{1 + \sin^2 a} p_n.$$

It will rarely be necessary to use values of p_n greater than 50 lbs. per square foot. The following table gives values of the coefficient of p_n in the above formula for different values of a . The value of p_n may be taken as from 40 to 50 lbs. per square foot.

a	$\frac{2 \sin a}{1 + \sin^2 a}$	a	$\frac{2 \sin a}{1 + \sin^2 a}$
0°	0.00	50°	0.97
10°	0.34	60°	0.99
20°	0.61	70°	1.00
30°	0.80	80°	1.00
40°	0.91	90°	1.00

* This formula is given by various writers. It is cited by Langley ("Experiments in Aerodynamics," p. 24), who attributes it to Duchemin. Professor Langley's elaborate experiments show so close an agreement with the formula that it may be used without hesitation in estimating the pressure on roofs.

§ 2. *Roof Truss with Vertical Loads.*

86. Notation. — The method of determining internal stresses in the case of vertical loading will be explained by reference to the form of truss shown in Fig. 30. The method will be seen to be independent of the particular form of the truss.

For designating the truss members and the lines of action of external forces a notation will be employed similar to that used in previous chapters. Let each of the areas in the truss diagram be marked with a letter or other symbol as shown in Fig. 30; then the truss member or force-line separating any two areas may be designated by the two symbols belonging to those areas. Thus, the lines of action of the external forces are *ab*, *bc*, *cd*, etc., and the truss members are *gh*, *hb*, *hi*, etc. It is to be noticed that the lines representing the truss members represent also the lines of action of forces, — namely, the internal forces in the members. The joint, or point at which several members meet, may be designated by naming all the surrounding letters. Thus, *bcih*, *hijg* are two such points.

87. Loads and Reactions. — The loads now considered are assumed to be applied in a vertical direction, and to act at the upper joints of the truss. This assumption as to the points of application may in some cases represent very nearly the facts; in other cases the loads will, in reality, be applied partly at intermediate points on the truss members. If the latter is the case, the load borne upon any member is assumed to be divided between the two joints at its ends. In this case the member will be subject not only to direct tension or compression, but to bending. With the latter we are not here concerned, although it must always be considered in designing the member.

The ends of the truss are supposed to be supported on horizontal surfaces, and the reaction at each point of support is assumed to have a vertical direction.

If the loading is symmetrical with reference to a vertical line

through the middle of the truss, it is evident that each reaction is equal to half the total load. If the loading is not symmetrical, the reactions cannot be determined so simply. They may, however, be readily computed by either graphic or algebraic methods. Graphically, the problem is identical with that solved in Art. 38. The truss is treated as a rigid body, the external forces acting upon it being the loads and reactions, which form a system of parallel forces in equilibrium. Two of these forces (the reactions) are unknown in magnitude, but known in line of action. The construction for determining their magnitudes is as follows :

Draw the force polygon $ABCDEF$ for the five loads ; choose a pole O , draw rays OA, OB, OC , etc., and draw the funicular polygon as shown in Fig. 30. The two polygons are to be completed by including the reactions FG, GA , and both polygons must close. We may draw first og , the closing line of the funicular polygon, and then the ray OG parallel to it, thus determining the point G in the force polygon. The reactions are now shown in magnitude and direction by FG and GA .

88. Determination of Internal Stresses. — When the external forces are all known, the internal stresses may be found very readily. The only principle needed is, that for any system of forces in equilibrium, the force polygon must close. The construction will now be explained.

Considering any joint of the truss (Fig. 30) as $ghijg$, fix the attention upon the portion of the truss bounded by the broken line in the figure. This portion is a body in equilibrium under the action of four forces whose lines of action coincide with the axes of the four bars gh, hi, ij, jg , respectively. These forces are *internal* as regards the truss as a whole, but *external* to the part in question ; each force being one of the pair constituting the internal stress at any point of the bar. Such a force acts *from* the joint if the stress in the bar is a tension ; *toward* it if the stress is a compression. (Art. 69.)

Since these four forces form a system in equilibrium, their force polygon must close. This condition will enable us to fully determine the magnitudes of the forces, provided all but two are known, since the polygon can then be constructed as in Art. 18.





Fig. 30



We cannot, however, begin with the joint just considered, since at first the four forces are all unknown in magnitude.

If, however, we start with the joint *gabli*, the polygon of forces can be at once drawn. For, reasoning as above, it is seen that the portion of the truss immediately surrounding this joint is in equilibrium under the action of four forces: the reaction in the line *ga*, the load in the line *ab*, and the internal forces in the lines *bh*, *hg*. Of these forces, two (the reaction and the load) are completely known; and it is necessary only to draw a polygon of which two sides represent the known forces and the other two sides are made parallel to the members *bh*, *hg*. Such a polygon is shown in Fig. 30; and *BH* and *HG* represent in magnitude and direction the forces whose lines of action are *bh*, *hg*.

Evidently, BH and HG represent also the magnitudes (Art. 63) of the internal stresses in the two members bh and hg . The nature of these stresses may be found as follows: Since the four forces represented in the polygon $GABHG$ are in equilibrium, and since GA , AB are the directions of two of them, the directions of the other two must be BH , HG . Hence, BH acts *toward* the joint and HG *from* it. This shows that the stress in bh is a *compression*, while that in hg is a *tension*.

Passing now to the joint $bcihb$, it is seen that of the four forces whose lines of action meet there, two are fully known, namely, the load BC acting vertically downward and the internal force in hb acting toward the joint (since the stress is compressive), while the remaining two (viz., the internal forces in ci and ih) are unknown in magnitude and direction. Since, however, the unknown forces are but two in number, the force polygon can be completely drawn, and is represented by the quadrilateral $HBCIH$. The directions of the forces are found as in the preceding case, and it is seen that the bars ci and ih both sustain compressive stresses.

The process may be continued by passing to the remaining joints in succession, in such order that at each there remain to be determined not more than two forces. The complete construction is shown in Fig. 30.

It is evident that the loads AB and EF might have been omitted without changing the stresses in any of the truss members. For their omission would leave as the complete force polygon for external forces $BCDEGB$, and the two reactions would be GB and EG ; but the force diagram would be otherwise unchanged.

The great convenience of the notation adopted is now seen.*

* This is known as Bow's notation. The notation adopted in Part I involves the same idea, but it is not usually employed in works on Graphic Statics, though possessing very evident advantages. It was suggested to the writer by its use in certain of Professor Eddy's works.

The line representing the stress in any member is designated in the force diagram by letters similar to those which designate that member in the truss diagram. The latter is evidently a *space diagram* (Art. 11). The force diagram is often called a *stress diagram*, since it shows the values of the internal stresses in the truss members.

89. Reciprocal Figures. — There are always two ways of completing the force polygon when two of the forces are known only in lines of action. (See Art. 18.) Either way will give correct results, but unless a certain way be chosen, it will become necessary to repeat certain lines in the stress diagram. Thus, if, in Fig. 30, instead of $GABHG$ we draw $GABH'G$, the lines GH' , $H'B$ are not in convenient positions for use in the other polygons of which they ought to form sides. The lettering of the diagrams will also be complicated. As an aid in drawing the lines in the most advantageous positions, it is convenient to remember the fundamental property of figures related in such a way as the force and space diagrams shown in Fig. 30.

Such figures are said to be *reciprocal* with regard to each other. The fundamental property of reciprocal figures is that for every set of lines intersecting in a point in either figure, there is in the other a set of lines respectively parallel to them and forming a closed polygon.

It is also an aid to remember that the order of the sides in any closed polygon in the stress diagram is the same as the order of the corresponding lines in the truss diagram, if taken consecutively around the joint. This usually enables us at once to draw the sides of each force polygon in the proper order.

90. Order of External Forces in Force Polygon. — It will be observed that in the case above considered, in constructing the force polygon for the loads and reactions, these forces have been taken consecutively in the order in which their points of

be assumed to act at N , where its line of action intersects the exterior member of the truss, and the fictitious member MN inserted. The stresses in the actual truss members will be unaffected by this assumption, and such a device is necessary in order that the stress diagram may be the true reciprocal of the truss diagram.

§ 3. *Stresses Due to Wind Pressure.*

91. **Direction of Reactions Due to Wind Pressure.** — Since the effective pressure of the wind has the direction normal to the surface of the roof (Art. 85), it has a horizontal component which must be resisted by the reactions at the supports. These cannot, therefore, act vertically, as in the case when the loading is vertical. Their actual directions will depend upon the manner in which the ends of the truss are supported.

If the ends of the truss are immovable, the directions of the reactions cannot be determined, since any one of an infinite number of pairs of forces acting at the ends would produce equilibrium. (The same would be true of the reactions due to vertical loads.) In such a case the usual assumption is one of the following: (1) the reactions are assumed parallel to the loads; (2) the resolved parts of the reactions in the horizontal direction are assumed equal.

In the case of trusses of large span it is not unusual to support one end of the truss upon rollers so that it is free to move horizontally, the other end being hinged, or otherwise arranged to prevent both horizontal and vertical motion. This allows for expansion and contraction with change of temperature, as well as for movements due to the small distortions of the truss under loads. With this arrangement the reaction at the end supported on rollers must be vertical; and since the point of application of the other reaction is known, both can be fully determined by the method described in Art. 39.

92. Determination of Reactions. — The methods of finding reactions will now be explained for the three cases mentioned in the preceding article: (1) Assuming both reactions parallel to the wind; (2) assuming the horizontal resolved parts of the two reactions equal; and (3) assuming one reaction vertical.

(1) The first case needs no explanation, since it is identical with that described in Art. 87, except that the loads and reactions have a direction normal to one surface of the roof, instead of being vertical. It is to be noticed that this assumption cannot be made if the roof surface is curved, since the lines of action of the forces will not be parallel. But since the direction of the resultant of the loads will be known from the force polygon, both reactions may be assumed to act parallel to this resultant, and the construction made as before.

(2) In the second case, let each reaction be replaced by two forces acting at the support, one horizontal and the other vertical. The two horizontal forces are known as soon as the force polygon for the loads is drawn, and the two vertical forces may be found as in the preceding case, since their lines of action are known.

In Fig. 32, let ab , bc , cd be the lines of action of the wind forces. Let the right reaction be considered as made up of a horizontal component acting in de and a vertical component acting in ef ; and let the left reaction be replaced by a vertical component acting in fg and a horizontal component acting in ga . Draw the force polygon (or "load-line") $ABCD$. By the assumption already made GA and DE are to be equal, and their sum is to equal the horizontal resolved part of AD . Through the middle point of AD draw a vertical line; its intersections with horizontal lines through A and D determine the points G and E , so that the two forces GA and DE become known. The only remaining unknown forces are the vertical forces EF and FG . Choose a pole O , draw rays to the points G , A , B , C , D , E , and then the corresponding strings. Through the points determined by the intersection of og with fg , and oe

with ef , draw the string of . The corresponding ray drawn from O intersects EG in the point F , thus determining EF and FG . The reactions are now wholly known; that at the left support being DF , and that at the right support FA .





Fig. 32



(3) For the third case the construction is shown in Fig. 33 (*A*) and (*B*), for the two opposite directions of the wind. The method is identical with that employed in Art. 39. Only one point of the line of action of the left reaction is known, hence this is taken as the point of intersection of the corresponding strings of the funicular polygon. One of these strings can be drawn at once, since the corresponding ray is known; and the other is known after the remaining strings have been drawn, since it must close the polygon. The construction should be carefully followed through by the student.

The funicular polygons for the two directions of the wind are distinguished by the use of O and O' to designate the two poles.

In Fig. 33 (A), $ABCDEFGHIA$ is the force polygon for the case when the wind is from the right. Notice that the points A, B, C, D , coincide. This means that the loads AB, BC, CD , are each zero.





Fig. 33



In diagram (B), $ABCDEFGHIA$ is the force polygon for the case when the wind is from the left. The points E, F, G, H , coincide, because the loads EF, FG, GH , are each zero.

93. **Stress Diagrams for Wind Pressure.** — When the loads and reactions due to wind pressure are known, the internal stresses can be found by drawing a stress diagram, just as in the case of vertical loads. The construction involves no new principle, and will be readily made by the student. In Figs. 33 (A) and 33 (B) are shown the diagrams for the two directions of the wind.

The stresses in all members of the truss must be determined for each direction of the wind. If the truss is symmetrical with respect to a vertical line, as is usually the case, it may be that the same stress diagram will apply for both directions of wind. This will be so if the reactions are assumed to act as in cases (1) and (2) of the preceding article. In the case represented in Fig. 33, however, the hinging of one end of the truss destroys the symmetry of the two stress diagrams, and both must be drawn in full.

§ 4. *Maximum Stresses.*

94. **General Principles.** — For the purpose of designing any truss member, it is necessary to know the greatest stresses to which it will be subjected under any possible combination of loads.

Stresses are combined in accordance with the principle stated in Art. 78, that the resultant stress in a truss member due to the combined action of any loads is equal to the algebraic sum of the stresses due to their separate action.

The method will be illustrated by the solution of an example with numerical data.

95. **Problem—Numerical Data.** — Let it be required to design a wrought iron truss of 40 ft. span, of the form shown in Fig. 34 (Pl. I). Let 12 ft. be the distance apart of trusses, and let the loads be as follows :

Weight of truss, to be assumed in accordance with the formula of Art. 82: $W = \frac{3}{4} al (1 + \frac{1}{10} l)$. This gives $W = 1800$ lbs. Assuming this to be divided equally among the upper panels, and that the load for each panel is borne equally by the two adjacent joints, the load at each of the joints *bc*, *cd*, *de* is 450 lbs. The loads at the end joints may be neglected, being borne directly at the supports.

Weight of roof. — This depends upon the materials used and the method of construction, but will be taken as 6 lbs. per sq. ft.

of roof area, giving 900 lbs. as the load at each joint. This, also, is a permanent load. Total permanent load per joint, 1350 lbs.

Weight of snow.—Taking this as 15 lbs. per horizontal square foot, we find 1800 lbs. as the load at each joint.

Wind pressure.—This is computed from the formula

$$p_a = \frac{2 \sin \alpha}{1 + \sin^2 \alpha} p_n. \quad (\text{Art. 85.})$$

For this case we put $\sin \alpha = \frac{1}{2} \frac{5}{6} = \frac{5}{6}$; $p_n = 40$ lbs. per sq. ft.; whence $p_a = 35$ lbs. per sq. ft. (about). This gives upon each panel of the roof 5250 lbs. Then with the wind from either side, the wind loads on that side would be 2625 lbs., 5250 lbs., 2625 lbs. respectively.

96. **Stress Diagrams.**—We are now ready to construct the stress diagrams.

The truss is shown (Pl. I) in Fig. 34 (A). Fig. 34 (B) is the stress diagram for permanent loads. No diagram for snow loads is needed, since it would be exactly similar to that for permanent loads. The snow load at any joint being four-thirds as great as the permanent load, the stress in any member due to snow is four-thirds that due to permanent loads.

Fig. 34 (C) shows the stress diagram for the case of wind blowing from the left. The reactions are assumed to act in lines parallel to the loads—that is, normal to the roof. With this assumption, no separate diagram is needed for the case of wind from the right, since such a diagram would be exactly symmetrical to Fig. 34 (C). For example, the stress in the member gh due to the wind blowing from the right is given by the line GM in Fig. 34 (C).

97. **Combination of Stresses.**—After the stress diagrams are completed for the various kinds of loads, the stresses should be scaled from the diagrams and entered with proper sign in a table, as follows :

Member.	Permanent Load.	Snow.	Wind R.	Wind L.	Max.
<i>bh</i>	- 1525	- 2030	- 6270	- 7925	- 11480
<i>ci</i>	- 1255	- 1670	- 6270	- 7925	- 10850
<i>hi</i>	- 360	- 480	0	- 5250	- 6090
<i>ik</i>	+ 595	+ 790	+ 550	+ 6650	- 8035
<i>gl</i>	+ 1245	+ 1660	+ 2600	+ 8800	+ 11705
<i>gk</i>	+ 730	+ 975	+ 2300	+ 2300	+ 4005
<i>gm</i>	+ 1245	+ 1660	+ 8800	+ 2600	+ 11705
<i>lk</i>	+ 595	+ 790	+ 6650	+ 550	- 8035
<i>ml</i>	- 360	- 480	- 5250	0	- 6090
<i>dl</i>	- 1255	- 1670	- 7925	- 6270	- 10850
<i>em</i>	- 1525	- 2030	- 7925	- 6270	- 11480

By combining the results, the maximum stress in each member for any possible condition of loading can be determined. The possible combinations of loading are the following: Permanent load alone; permanent and snow loads; permanent load, and wind from either direction; permanent and snow loads, and wind from either direction. The student will readily understand the method of combining the separate results.

The problem here solved relates to a very simple form of truss. With some forms there may occur a reversal of stress in certain members, under different conditions of loading.

It is to be noticed that in the table the word maximum is used in its numerical sense, and has no reference to the algebraic sign of the stress.

98. **Examples.**—In Fig. 35 (*A*) to (*F*), are shown several forms of truss for which the student may draw stress diagrams, assuming loads in accordance with the data given in Arts. 82 to 85. In determining reactions due to wind pressure, the

three assumptions mentioned in Art. 92 should all be used in different cases, that the student may become familiar with the principle of each.




Fig. 35

§ 5. Cases Apparently Indeterminate.

99. **Failure of Usual Method.**—In attempting to construct the stress diagram by drawing the force polygon for each joint in succession, as in the cases thus far treated, a difficulty is met in certain forms of truss. It may happen that after proceeding to a certain point it is impossible to select a joint for which the force polygon can be completely drawn, the number of unknown forces for every joint being greater than two.

Thus, in the truss shown in Fig. 36, if the stress diagram is started in the usual way, beginning at the left support, the force polygons for three joints may be constructed without difficulty, thus determining the stresses in bl , lk , lm , cm , mn , nk . But the force polygon for $cdqpnmc$ cannot be constructed, since three forces are unknown,—namely, those in dq , qp , pn . And at the joint $knpsk$, the stresses in np , ps , and sk are unknown. The problem, therefore, seems at this point to become indeter-

minate, since either of the two polygons can be completed in any number of ways, so far as the known forces determine. It can be shown, however, that this ambiguity is only apparent. This may be proved as follows :

Consider the portion of the truss to the left of the broken line $M'N'$. It is in equilibrium under the action of eight forces ; five of these (four loads and a reaction) are known ; the remaining three are the forces in er , rs , and sk . Now, the problem of determining these three unknown forces is the same as that treated in Art. 40. It was there found to be a determinate problem, unless the lines of action of the three unknown forces intersect in a point or are parallel.

That the problem is determinate may be seen also from the principle of moments (Art. 51). The eight forces mentioned being in equilibrium, the sum of their moments is zero for any origin in their plane. Let the origin be taken at the point of intersection of the lines of action of two of the unknown forces, as er , rs . Then from the principle of moments we have (since the moments of the two forces named are zero) : Algebraic sum of moments of loads and reaction to left of section + moment of $SK=0$. The only unknown quantity in this equation is the magnitude of SK , which may, therefore, be determined. The other unknown forces may be found in a similar manner, the origin of moments being in each case chosen so as to eliminate two of the three unknown forces.

The whole problem of drawing the stress diagram is now seen to be determinate. For, as soon as the stress in sk is known, the force polygon for the joint $knpsk$ contains but two unknown sides, and can be drawn at once. No further difficulty will be met.

100. Solution of Case of Failure—First Method.—The reasoning of the preceding article suggests two methods of treating the so-called ambiguous case. These will now be described.

The first method is to apply the construction of Art. 40, as follows: Referring to Fig. 36, consider the equilibrium of the portion of the truss to the left of the line $M'N'$. The system of forces consists of those whose lines of action are $ka, ab, bc, cd, de, er, rs, sk$. Let them be taken in the order named, and draw the force polygon for the known forces. (The reaction ka is supposed to be already determined.) The known part of the force polygon is $KABCDE$; the unknown part is to be marked $ERSK$. Choose a pole O and draw rays to K, A, B, C, D , and E ; then draw the corresponding strings of the funicular polygon. Remembering the method of Art. 40, we draw first oe , making it pass through the intersection of $er and $rs$$




Fig. 36

(the reason for this being that *it makes the string os also pass through that point*); then draw in succession od, oc, ob, oa, ok . The string ok intersects sk in a point through which os must be drawn. Hence os must join that point with the starting point of the polygon. This completes the funicular polygon, except the string or , which must pass through the intersection of er

and rs in some direction not yet known. This string is not necessary to the solution of the problem.

Since os is now known, OS may be drawn parallel to it from O ; and by drawing a line from K parallel to the known direction of KS , the point S is determined, and KS becomes known.

To find ER and RS it is only necessary to draw from S a line parallel to rs , and from E a line parallel to er ; their intersection gives the point R , and the force polygon for the system of forces considered is complete. The stresses in er , rs , and sk being now known, the stress diagram may be completely drawn by the usual method.

It is interesting to notice that the method just described determines the lines ER , RS , SK , in their proper position in the complete stress diagram. The determination of ER and RS by this method is not necessary, since the usual method of drawing the stress-diagram can be carried out as soon as SK is known. But the independent determination of ER and RS by the two methods serves as a check on the accuracy of the construction.

The funicular polygon employed in the above construction, so far as it belongs to the external forces, may coincide with the corresponding part of the funicular polygon used in determining the reactions. If this is desired, two points must be observed: (1) the string oe must be the first drawn, and must pass through the intersection of er and rs , and (2) the pole must be so chosen that ok will not be nearly parallel to ks .

It should also be noticed that the construction of the funicular polygon might begin with the string ok , which should then be made to pass through the intersection of rs and sk . The student will be able to carry out this construction without difficulty.

101. Solution of Case of Failure — Second Method. — It will now be shown how the apparently ambiguous case can be

treated graphically by the principle of moments. Referring again to Fig. 36, consider the portion of the truss to the left of section $M'N'$. It is acted upon by eight forces, of which five (the loads and the reaction) are known, and three (whose lines of action are er , rs , sk) are unknown. The algebraic sum of the moments of all these forces about any origin must be zero. Let the origin be taken at the point of intersection of er and rs , so that the moments of the forces acting in these lines are both zero; then the sum of the moments of the five known forces, plus the moment of the force acting in the line sk , must equal zero. Now the sum of the moments of the five known forces may be found by the method of Art. 56. Through the origin of moments draw a line parallel to the resultant of the forces named (that is, a vertical line), and let i equal the length intercepted on it by the strings oe , ok . Then the required moment is $-iH$, where H is the pole distance. (The minus sign is given in accordance with the convention that left-handed rotation shall be positive.) Let P =unknown force in line sk , and h its moment-arm. For the purpose of computing the moment, assume the stress in sk to be a tension; then the force P acts toward the right and its moment is positive, the value being $+Ph$.

Hence,

$$Ph - Hi = 0;$$

or,

$$P = \frac{i}{h} H.$$

From this equation P may be computed. The computation may be made graphically as follows: Draw (Fig. 36) a triangle WUV , making $WU=H$ (force units) and $WV=h$ (linear units). Lay off $WY=i$ (linear units) and draw YX parallel to VU . Then WX (force units) represents P . This is readily seen, since from the two similar triangles we have the proportion $\frac{P}{H} = \frac{i}{h}$, which agrees with the equation above deduced.

The computation is simplified if the pole distance H is taken equal to as many force units as h is linear units; or if H

is some simple multiple of h . For, suppose $H = nh$; then $P = \frac{inh}{h} = ni$. If $n = 1$, $P = i$.

The stress in sk is found to be a tension, since P is positive. Whatever the nature of the stress, it may be assumed a tension in writing the equation, and the sign of the value found will show whether the assumption coincides with the fact.

102. Other Methods for Case of Failure. — In certain cases the method of treating the "ambiguous case" may profitably be varied.

(1) The construction of Art. 100 may be modified as follows: Determine the resultant of the known external forces acting on the portion of the truss to one side of the section $M'N'$. This resultant is in equilibrium with the three unknown forces acting in the members er , rs , sk . Hence these forces can be determined by the special method explained in Art. 42.

The resultant of the five known forces is represented in magnitude and direction by KE in the force polygon; and its line of action passes through the intersection of the strings oe , ok in the funicular polygon. Since this point of intersection is likely to be inaccessible, the construction of Art. 42 cannot be conveniently applied. It may be modified by using instead of KE the two forces KA (the reaction in the line ka) and AE (the resultant of the four loads, its line of action being determined by the intersection of the strings oa and oe). First determine forces in the three lines er , rs , sk , which shall be in equilibrium with KA ; then make a similar construction for AE , and combine the results.

(2) It has been proposed to employ the following reasoning: Remove the members pq and qr , and insert another represented by the broken line in Fig. 36. Evidently this does not change the stress in the member sk , since the forces acting on the truss to the left of the section $M'N'$ are unchanged. But with this change the difficulty encountered in constructing the stress diagram by the usual method is avoided. For when the joint

$nmcdqpn$ is reached, the forces acting there will be all known except two. Let the stress diagram be drawn in the usual way until the stress in sk is known. Then restore the original bracing and repeat the construction, using the value just determined for SK .

This method is convenient whenever it is applicable. Cases may, however, arise, in which it will fail. For instance, if a load is applied at the joint $pqrsp$, the members pq and qr cannot both be omitted, and the method cannot be applied.



Fig. 37

Again, it would be inapplicable in case of a truss such as shown

in Fig. 37, with loads at all upper joints. In such cases, one of the methods explained in the preceding articles may be applied.

Other methods might be mentioned, but the foregoing discussion of the case will probably be found sufficient.

103. Failing Case in Other Forms of Truss. — The usual method of constructing the stress diagram may fail in other forms of truss, though the one above described is the most common. In such a case, the problem of finding the stresses may be really indeterminate, or only apparently so. Whenever it is possible to divide the truss into two parts by cutting three members which are not parallel and do not intersect in one point, the stresses in the three members cut are determinate as soon as all external forces are known, and can be found by methods already given. If more than three members are cut, the problem of finding the stresses in them is indeterminate, unless all but three of these stresses are known. By remembering these principles, the determinateness of any given problem may readily be tested. (See Art. 70.)


§ 6. *Three-Hinged Arch.*

104. Arched Truss Defined. — If a truss is so supported that when sustaining vertical loads the reactions at the supports

have horizontal components directed toward the centre of the span, the truss becomes an *arch*. The only kind of arch we shall here consider is that consisting of two partial trusses hinged together at the crown, and each hinged at the point of support.

Such a truss is shown in Fig. 38, in which the two partial trusses are hinged to the abutments at P and Q , and connected by a hinge at the point R . Since a hinge at the support allows the reaction of the supporting body upon the truss to take any direction in the plane of the truss, the directions of the reactions at P and Q are unknown, as is also that of the force exerted by either partial truss upon the other at the point R . The problem of determining the reactions may, therefore, at first sight seem indeterminate. It will be shown in the next article that it is in reality determinate, and that the only principles needed in the solution are such as have been already often applied in the preceding chapters. The three-hinged arch is indeed a "simple" structure (Art. 75), since the theory of elasticity is not needed in the determination of the reactions.

105. Reactions Due to a Single Load.—The method of finding the reactions is most clearly understood by considering the



effect of a single load on either partial truss. Let a load be applied at S (Fig. 38) and let all other loads acting on either portion of the truss (including the weight of the structure) be

neglected. Call the two partial trusses X and Y , and consider the part Y . The only forces acting upon it are the reaction exerted by the abutment at Q and the force exerted at R by the truss X . These two forces, being in equilibrium, must have the same line of action, which is, therefore, the line QR . Consider now the body X . The external forces acting upon it are the load at S , the reaction of the abutment at P , and the force exerted by Y at the point R . But this last force is equal and opposite to the force exerted by X upon Y , and its line of action is therefore QR . The three forces acting upon the body X being in equilibrium, their lines of action must meet in a point; which point is found by prolonging QR to meet the line of action of the applied load. Let T be this point, then PT is the line of action of the reaction at P . The reactions can now be determined by drawing the triangle of forces. This triangle is ABC in the figure, AB representing the load at S , BC the reaction in the line QR (also marked bc), and CA the reaction in the line PT (marked also ca). Evidently ABC may be regarded as the polygon of external forces, either for the partial truss X , or for the whole structure composed of X and Y ; and BC represents either the force exerted by Y upon X at R , or the force exerted upon Y by the supporting body at Q .

If, now, the structure be loaded at other points, the reactions due to each load may be found separately; the resultant of all such separate reactions at either support will be the true reaction at that support when all the loads act together. A convenient method of applying these principles will be given in the next article.

106. Reactions and Stresses Due to Any Vertical Loads. — In Fig. 39 is represented a truss consisting of two parts supported by hinges at P' and Q' and hinged together at R' . Consider all vertical loads to be applied at the upper joints, their lines of action being marked in the usual way. We shall first explain the construction for finding the reactions at the supports; after

these are determined, the drawing of the stress diagram will present no difficulty.

Since we shall sometimes deal with one of the partial trusses, and sometimes with the two considered as a single body, it will be well at the outset to specify the external forces acting on each of these bodies.




Fig. 39

(1) For the partial truss at the left we have five applied loads, the reaction at R' (exerted by the other truss), and the reaction at P' . The force polygon for these forces will be marked as follows: $ABCDEFLA$. (The meaning of the letters will be understood before the force polygon is actually drawn, by reference to the corresponding letters in the space diagram.)

(2) For the right-hand partial truss the external forces are five loads and two reactions, and the force polygon will be marked thus: $FGHIJKLF$. (Notice that FL and LF are equal and opposite forces, being the "action and reaction" between the two trusses at R' .)

(3) For the combined structure the external forces are the ten loads and the reactions at P' and Q' . (The action and reaction at R become now internal forces.) The force polygon will be marked thus: $ABCDEFGHGIJKLA$.

Begin the construction by drawing the force polygon for the ten loads on the whole structure, lettering it as just indicated. Choose a pole O , draw the rays, and then the funicular polygon as far as possible. Now consider the right partial truss as unloaded. The resultant of the remaining five loads is represented in magnitude and direction by AF ; its line of action must pass through the intersection of oa and of , and is therefore the line marked af . Now, reasoning as in the preceding article, we see that the reaction at Q' must act in the line $Q'R'$. Let $Q'R'$ intersect af in T' , then $P'T'$ is the line of action of the reaction at P' . Hence the complete force polygon for the whole truss, when the right half is unloaded, may be found by drawing from F a line parallel to $Q'R'$, and from A a line parallel to $P'T'$, prolonging them till they intersect at L' . The reaction at P' is $L'A$, and that at Q' is FL' . (The line of action of the latter is marked fl' .)

Next, consider the left half to be without loads, the other half being loaded. The resultant of the five loads now acting is FK , its line of action fk being drawn through the point of intersection of of and ok . The reactions at P' and Q' for the present case have lines of action $P'R'$ and $Q'T'$, found just as in the first case of loading. These reactions are therefore determined in magnitude and direction by drawing from K a line parallel to $Q'T'$ and from F a line parallel to $P'R'$, prolonging them till they intersect at L'' . The complete force polygon for this case of loading is therefore $FGHIJKL''F$.

Consider now that both parts of the truss are loaded. The reaction at P' is the resultant of the two partial reactions $L'A$, $L''F$, and the reaction at Q' is the resultant of the two partial reactions FL' , KL'' . From L'' and L' draw lines parallel respectively to FL' and FL'' , intersecting in L . Then $L''L$ is equal and parallel to FL' , and LL' is equal and parallel to $L''F$. Hence KL and LA represent the resultant reactions at Q' and P' respectively. This completes the polygon of external forces for the whole truss, as well as that for each partial truss.

The stress diagram can now be drawn in the usual way, beginning at the point P' . The diagram for one partial truss is shown in Fig. 39 (*B*).

If loads are applied at the lower joints of the trusses, the reactions due to these may be found in the same manner as for the upper loads. But before beginning the determination of the stresses, the polygon must be drawn for the external forces taken in order around the truss. (See Art. 90.)

107. Case of Symmetrical Loading. — If the two half trusses are exactly similar and symmetrically loaded, the determination of reactions and stresses is much simplified.

(1) As regards the reactions, symmetry shows that the forces exerted by the two trusses upon each other at R' are horizontal. Hence, referring to Fig. 39, and considering either half-truss, as that to the left, the line of action of the reaction at P' may be found by drawing a horizontal line through R' and prolonging it to intersect af , the line of action of the resultant of all loads on the left truss; the line joining this point of intersection with P' is the required line of action of the reaction at the left abutment. The two reactions are now determined by drawing from F a horizontal line and from A a line parallel to the line just determined, and prolonging them till they intersect.

(2) As to the stresses, only one partial truss need be considered, since the stress diagrams for the two portions will be symmetrical figures.

These principles might have been employed in the case discussed in the preceding article; but the method there used is applicable to cases in which neither the trusses nor the loads are symmetrical.

108. Wind Pressure Diagram. — The diagrams for wind pressure will present no difficulty. The determination of the reactions will, indeed, be simpler than in the preceding case, since only one partial truss will be loaded at any one time, and the line of action of one reaction is therefore known at the outset. The construction is shown in Fig. 40.




Fig. 40.

In computing wind pressure loads, it will be assumed that each joint sustains half the pressure coming upon each of the two adjacent panels. It will be sufficiently correct in computing the pressure at any joint, to assume the slope of the roof

as that of the tangent to the roof curve at the joint in question; and the direction of the wind load may be taken as that of the normal to the roof curve at the joint. The force polygon for the wind loads is therefore not a straight line when the roof is curved. In Fig. 40, this polygon is $FGHIJK$. The reactions are to be marked KL , LF . (Since there are no loads on the other half-truss, the points $ABCDEF$ will coincide.) Choosing a pole O , draw the funicular polygon as shown, and determine the line of action of the resultant of all the wind loads. This line of action fk is drawn parallel to FK , through the point of intersection of the strings of and ok . Prolong fk to intersect $P'R'$ produced at T'' ; then $Q'T''$ is the line of action of the reaction at Q' . The force polygon may now be completed by drawing KL parallel to $Q'T''$ and LF parallel to $P'R'$. The reactions KL and LF being thus determined, the stress diagram can be drawn without difficulty.

The stress diagram is drawn for both partial trusses, with the result shown in the figure. If the two trusses are symmetrical, the diagram for the other direction of the wind need not be drawn; the stresses for this case being found from the diagram already drawn. If, however, the partial trusses are dissimilar, a second wind-diagram must be drawn.

It is not necessary to draw separate space diagrams for vertical loads and wind-forces. The constructions of Figs. 39 and 40 have been here kept wholly separate, in order that the explanation may be more easily followed.

109. Check by Method of Sections. — In case of a truss of long span, especially when the members have many different directions and are short compared with the whole length of the span, the small errors made in drawing the stress diagram are likely to accumulate so much as to vitiate the results. Thus, in Fig. 39, if, in drawing the stress diagram, we begin at P' and pass from joint to joint, there is no check upon the correctness of the work until the point R' is reached. At that point we

have a second determination of the reaction exerted by each half-truss upon the other; and it is quite likely that the two values found will not agree.

By a method like that employed in Art. 100 for the "indeterminate" form of truss, we may avoid the necessity of making so long a construction before checking the results. In Fig. 39 take a section cutting the three members cq , qr , rl , and apply the principles of equilibrium to the body at the left of the section. The forces acting on this body are LA , AB , BC , CQ , QR , RL . Choose a pole O' and draw the funicular polygon for this system, making the string $o'c$ pass through the point of intersection of cq and qr . Draw successively the strings $o'c$, $o'b$, $o'a$, $o'l$, prolonging the last to intersect lr . Through the point thus determined, draw $o'r$, which must also pass through the point of intersection of cq and qr . As soon as $o'r$ is known, the corresponding ray $O'R$ can be drawn in the force diagram, and then by drawing from L a line parallel to lr , the point R is determined. We may now close the force polygon, since the directions of the two remaining forces (cq and qr) are known.

The stresses in the three members cut being now known, we have a check on the correctness of the construction of the stress diagram, as soon as these members are reached in the process.

This method will be found of great use, not only for this form of truss, but for any truss containing many members.

§ 7. Counterbracing.

110. **Reversal of Stress.** — If the loads supported by a truss are fixed in position and unchanging in amount, the stress in any member remains constant in magnitude and kind. But in most cases such are not the conditions, and it may happen that under different combinations of loading, the stress in a certain member is sometimes tension and sometimes compression. It

is often thought desirable to prevent such changes of stress, the design of the members and their connections being thereby simplified. To accomplish this is the object of *counterbracing*.

III. Counterbracing. — Consider a truss such as the one shown in Fig. 41, subjected to vertical loads and to wind pressure from either side. A diagonal member such as xy may sustain tension under vertical loads alone, or with the wind from the left; while with the wind from the right it may sustain compression.

Now suppose xy removed, and a member represented by the broken line xy' introduced. It may easily be shown that any




Fig. 41

system of loading which would cause compression in xy will cause tension in this new member; and *vice versa*. For, divide the truss by a section MN cutting xy and two chord members as shown, and let L be the point of intersection of the two chord members produced. The kind of stress in xy or the other member (whichever is assumed to be present) may be determined by considering the system of forces acting on one portion of the truss, as that to the left of the section MN . Let the principle of moments be applied to this system, the origin being taken at L . If the external forces acting on the portion of the truss considered be such as to tend to cause right-handed rotation about L , the stress in xy must be compression in order to resist this tendency; while, if xy be replaced by xy' , a tension must exist in that member to resist right-handed rotation about L . Similarly, a tendency of the external forces to produce left-handed rotation about L would be resisted by a tension in xy ; or by a compression in the member xy' .

If the two members act at the same time, the stresses in

them will be indeterminate. These stresses may, however, be made determinate by the following device :

Let the member xy be so constructed that it cannot sustain compression. Then, whenever the external forces are such as to tend to throw compression upon it, it ceases to act as a truss-member, and the member xy' receives a tension which is determinate.

If the member xy' be constructed in the same way, any tendency to throw compression upon it causes it immediately to cease to act, and puts upon the member xy a tension instead.

A member such as xy' , constructed in the manner mentioned, is called a *counterbrace*.

112. Determination of Stresses with Counterbracing. — The use of counterbracing adds somewhat to the labor of determining the maximum stresses, since the members actually under stress are not always the same. The method of treating such cases will be illustrated in the next article by the solution of an example ; but first the main steps in the process may be outlined as follows :

(a) Construct separate stress diagrams for vertical loads and for wind in each direction, assuming the diagonals in all panels to slope the same way.

(b) Determine by comparison of these diagrams in which of the diagonal members the resultant stress is ever liable to be a compression. Draw in counters to all such members.

(c) With these counterbraces substituted for the original members, either draw new stress diagrams, or make the necessary additions to those already drawn. If the latter method is adopted, the added lines should be inked in a different color from that employed originally. (In some cases, this construction may be unnecessary on account of symmetry, as will be illustrated in the next article.)

(d) Combine the separate stresses for maxima in the usual way.

113. **Example.** — In Fig. 42 (Pl. II) are given stress diagrams for a “bow-string” roof-truss in which counterbracing is employed. At (A) is shown the truss or space diagram. The span is 48 ft. ; rise of top chord, 16 ft. ; rise of bottom chord, 8 ft. The chords are arcs of parabolas. The whole truss is divided into six panels by equidistant vertical members. The distance apart of trusses is taken as 12 ft.

Assume the weight of the truss at 2400 lbs., and that of the roof at 3600 lbs. ; this makes the total permanent load 1000 lbs. per panel. Take 800 lbs. as the load at each upper joint, and 200 lbs. as the load at each lower joint.

The snow load, computed at 15 lbs. per horizontal square foot, is about 1440 lbs. per panel.

Wind pressure is to be computed from the formula of Art. 85.

We now proceed to apply the method outlined in the preceding article.

(a) Assuming one set of diagonals present, we construct the stress diagrams for the various kinds of loads.

Diagram for permanent loads. — This is shown at (B) Fig. 42, which needs little explanation. It will be noticed that the stress in every diagonal member is zero. This will always be the case if the chords are parabolic and the vertical loads are equal and spaced at equal horizontal distances.

Diagram for snow loads. — Fig. 42 (C) is the stress diagram for snow loads. In this case, also, the stresses in the diagonals are all zero.

Wind diagrams. — At (D) and (E) are shown the diagrams for the two directions of the wind. The only thing needing special mention is the method used in laying off the force-polygon for the wind loads. We first compute the normal wind pressure on each panel by the formula of Art. 85. We thus find, when the wind is from the right, the following total pressures, taking $p_n = 40$ lbs. per sq. ft. :

On panel *d*, 1650 lbs. On panel *e*, 3870 lbs. On panel *f*, 5480 lbs.

In Fig. 42 (*D*) these are laid off successively in their proper directions to the assumed scale. Thus CD' , $D'E'$, $E'G$ represent respectively 1650 lbs. normal to dq , 3870 lbs. normal to es , and 5480 lbs. normal to ft . Now each of these loads is to be equally divided between the two adjacent joints. Bisect CD' at D , $D'E'$ at E , and $E'G$ at F ; then CD , DE , EF , FG represent the loads at the joints cd , de , ef , and fg respectively. The "load line" is therefore $CDEFG$.

The reactions are assumed to be parallel to the resultant load. With this explanation the figures (*D*) and (*E*) will be readily understood.

(*b*) *Comparison of results.* — The stresses due to permanent loads, wind right, and wind left, are shown in tabular form for convenience of comparison.

Member.	Perm. Load.	Snow Load.	Wind R.	Wind L.	Max.
<i>aj</i>	- 6660	- 9680	- 4250	- 14070	- 16340
<i>bl</i>	- 5350	- 7780	- 4880	- 9650	- 13130
<i>cn</i>	- 4550	- 6640	- 6380	- 6200	- 11190
<i>dq</i>	- 4550	- 6640	- 9500	- 4250	- 14050*
<i>es</i>	- 5350	- 7780	- 15030	- 3450	- 20380*
<i>ft</i>	- 6660	- 9680	- 14070	- 4300	- 20730*
<i>jh₆</i>	+ 5080	+ 7400	+ 780	+ 13500	+ 12480
<i>kh₆</i>	+ 4680	+ 6820	+ 700	+ 12450	+ 11500
<i>mh₄</i>	+ 4470	+ 6520	+ 1950	+ 7350	+ 10990
<i>ph₃</i>	+ 4470	+ 6520	+ 4100	+ 4100	+ 10990*
<i>rh₂</i>	+ 4680	+ 6820	+ 7680	+ 2050	+ 12360*
<i>th₁</i>	+ 5080	+ 7400	+ 13500	+ 800	+ 18580*
<i>jk</i>	+ 1180	+ 1440	+ 150	+ 2650	+ 2620
<i>lm</i>	+ 1180	+ 1440	- 280	+ 4100	+ 2620
<i>np</i>	+ 1180	+ 1440	- 950	+ 3800	+ 2620*
<i>qr</i>	+ 1180	+ 1440	- 1650	+ 2525	{ + 2620* - 470* }
<i>st</i>	+ 1180	+ 1440	- 1350	+ 1250	{ + 2620* - 170* }
<i>kl</i>	0	0	+ 1300	- 4600	+ 1300*
<i>mn</i>	0	0	+ 2700	- 4100	+ 2700*
<i>pq</i>	0	0	+ 4850	- 3150	+ 4850*
<i>rs</i>	0	0	+ 7080	- 1950	+ 7080*

It is seen that the diagonals shown are all in tension when the wind is from the right, and all in compression when the wind is from the left. Therefore counters are needed in all panels, and the counters will all come in action whenever the wind is from the left.

(c) *Stresses in counterbraces.* — It is evident from symmetry that no new diagrams are needed to determine the stresses in the counterbraces. In fact, the counterbrace in each panel is situated symmetrically to the main diagonal in another panel, and is subject to exactly equal stresses.

(d) *Combination for maxima.* — In combining the results for the greatest stresses in the various members, it will be assumed that the greatest snow load and the greatest wind load can never act simultaneously. For each member, therefore, the stress due to permanent load is to be added to the snow stress or the wind stress, whichever is greater. Again, in combining the tabulated results, we consider only the columns headed permanent load, snow load, and wind right; since whenever the wind is from the left, the other system of diagonals is in action. This gives the results entered in the last column.

We now notice the following facts:

(1) The results given for the diagonal members are the true maximum stresses.

(2) The stress found for each diagonal applies also to the symmetrically situated counterbrace.

(3) For any other member, we are to choose between the maximum found for that member and the value found for the symmetrically situated member. Thus, -20730 is the true maximum stress for both aj and ft ; etc. (The numbers denoting true maximum stresses are marked with a (*) in the table.)

It is seen that the verticals, with one exception, may sustain a reversal of stress. Thus, jk and st must be designed for a tension of 2620 lbs., and also for a compression of 170 lbs.; while lm and qr are each liable to 2620 lbs. tension and to 470 lbs. compression.

CHAPTER VI. SIMPLE BEAMS.

§ 1. *General Principles.*

114. **Classification of Beams.** — A beam has been defined in Art. 79. Beams may be treated in two main classes, the basis of classification being that described in Art. 75. These two classes will be called *simple* and *non-simple* beams respectively. The present chapter deals only with simple beams, the definition of which may be stated as follows:

A simple beam is one so supported that it may be regarded as a rigid body in determining the reactions.

A simple beam may rest on two supports at the ends; or it may overhang one or both supports.

A *cantilever* is any beam projecting beyond its supports. Such a beam may be either simple or non-simple.

A *continuous beam* is one resting on more than two supports. Such a beam is *non-simple*.

A beam may be supported in several ways. It is *simply supported* at a point when it rests against the support so that the reaction has a fixed direction. It is *constrained* at a point if so held that the tangent to the axis of the beam at that point must maintain a fixed direction. If *linged* at a support, the reaction may have any direction. We shall deal mainly with the case of simple support.

In what follows it will be assumed that the beam rests in a horizontal position, since this is the usual case.

115. **External Shear, Resisting Shear, and Shearing Stress.** — The *external shear* at any section of a beam is the algebraic

sum of the external vertical forces acting on the portion of the beam to the left of the section.

The *resisting shear* at any section is the algebraic sum of the internal vertical forces in the section acting on the portion of the beam to the left, and exerted by the portion to the right of the section.

The *shearing stress* at any section is the stress which consists of the internal vertical forces in the section, exerted by the two portions of the beam upon each other. It consists of the resisting shear and the *reaction* to it. (See Art. 63.)

Let AB (Fig. 43) be a beam in equilibrium under the action of any external forces. At any point in its length, as C , conceive a plane to be passed perpendicular to the axis of the beam, and consider the portion AC , to the left




FIG. 43

of the section. The principles of equilibrium apply to the body AC , and the external forces acting upon it include, besides those forces to the left of C that are external to the whole bar, certain forces acting across the section at C that are *internal* to AB , but *external* to AC . (Art. 61.) These latter forces comprise that constituent of the internal stress between AC and CB which is exerted *by CB upon AC* .

Represent by V the algebraic sum of the resolved parts in the vertical direction of all forces acting on AB to the left of the section at C , upward forces being called positive. V is the *external shear* at the given section as above defined.

Since the body AC is in equilibrium, condition (1), Art. 58, requires that the algebraic sum of the resolved parts in the vertical direction of all forces acting on it must equal zero. Hence the forces acting on AC in the section at C must have a vertical component equal to $-V$. This vertical component is called the *resisting shear* in the given section. This resisting shear is one of the forces of a stress of which the other is an equal and opposite force exerted by AC upon CB . This stress is called the *shearing stress* in the section, and is called positive

when it resists a tendency of AC to move upward, and of CB to move downward.

116. **Bending Moment, Resisting Moment, and Stress Moment.**

— The *bending moment* at any section of a beam is the algebraic sum of the moments of all the external forces acting on the portion of the beam to the left of the section; the origin of moments being taken in the section.

The *resisting moment* at any section is the algebraic sum of the moments of the internal forces in the section acting on the portion of the beam to the left, and exerted by the portion to the right of the section; the origin of moments being the same as for bending moment.

The *stress moment* or *moment of internal stress* at any section consists of the two equal and opposite moments of the forces exerted across the section by the two portions of the beam upon each other.

Referring again to Fig. 43, let us analyze further the forces in the section at C . Applying to the body AC the second condition of equilibrium ((2) of Art. 58), and taking an origin at a point in the section, we see that the algebraic sum of the moments of all the external forces acting on the beam to the left of the section plus the sum of the moments of the internal forces acting on AC in the section must equal zero. The former sum is defined as the *bending moment* at the given section. Represent it by M . The latter sum is defined as the *resisting moment* at the section, and must be equal to $-M$, by the above principle.


We have thus far referred only to the internal forces exerted by CB upon AC ; but evidently the equal and opposite forces exerted by AC upon CB have a moment numerically equal to M . The equal and opposite moments of the equal and opposite forces of the stress in the section together constitute the *stress moment* in the section.

If the external forces applied to the beam are all vertical, the value of M will be the same at whatever point of the section

the origin is taken ; since the arm of each force will be the same for all origins in the same vertical line. If the loads and reactions are not all vertical, the value of M will generally depend upon what point in the section is taken as the origin of moments.

117. Curves of Shear and Bending Moment. — The *curve of shear* for a beam is a curve whose abscissas are parallel to the axis of the beam, and whose ordinate at any point represents the external shear at the corresponding section of the beam.

Let AB (Fig. 44) represent a beam loaded in any manner, and let $A'B'$ be taken parallel to AB . At every point of $A'B'$ suppose an ordinate drawn whose length shall represent the external shear at the corresponding section of AB . The line ab , joining the extremities of all these ordinates, is the *shear curve*. Positive values of the shear may be represented by ordinates drawn upward from $A'B'$, and negative values by ordinates drawn downward. (Instead of drawing $A'B'$ parallel to the beam, it may be any other straight line whose extremities are in vertical lines through A and B .)



The *curve of bending moment* for a beam is a curve whose abscissas are parallel to the axis of the beam, and whose ordinate at any point represents the bending moment at the corresponding section of the beam. Thus in Fig. 44, $A''C''B''$ may represent the bending moment curve for the beam AB . (Evidently $A''B''$ might be inclined to the direction of AB , without destroying the meaning of the curve.) Positive and negative values of the bending moment will be distinguished by drawing the ordinates representing the former upward and those representing the latter downward from the line of reference $A''B''$.

118. Moment Curve a Funicular Polygon. — If the loads and reactions upon the beam are all vertical, every funicular polygon for these forces taken consecutively along the beam, is a

curve of bending moments. Thus, let MN (Fig. 45) represent a beam under vertical loads, supported at the ends by vertical reactions. Draw a funicular polygon for the loads and reactions as shown.




Fig. 45

Now, by definition, the bending moment at any section is equal to the moment of the resultant of all external forces acting on the beam to the left of the section, the origin of moments being taken in the section. By Art. 56, this moment can be found by drawing through the section a vertical line and finding the distance intercepted on it by the two strings corresponding to the resultant mentioned; the product of this intercept by the pole distance is the required moment. Hence, if oe (Fig. 45) is taken as axis of abscissas, the broken line made up of oa, ob, oc, od , is a "curve of bending moments."

119. **Design of Beams.** — The principles involved in the design of beams will not be here fully discussed. Every problem in design involves the determination of shears and bending moments throughout the beam; and the graphic methods of determining these will alone be considered in the following articles.

§ 2. Beam Sustaining Fixed Loads.

120. **Shear Curve for Beam Supported at Ends.** — Let MN (Fig. 45) represent a beam supported at the ends and sustaining loads as shown. Draw the force polygon $ABCD$, and with pole O draw the funicular polygon. The closing line is oe

(marked also $M''N''$), and OE drawn parallel to $M''N''$ fixes E , thus determining DE , EA , the reactions at the supports.

Take $M'N'$ as the axis of abscissas for the shear curve.

The shear at every section can be at once taken from the force polygon. For, remembering the definition of external shear (Art. 115) we have :

Shear at any section between M and P is EA (positive).

Shear at any section between P and Q is EB (positive).

Shear at any section between Q and R is EC (negative).

Shear at any section between R and N is ED (negative).

Hence the shear curve is the broken line drawn in the figure.

121. Moment Curve for Beam Supported at Ends. — As in Art. 118, it is seen that the funicular polygon already drawn (Fig. 45) is a bending moment curve for the given forces. For the bending moment at any section of the beam is equal to the corresponding ordinate of this polygon, multiplied by the pole distance.

For simplicity, it will be well always to choose the pole so that the pole distance represents some simple number of force-units.

The sign of the bending moment is readily seen to be negative everywhere, according to the convention already adopted (Art. 47).

122. Shear and Moment Curves for Overhanging Beam. — Consider a beam such as shown in Fig. 46, supported at Q and T , and sustaining loads at M , P , R , S , and N .

This case may be treated just as the preceding, care being exercised to take all the external forces (loads and reactions) in order around the beam.

The construction is shown in Fig. 46. First, the reactions at Q and T are found as in the preceding case, by drawing the funicular polygon, finding the closing line, and drawing OG parallel to it. The reactions are FG and GA . Then the value



of the external shear can be found for any section from the definition, and is always given in magnitude and sign by a certain portion of the force polygon $ABCDEFGA$. The resulting curve is shown in the figure, $M'N'$ being the line of reference.




Fig. 46

Similarly, from the definition of bending moment, and the principle of Art. 56, the bending moment at any section is equal to the ordinate of the funicular polygon multiplied by the pole distance. The polygon is shaded in the figure to indicate the ordinates in question. It is seen that the bending moment is positive at every section of the beam.

123. Distributed Loads. — In all the cases thus far discussed, the loads applied to the beam have been considered as concentrated at a finite number of points. That is, it has been assumed that a finite load is applied to the beam *at a point*. Such a condition cannot strictly be realized, every load being in fact distributed along a small length of the beam. If the length along which a load is distributed is very small, no important error results from considering it as applied at a point.

In certain cases a beam may have to sustain a load which is distributed over a considerable part of its length, or over the whole length. Such a load may be treated graphically with sufficient correctness by dividing the length into parts, and

assuming the whole load on any part to be concentrated at a point. The smaller these parts, the more nearly correct will the results be.

It may be remarked by way of comparison that while algebraic methods are most readily applicable to the case of distributed loads, the reverse is true of graphic methods, which are most easily applied in the very cases in which analytic methods become most perplexing.

124. Design of Beam with Fixed Loads. — The above examples are sufficient to explain the method of treating any simple beam under fixed loads. Under such loading the shear and bending moment at each section of the beam remain unchanged in value, and no further discussion is necessary as a preliminary to the design of the beam. We proceed next to the case of beams with moving loads.

§ 3. *Beam Sustaining Moving Loads.*

125. Curves of Maximum Shear and Moment. — When a beam sustains moving loads, the shear and moment at any section do not remain constant for all positions of the loads. In such a case it is the greatest shear or moment in each section that is to be used in designing the beam.

A *curve of maximum shear* is a curve of which the ordinate at each point represents the greatest possible value of the shear at the corresponding section of the beam for any position of the loads.

A *curve of maximum moment* is a curve whose ordinate at each point represents the greatest possible value of the bending moment at the corresponding section of the beam for any position of the loads.

In the following articles will be explained a method of determining any number of points of the curves just defined, in the case of a simple beam supported at the ends. The moving

load will be taken to consist of a series of concentrated loads with lines of actions at fixed distances apart. An example of such a load is the weight of a locomotive and train; the points of application of the loads being always under the several wheels.

126. Position of Loads for Greatest Shear at Any Section. —

In Fig. 47 (Pl. III) let the vertical lines ab , bc , etc., represent the lines of action of the moving loads in their true relative positions; the magnitudes of the loads being shown in the force polygon or "load line" $ABCD$. . . Let XY represent the length of the beam, and let it be required to determine the position of the moving loads that will cause the maximum positive shear at any section, as at that marked J .

First, consider the effect of a single load in any position. It is seen that any load to the right of J produces at that point a positive shear. For, by definition, the external shear is equal to the algebraic sum of all vertical forces to the left of the section, upward forces being reckoned positive. Now a load to the right of J causes no forces to act at the left of this section, except an upward reaction at X . On the other hand, a load to the left of J produces negative shear at that point. For the shear due to it is equal to the reaction at X minus the load itself, which will always be negative, since the load is greater than the reaction due to it. (It is also to be noticed that the shear due to a load at the left of the section is equal numerically to the reaction it produces at Y .)

Again, the shear due to any load is greater in magnitude, the nearer the load is to the section considered. For, as a load on JY approaches J , the reaction at X increases; and as a load on XJ approaches J , the reaction at Y increases.

Two principles are thus reached to guide in assigning the position of the loads that will produce the greatest positive shear at any section: (1) The segment of the beam to the left of the section should be without load and that to the right fully

loaded; and (2) the loads on the loaded segment should be as near the section as possible.

It would seem, therefore, that the greatest positive shear at the point J will occur when the loads are brought on the beam from the right to such a position that the foremost load in the series is just at the right of J . And, in general, this will be true, unless the foremost load is small in comparison with the whole load on the beam, or unless the distance between the first and second loads is considerable. In such cases it may be that a greater shear will result when the second load is brought up to the section. For, suppose the first load to be just at the right of J , and consider the effect of moving the whole series of loads to the left. As the first load passes the section, it produces a diminution of the shear equal in amount to the load. On the other hand, as the loads continue to move to the left, the effect of every load in producing reaction at X increases, while no further *decrease* in the shear at J occurs until the second load passes the section. Now, it may be that the net result of bringing the second load up to J will be to increase the shear at that section. If the first two or more loads are very small, it may be that the third or fourth load should be brought to the section to produce the greatest shear. Usually, however, it will be necessary to try only two (or at most three) positions.

Instead of resorting to trials to determine for which position the shear is greatest, we may apply a simple rule which will now be deduced.

Let P_1 =magnitude of foremost load, P_2 =magnitude of second load, etc., W being the total load on the beam. Let l =total span, and m =distance between P_1 and P_2 . Let x =distance from Y to the center of gravity of W when P_1 is at a given section. Let us compute the shear when P_1 is just at the right of the section, and then determine the effect of moving all loads to the left, until the second load comes to the section.

When P is at the right of the section, the shear is equal to

the reaction at X , say R . Then (calling V the external shear) we have

$$V = R = \frac{Wx}{l}.$$

If now the loads be moved until P_1 comes to a point just at the right of the section, the reaction due to W becomes $W \frac{(x+m)}{l}$, and the shear at the section becomes

$$V = R - P_1 = \frac{W(x+m)}{l} - P_1.$$

The increase of the shear is, therefore,

$$\frac{W(x+m)}{l} - P_1 - \frac{Wx}{l} = \frac{Wm}{l} - P_1.$$

This increase is plus or minus according as $\frac{Wm}{l}$ is greater or less than P_1 ; that is, as W is greater or less than $\frac{P_1 l}{m}$. Hence the following rule:

The maximum positive shear in any section of the beam occurs when the foremost load is infinitely near the section, provided W is not greater than $\frac{P_1 l}{m}$. If W is greater than $\frac{P_1 l}{m}$, the greatest shear will occur when some succeeding load is at the section.

In the above discussion it has been assumed that in bringing P_1 up to the section no additional loads are brought upon the beam. If this assumption is not true, let W' be the new load brought on the beam, and x' the distance of its center of gravity from the right support when P_1 is at the section. Then the shear corresponding to this position is

$$V = R - P_1 = \frac{W(x+m)}{l} + \frac{W'x'}{l} - P_1;$$

and the increase of shear due to the assumed change in the position of the load is

$$\frac{Wm}{l} + \frac{W'x'}{l} - P_1.$$

Hence, in the statement of the above rule, we have only to substitute $Wm + W'x'$ for Wm ; or, $W + \frac{W'x'}{m}$ for W . The additional load W' may be neglected except when the condition $W = \frac{P_1 l}{m}$ is nearly satisfied; for the term $W'x'$ will always be small in comparison with Wm .

The application of this rule is very easy, and will save much labor in the graphic construction of the shear curve.

If it is found that the first load should be past the section for the position of greatest shear, we may determine whether the second or the third should be at the section by an exactly similar method. We have only to apply the above rule, substituting P_2 for P_1 , and for m the distance between P and P_3 .

127. Determination of Maximum Shear. — The shear at any section due to any position of the moving loads can readily be determined from the force and funicular polygons, by a method which will now be shown.

Draw in succession the lines of action of the loads at their proper distances apart, as in Fig. 47 (Pl. III). Draw the load-line $ABCD \dots$, and choosing a pole O , draw the funicular polygon. The same space diagram may be used for any position of the moving loads; for, instead of moving the loads in either direction, we may assume the loads fixed and move the beam in the opposite direction.

By applying the rule deduced in Art. 126, it may be shown that there is a point Z in the beam, such that for any section to the right of Z the foremost load should be at the section in order that the shear may be a maximum; while for any section to the left of Z the second load must be brought to the section. The position of this point is readily determined, as follows:

In the case shown in Fig. 47, we have

$$l = 64 \text{ ft.}, \quad m = 8.1 \text{ ft.}, \quad P_1 = 8000 \text{ lbs.}, \quad \frac{P_1 l}{m} = \frac{64}{8.1} \times 8000 = 63200.$$

Hence, as the load moves from right to left, W is less than

$\frac{P_1 l}{m}$ until the whole load on the beam reaches 63200 lbs. This occurs when the fifth load is at Y . Hence the point Z is located at a distance from Y equal to the distance between the lines of action of the first and fifth loads.

For any point to the left of Z , the greatest shear will probably occur when the second load is at the section. To test whether in any case the third load should be at the section, we apply the same principle, as follows: The second load is 15000 lbs.; the distance between the second and third loads is 5.8 ft. Hence, for greatest shear, the third load should not be at the section unless the whole load on the beam is at least $\frac{64}{5.8} \times 15000$ lbs. or 165500 lbs. But it is easily seen that the total load can never be so great.

We may now explain the construction for finding the greatest shear at any section. Consider a section at the left of Z , as at the point marked J . From the above reasoning it is evident that the second load must be brought close to the section. In Fig. 47, $S_1 S_2$ is drawn to represent the beam, its position being such that the point J is infinitely near bc , the line of action of the second load. Through the extremities of the beam $S_1 S_2$ draw vertical lines to represent the action-lines of the reactions at the supports. The portion AB' of the load line represents the loads now on the beam, and the corresponding extreme strings of the funicular polygon are oa and ob' . If now we consider the funicular polygon for the loads and reactions acting on the beam in the supposed position, we see that the closing side is found by joining the points in which the action-lines of the end reactions intersect oa and ob' respectively. This is marked oj' in the figure. Now draw in the force diagram a ray parallel to this closing line, and let J' be its point of intersection with the load line; then $B'J'$ and $J'A$ are the two reactions. The shear at the point J is evidently the algebraic sum of the reaction $J'A$ and the load AB ; hence it

is represented by $J'B$. In Fig. 47 let X, Y , be drawn to represent the length of the beam, and let the ordinates of the shear curve be drawn from it. Then from J we lay off an ordinate equal to $J'B$. The whole curve of maximum shear is shown in the figure, but the construction for finding it is given for only one point.

128. Shear Curve for Combined Fixed and Moving Loads. — Let the beam sustain a fixed load of 25000 lbs. uniformly distributed along the beam. The shear close to the left support due to this load is equal to the reaction, or 12500 lbs.; and decreases as we pass to the right by $\frac{25000}{64}$ lbs. for each foot. At the middle of the beam the shear is zero, and at the right support it is -12500 lbs. Hence the shear curve is a straight line, and may be drawn as follows: From X , lay off an ordinate downward representing 12500 lbs., and from Y , an ordinate upward representing 12500 lbs.; the straight line joining the extremities of these ordinates is the shear curve for the fixed load. Positive shears are laid off downward and negative shears upward for the reason that, if this be done, the greatest positive shear at any point due to fixed and moving loads is represented by the total ordinate measured between the shear curves for fixed loads and for moving loads. It is seen that at a certain point somewhere to the right of the center of the beam this greatest shear is zero, and for all sections to the right of this point it is negative. This point is determined by the intersection of the two shear curves.

129. Position of Loads for Greatest Bending Moment. — Referring to the beam XY shown in Fig. 47 (Pl. III), consider the bending moment at any section (as J) due to a load anywhere on the beam. First, suppose the load is at the right of the section. In this case the only force brought upon the portion of the beam to the left of the section is a reaction at X . By definition (Art. 116) the bending moment at J is the moment of this reaction about an origin at J , and is negative. Moreover,

since the reaction will become greater as the load moves toward the left, the greatest bending moment due to a load at the right of the section will occur when the load is as near the section as possible. Next consider a load at the left of the section. The bending moment due to it is equal to the moment of the resultant of the load and the left reaction. But this resultant is equal and opposite to the reaction at the right support, and has the same line of action (because the load and the two reactions due to it are in equilibrium); hence the bending moment is the negative of the moment of the right reaction about an origin in the section. The bending moment is therefore negative, and is greatest when the right reaction is greatest. Hence, a load at the left of the section produces its greatest bending moment when the load is as near as possible to the section.

We are therefore led to the following general principles for a simple beam supported at the ends:

(1) The bending moment at every section is negative for all positions of the moving loads.

(2) The negative bending moment at any section has its greatest value when the whole beam is loaded as completely as possible, and the heaviest loads are near the section.

These principles serve as a general guide, but unless the moving loads are equidistant and equal in magnitude it will be necessary to try several positions before the position for greatest bending moment will be known. Usually one of the heaviest loads should be directly at the section.

Instead of resorting to repeated trials, the position of loads giving greatest bending moment at any section may be found by means of a simple rule which will now be deduced.

Let l = length of beam between supports; W = total load on beam; x = distance of center of gravity of W from right support; W_1 = load on beam to left of given section; x = distance of center of gravity of W_1 from section; l_1 = distance of section from left support; R = reaction at left support; M = bending moment at the section. Then we have

$$R = \frac{Wx}{l};$$

$$M = Rl_1 - W_1x_1 = \frac{Wl_1}{l}x - W_1x_1.$$

If the loads all move an infinitesimal distance to the left, then x and x_1 receive equal infinitesimal increments, and the increment of M is

$$dM = \frac{Wl_1}{l} dx - W_1 dx_1 = \left(\frac{Wl_1}{l} - W_1 \right) dx$$

(since $dx_1 = dx$). Now if M is a maximum, we must have $\frac{dM}{dx} = 0$; that is, $\frac{Wl_1}{l} - W_1 = 0$; or, $\frac{W_1}{l_1} = \frac{W}{l}$. Hence the following rule:

When the bending moment at any section of the beam has its greatest value, the loads on the two segments of the beam are to each other as the lengths of the segments.

In case of concentrated loads, the condition just stated can generally not be exactly satisfied except for certain sections of the beam. It will usually be found that the position most nearly fulfilling the condition is that in which some heavy load is just at the section. This will be illustrated in the next article.

[NOTE. — The above reasoning applies only to the case of concentrated loads, and is not rigorous for this case, if, in the position of maximum moment for any section, a load is at the section; for $\frac{dW_1}{dx}$ will not then be zero, as assumed above. In such a case $\frac{dM}{dx}$ is discontinuous, and its value changes sign as the loads pass through the position for which $\frac{W_1}{l_1} - \frac{W}{l} = 0$. It is still true that this condition is satisfied in the position of maximum moment, provided the load at the section is regarded as divided in some certain ratio between the two segments of the beam.]

130. Determination of Bending Moments. — The application of the above principles and the method of determining the bending moment at any section of the beam will now be shown for the case represented in Fig. 47 (Pl. III). Let the greatest bending moment be found for the section J . From the general

principles deduced in Art. 129, it is probable that the loads nearest the section should be the third and fourth in the series. Also, since the point J divides the span into segments of 16 ft. and 48 ft., the load on the left segment should be one-fourth the total load on the beam. Now it is readily found that when the load CD is just at the right of the section, the whole load on the beam is 112,000 lbs., while the load on the left segment is 23,000 lbs., which is less than one-fourth of 112,000. And when the load CD is just at the left of the section, the load on the left segment is 38,000 lbs., which is greater than one-fourth of 112,000. Hence the bending moment is a maximum when the load CD is just at the section.

In Fig. 47, M, M_j represents the beam for this position of the loads, and the closing line of the funicular polygon is marked oj'' . Using the principle of Art. 56, we find the bending moment at the given section by measuring the distance intercepted on cd by the strings od and oj'' and multiplying it by the pole distance in the force diagram.

Let $X_m Y_m$ (Fig. 47) be the axis of abscissas for the curve of maximum moments. From the point J draw an ordinate equal to the intercept just found; this locates a point of the required moment curve.

Other points may be determined in the same manner. The curve is shown in the figure, but the construction is not given for any section except that at J .

It must be remembered that each ordinate is to be multiplied by the pole distance. Hence it will be convenient to choose the pole distance equal to some round number of force units.

131. Moment Curve for Fixed Loads. — The greatest bending moment due to moving loads must be combined with the bending moment due to fixed loads. If the fixed load is uniformly distributed, as already assumed in the computation of shear, it may be divided into parts, each assumed concentrated at its center of gravity, and a funicular polygon drawn, using the

same pole distance employed in the force diagram for moving loads. The ordinates of this funicular polygon may be laid off upward from the line $X_m Y_m$, and their ends joined to form a continuous curve. The total ordinate from this curve to that already drawn for moving loads represents the true greatest bending moment at the corresponding section of the beam. The curve is shown in the figure, but the construction is omitted, since it involves no new principle.

It is to be remembered that the bending moment found for any section is a possible value for the other section equally distant from the center of the beam, since the train may be headed in the opposite direction, and the same construction made, viewing the beam from the other side. The same statement holds as to shears.

132. Design of Beam sustaining Moving Loads. — In designing a beam to sustain moving loads, the greatest shear and bending moment that can come upon it for any position of the loads must be known for every section. The methods above given are sufficient for the determination of these quantities; and the problem of designing the beam will not be here further discussed.

133. Plate Girders and Lattice Girders. — A *plate girder* is a beam built up of rolled plates and angle-irons riveted together, the cross-section being as shown in Fig. 48. If latticing is substituted for the plate, the beam becomes a *lattice girder*. Railway bridges of spans under 100 ft. frequently employ either rolled beams, plate girders, or lattice girders. (See Cooper's "Specifications for Iron and Steel Railroad Bridges.") The methods given in the preceding articles are especially useful in designing this class of bridges.



Fig. 48

The student should make the complete construction for determining the curves of maximum shear and bending moment for a beam designed to carry the series of moving loads shown in Fig. 47.

CHAPTER VII. TRUSSES SUSTAINING MOVING LOADS.

§ 1. *Bridge Loads.*

134. General Statement. — The most important class of trusses sustaining moving loads is that of bridge trusses. The two main classes of bridges are highway bridges and railway bridges. The forms of trusses most commonly used differ for the two classes, as do also the amount and distribution of loads.

Before the design can be correctly made, the weights of the trusses themselves must be known. Since these weights depend upon the dimensions of the truss members, they cannot be known with certainty until the design is completed. The remarks made in Art. 82 regarding the design of roof trusses are here applicable.

In the following articles we shall give data available for preliminary estimates of truss weights.

As stated in Art. 133, railway bridges of short span are frequently supported by rolled or built beams. When the span is longer than 100 ft., trusses should be used. (Cooper's "Specifications.")

135. Loads on Highway Bridges. — (1) *Permanent load.* — The permanent load sustained by a highway bridge truss includes the weight of the truss itself, of the lateral or "sway" bracing, of the floor and the beams and stringers supporting it. These weights are all subject to much variation, but, for purposes of preliminary design, the following formula, taken from Merriman's "Roofs and Bridges," may be used.

Let w = weight of bridge in pounds per linear foot ; l = span in feet ; b = width in feet. Then

$$w = 140 + 12 b + 0.2 bl - 0.4 l.$$

(2) *Snow load.* — The weight of snow may be taken as in case of roof trusses (Art. 84). The values there given are probably in excess of those ordinarily employed in practice.

(3) *Wind load.* — The pressure of wind striking the bridge laterally is resisted by the chord members together with the lateral bracing. These constitute horizontal trusses, in which the stresses are to be found in the same way as for the main trusses of the bridge. As the determination of wind stresses requires the use of no special methods or principles, they will not be here considered. The student is referred to Burr's "Stresses in Roofs and Bridges," Merriman's "Roofs and Bridges," and other available works for a complete discussion of wind pressure and its effects on bridge trusses.

(4) *Moving load.* — The most dangerous moving load for a highway bridge is usually a crowd of people or a drove of animals. This is commonly taken as a uniformly distributed load, which may cover the whole bridge or any portion of it. Its value is variously taken at from 60 lbs. to 100 lbs. per square foot of area of floor, depending upon the span and upon local conditions.

It may be that in certain cases the greatest stresses will result from the passage of heavy pieces of machinery over the bridge, as, for example, a steam road roller. This should of course be considered in the design.

For a complete discussion of loads on highway bridges, the student is referred to Waddell's "Highway Bridges."

136. Loads on Railway Bridges. — (1) *Permanent load.* — The permanent load on a railway bridge includes (a) the weight of the track system, which is known or may be determined at the outset ; (b) the weight of longitudinal stringers and cross-

beams, which can be determined before the trusses are designed ; and (c) the weights of trusses. The weight of the track system may be taken at 400 lbs. per linear foot for a single track. (See Burr's "Stresses in Bridge and Roof Trusses" ; Cooper's "Specifications for Iron and Steel Railroad Bridges" ; Merriman's "Roofs and Bridges.") The total weight of track system and supporting beams and stringers varies from 450 lbs. to 600 lbs. per linear foot. (Merriman.) For spans less than 100 feet, Merriman gives the following formulas, in which w is the total dead load of the bridge in pounds per linear foot, and l is the span in feet :

$$\text{For single track, } w = 560 + 5.6 l.$$

$$\text{For double track, } w = 1070 + 10.7 l.$$

See also Art. 8 of Burr's work above cited.

(2) *Snow and wind.* — Railway bridges usually offer little opportunity for the accumulation of snow. Wind pressure is, however, an important factor. Besides the pressure upon the bridge itself, the pressure upon trains crossing the bridge must be considered. The latter is a moving load and may be dealt with in the same way as other moving loads. Its amount may be computed from the area of the exposed surface of the train and the known (or assumed) greatest pressure due to wind striking a vertical surface (Art. 85).

For further discussion of wind pressure, the student is referred to the works already cited. The graphic methods of determining stresses due to wind will be evident when the methods for vertical loads given in the following articles are understood.

(3) *Moving loads.* — The moving load to be supported by a bridge consists of the weights of trains. Such a load is applied to the track at a series of points, namely, the points of contact of the wheels. But the load is applied to the trusses only at the points at which the floor beams are supported. Hence the actual distribution of loads upon the truss is somewhat complex. It was formerly common to substitute for the actual

load a uniformly distributed load, thus simplifying the problem of determining stresses. It is now more usual to consider the actual distribution of loads for some standard type of locomotive used by the railroad concerned, or specified by its engineers. For examples of such distributions the student is referred to Cooper's "Specifications" already cited; also to Fig. 47, and to the following portions of this chapter.

137. Through and Deck Bridges. — A bridge is called *through* or *deck* according as the floor system is supported at points of the lower or of the upper chord. In the former case, if the trusses are too low to require lateral bracing above, they are called *pony* trusses.

The weight of the truss itself is to be divided between the upper and lower joints. But the weight of the floor system and of the supporting beams and stringers comes wholly at the lower joints of a through bridge, or at the upper joints of a deck bridge. The moving load is, of course, applied at the same joints at which the floor system is supported.

If the floor system is supported directly upon the upper chord, as is sometimes the case, the moving load and part of the dead load produce bending in the chord members; otherwise the design is unaffected by this construction.

§ 2. *Truss Regarded as a Beam.*

138. Classification of Trusses. — Since a bridge truss acts as a practically rigid body resting on supports at the ends or other points and sustaining vertical loads, it may be regarded as a beam, and trusses may be classified in the same way as beams (Art. 114). The only class to be here considered is that of *simple trusses*, or such as may be regarded as rigid bodies for the purpose of determining the reactions.

Cantilever trusses and continuous trusses are defined like the corresponding classes of beams (Art. 114). The most important case is that of a truss *simply supported* at the ends.

139. **External Shear for a Truss.** — If a truss be regarded as a beam, the external shear, resisting shear, and internal shearing stress at any section may be defined just as in Art. 115. In some forms of truss a knowledge of the external shear at any section makes it possible to compute readily the stresses in certain truss members. Thus, in the portion of a truss represented in Fig. 49, let the section MN cut three members, of which




Fig. 49

two are horizontal. (The member $x'y'$ is disregarded.) Since each member can exert forces only in the direction of its length, the external shear in the section MN must be wholly resisted by the diagonal xy ; and the internal force in xy must be such that its resolved

part in the vertical direction is equal in magnitude to the external shear in the section. Let the external shear V be represented by YZ (Fig. 49); draw YX parallel to yx and ZX horizontal; then XY will represent the stress in xy . If V is positive (Art. 115), the stress in xy is a tension. If V is negative, the stress is a compression. If the member xy were replaced by one sloping the other way from the vertical, these statements as to kind of stress would be reversed.

If no two of the three members cut by any section are parallel, the stresses cannot be computed so simply, since all may contribute components of force to resist the external shear.

140. **Bending Moment for a Truss.** — In many cases the stresses in the truss members can be found from the values of the bending moment at different sections.

Thus, in Fig. 49, let a section MN be taken cutting three members as shown, and let the origin of moments be taken at the point of intersection of two of them (as bx and xy); then since the moments of the internal forces in these two will be

zero, the resisting moment is equal to the moment of the internal force in the third member ay . The arm of this latter force is the perpendicular distance of its action line from the origin. Call it h , and let p represent the force itself, and M the bending moment. Then, numerically,

$$ph = M. \quad \therefore p = \frac{M}{h}.$$

If M is positive (in accordance with the convention of Art. 47), p must act from right to left, hence the stress in ay is a compression. If M is negative, the stress is a tension. (It must be remembered that the forces whose moments make up the bending moment M act upon the portion of the truss to the left of the section.)

This method applies equally well to the case in which no two of the members cut are parallel. It is an application of a principle of much importance in the determination of stresses in truss members.

§ 3. *Truss with Parallel Chords sustaining Concentrated Loads.*

141. **General Method.** — It was shown in Art. 139 that when both chords of the truss are horizontal, so that a vertical section through the truss will cut but one inclined member, the stress in such an inclined member may be easily found from the external shear in the section. Hence for such a truss, we may determine the greatest stresses in the web members by constructing the curve of maximum shear for the truss, in a manner similar to that employed in Art. 127 for a beam.

Again, the curve of maximum bending moments will usually enable us to determine the greatest chord-stresses (Art. 140).

The construction of these curves for the case of a truss is not quite so simple as in case of a beam, for reasons to be explained in the following article.

142. Distribution of Loads on Truss. — If the curves of maximum shear and moment for a given series of concentrated loads be constructed as in Arts. 127 and 130, they will not represent correctly the maximum shear and moment at all points of the truss. The reason for this will be seen by considering the way in which the loads are actually applied to the truss. The roadway of the bridge is usually supported by longitudinal beams, which themselves rest upon cross-beams or girders, the latter being supported at the joints of the truss. Hence, however the loads may be distributed upon the roadway, they are borne by the truss only at the joints. But in the method used in Arts. 127 and 130 for drawing curves of shear and bending moment, it was assumed that every load rests directly upon the beam, at a point immediately under the load.

In the case of the truss, since loads are applied only at the joints, the shear at any instant is the same throughout the length of a panel. What is needed, therefore, is the greatest possible shear for each panel of the truss. For simplicity, we shall consider first the shear due to dead loads, and then that due to the live loads, taking a numerical example.

143. Problem — Numerical Data. — Assume a "through" truss of the form shown in skeleton in Fig. 50 (Pl. IV); let the span be 96 ft., the truss being divided into 6 panels of 16 ft. each. The depth is taken at 15 ft. Assume the dead load as 1100 lbs. per linear foot for the whole bridge, — one-half being borne by each truss, — of which one-third is the weight of the floor system and track, and is therefore borne by the lower chord, and the remaining two-thirds is assumed to be divided equally between the upper and lower chords. We have then for the dead loads:

Lower panel load = 5866 lbs., say 6000 lbs.

Upper panel load = 2933 lbs., say 3000 lbs.

For the moving load we will assume a train drawn by two locomotives with weights distributed as shown in Fig. 50. In

computing stresses the train will be supposed to come on the bridge from the right.

144. Shear Curve for Fixed Loads. — The curve of shears for the dead load may be constructed as follows: In Fig. 50 (Pl. IV), the line X,Y , represents the axis of abscissas for the shear curve. The reaction at the left support, minus the dead load borne at that point, gives 24000 lbs. as the positive shear for every section between the support and the first upper panel joint. This is laid off downward from X,Y . Then passing to the right, as each load is passed, its amount must be subtracted from the shear. The result is the broken line $X'Y'$ shown in the figure.

145. Moment Curve for Fixed Loads. — To construct the bending moment curve for dead loads, we have only to draw a funicular polygon for these loads and the reactions due to them; the vertical ordinate at any section will represent the bending moment at that section. The actual value of the bending moment is the product of the ordinate into the pole distance; the former being measured in linear units, the latter in force units. The curve is shown in Fig. 50 (Pl. IV), the ordinates being laid off upward from the line $X_m Y_m$. The force polygon is shown at W , the pole being O , taken opposite the middle point of the load-line in order that the closing side of the funicular polygon may be horizontal, and can therefore be made to coincide with $X_m Y_m$. The pole distance represents 120,000 lbs.

146. Actual Shear for Given Position of Moving Loads. — The shear in any panel is readily found when the position of live loads is known. We have only to apply the definition of external shear (Art. 115) as the sum of all vertical forces acting on the portion of the truss to the left of the section considered. That is, we must find the reaction at the left abutment and subtract from it the sum of the loads between the left abutment and the section. It must be noticed that any

load on the panel considered is divided between the two adjacent joints; the part supported at the left end of the panel is to be subtracted in computing the shear. The graphic construction is explained in the following articles.

[NOTE. — It will be noticed that the actual distribution of any load among the different panel points is not strictly determinate by methods heretofore treated, if the longitudinal beams supporting the floor system are continuous (supported at more than two points. See Art. 114). We shall assume the portion of such a beam between two supports to act as a simple beam. The results of this assumption are probably as reliable as could be obtained by a more elaborate discussion.]

147. Position of Moving Load for Maximum Shear in Any Panel. — The position of the moving load which will give the maximum shear in any panel may be determined graphically by repeated trials. But it is possible to deduce a simple rule which will shorten the labor very materially.

It must first be noticed that the *general* principles stated in Art. 126, in treating of beams, are equally applicable here. We know, therefore, in a general way, that in order to get the greatest positive shear in a given panel, the portion of the truss to the right should be loaded as completely as possible, while the part to the left should be free from loads. This rule is not, however, absolute. In general the foremost loads will be upon the panel in question, or possibly to the left of it, in the position of greatest shear. We shall now prove the following

Proposition. — When the shear in any panel has its greatest value, the load upon that panel is to the total load on the truss as the length of the panel is to the length of the truss.

Let XY (Fig. 51) represent the length of the truss ($=l$), and CD ($=l'$) the length of the panel. Let W = total load on truss, and W' = total load on the panel. Consider the effect of moving all the loads to the left. Evidently the reaction at X is increased and the load at C is increased. The former increases the shear in the panel, while the latter decreases it. These are the only changes which are caused in the shear by the movement of the load. Now if the position of loads is

such that the shear is a maximum, the two effects mentioned must just neutralize each other for a very small displacement of the loads. (Otherwise a small displacement in one direction or the other would increase the shear.)




Fig. 51

Let x = distance of center of gravity of W from Y and x' = distance of center of gravity of W' from D . Let R = reaction at X and P = load at C due to W' . Then

$$R = W \frac{x}{l}; \quad P = W' \frac{x'}{l'}$$

If the whole load moves any distance, x and x' both increase by the same amount. For an infinitesimal displacement,

$$dR = \frac{W}{l} dx; \quad dP = \frac{W'}{l'} dx = \frac{W'}{l'} dx.$$

Now the increment of the shear is $dR - dP$ or

$$\left(\frac{W}{l} - \frac{W'}{l'} \right) dx.$$

Since this must be zero (as stated above), we have

$$\frac{W'}{l'} = \frac{W}{l}, \quad \text{or} \quad \frac{W'}{W} = \frac{l'}{l},$$

for the position of maximum shear. The proposition is therefore proved.

The condition may be written $W = \frac{l}{l'} W'$. If the truss is divided into n equal panels, then $\frac{l}{l'} = n$, and $W = n W'$.

This principle is so simple that it is easier of application than the graphic method of repeated trials.

[NOTE. — In the above discussion it is assumed that W' and W both remain constant during the movement dx ; that is, that no load enters or leaves the panel or the whole truss. Hence the reasoning is not rigorous for a case in which the condition $W = \frac{l}{p} W'$ requires a load to be at C or D , or at X or Y . The remark made in the note in Art. 129 applies here. The condition $W = \frac{l}{p} W'$ may always be applied provided a load at any joint may be treated as if divided between the adjacent panels in any desired ratio.]

148. Construction of Curve of Maximum Shear. — In Fig. 50 (Pl. IV) are shown the lines of action of the series of moving loads to be carried by the truss. The force polygon or load line is drawn for the whole series of loads, being the line ABC For the purpose of drawing the funicular polygon, the uniformly distributed load is divided into parts of 6000 lbs., each assumed to act at its center of gravity. With a pole O (the pole distance being taken so as to represent 120000 lbs.) the funicular polygon is drawn for the series of loads. Let us now consider the greatest shear in any panel of the truss, as in KL (Fig. 50).

Applying the principle already deduced, it is easily shown that the greatest shear occurs when the load CD is at the point L . For, suppose CD is just at the left of L ; the total load on the panel is then 38000 lbs., while the total load on the truss is 172000 lbs. Now the ratio of the whole span to the panel length $\left(\frac{l}{p}, \text{ Art. 147}\right)$ is 6; and since 38000 lbs. is greater than one-sixth of 172000 lbs., the load on the panel is too great to satisfy the required condition. Again, suppose CD is just at the right of L ; the total load on the panel is 23000 lbs., which is less than one-sixth of 172000; hence the load on the panel is too small to satisfy the condition for maximum shear. We conclude, therefore, that the shear is a maximum when the load CD is just at the point L . In Fig. 50, S_2S_2 represents the beam with load CD at L . Drawing vertical lines through the ends of S_2S_2 , the points in which these intersect the strings oa and of' determine two points of the closing string (of_2) of the funicular polygon for the loads and reactions now acting on the

truss. The ray OJ_2 is drawn parallel to this closing line, intersecting the load line in J_2 . This determines J_2A as the left reaction. To get the shear in the panel, we must subtract from this reaction the portion of the two loads AB, BC , which comes upon the truss at K . This portion is found by treating KL as a simple beam and determining the reactions at K and L due to loads AB and BC . Draw vertical lines through the points K and L of the truss (in the position S_2S_2); the points in which these verticals intersect the strings oa and oc are two points of the closing side of the funicular polygon for the loads and reactions on the beam KL . Parallel to this closing side draw a ray OJ_2' . This line divides the load line AC into two segments representing the portions of AB and BC supported on the truss at K and L respectively. Hence the shear in the panel is the reaction J_2A minus the load represented by the line AJ_2' .

Taking X, Y , (Fig. 50) as the axis of abscissas for the curve of shears, the portion of the curve of maximum shear corresponding to the panel KL is a straight line parallel to X, Y , at a distance from it equal to J_2J_2' .

The curve of greatest shear for the whole truss is shown in the figure, being the broken line $X''Y$, but the construction is given only for the panel KL . For other panels the method will be exactly similar.

149. Position of Load for Maximum Bending Moment. — In computing stresses in the chord members, the greatest bending moment is needed for each vertical section containing a chord joint. In considering the position of moving loads which will give the greatest bending moment at any section, the sections through joints carrying live loads must be treated separately from those through joints free from loads.

Let Fig. 51 represent a through truss (Art. 137), and consider first the bending moment at a section containing one of the lower joints, as C . It is readily seen that for such a

section the bending moment due to a load anywhere on the truss is exactly the same as if the truss were a beam upon which the load was supported directly. For, consider a load on any panel as BC . Though the load is actually divided between B and C , the reaction it causes at X is the same as if the truss were a beam supporting the load directly. Also, since the load is the resultant of the two parts at B and C , the sum of the moments of these two parts about any origin is equal to the moment of the load itself. Now, in computing bending moment caused by the given load at any section, we take the moment of the left reaction minus the part of the load which is carried at the left of the section. If the section is anywhere *except between B and C* , the result is the same whether we use the given load in its actual position, or its two components at B and C .

For finding the greatest bending moments at the sections A , B , C , etc., we may therefore apply the same rule as in the case of a beam (Art. 129). That is, when the bending moment for such a section is a maximum, the loads on the two segments of the truss are proportioned to the lengths of the segments.

Next consider a section somewhere between two loaded joints, as at C' (Fig. 51). The principles above stated hold for such a section for loads anywhere *except on the panel BC* . In case of a load on this panel, only a part is borne at the left of C' ; and, in computing bending moment, the part coming at C is to be omitted. Hence the above reasoning is not strictly applicable to this case. The following modification of the principle above deduced may however be shown to hold for any section of the truss.

Let the given section divide a panel BC into segments BC'' and $C''C$. Then, *if all loads on BC are treated as if divided between B and C in the ratio of BC'' to $C''C$, the general rule applicable to a beam may be used in assigning the position of loads for maximum bending moment.*

[The proof of this proposition will be omitted. The mode

of reasoning to be applied is similar to that used in Art. 147. The student should attempt the proof for himself.]

In general, the error will be small if the bending moment curve for the case of a beam is used in computing bending moments at all panel joints of the truss.

150. Curve of Maximum Bending Moments.—The greatest bending moment at any section can be easily found as soon as the position of moving loads producing it is known: The method will be explained with reference to the truss shown in Fig. 50 (Pl. IV).

By Art. 149, the greatest bending moment for each of the points K, L, M, N, P , is exactly the same as if the truss were a beam upon which the loads were supported directly. It is unnecessary to show the construction for these points, it being identical with that of Art. 130. We therefore consider a section through an upper joint as T . First the position of the moving load must be assigned.

By Art. 149, we may apply the general principle that the loads in the two segments of the truss should be in the same ratio as their lengths, provided all loads on the panel MN are treated as if equally divided between M and N (since the section considered divides MN into equal parts). Again, since the segment of the truss to the left of the section is seven-twelfths of the whole span, the load on the left segment should be seven-twelfths the total load on the truss.

It is found by trial that the condition for maximum bending moment at T is satisfied when the line of action $b'c'$ is at M . For, the total load on the truss, when the load is near this position, is 182000 lbs. Now suppose the load $B'C$ is just at the left of M . The three loads, $C'D', D'E', E'F'$, must be regarded as equally divided between M and N ; this gives for the whole load to the left of T 111500 lbs., which is greater than seven-twelfths of 182000 lbs. But if $B'C$ is just at the right of M , half of it must be regarded as borne at N , and the whole load

on the truss to the left of T is 104000 lbs., which is less than seven-twelfths of 182000 lbs.

Now draw M, M_i to represent the beam in the position for maximum bending moment at T ; that is, with the load $B'C'$ at M . From its extremities draw vertical lines intersecting the strings od and oc'' , and through the points thus determined draw ot' , the closing side of the funicular polygon for all the loads and reactions acting on the truss.

In determining the bending moment by the method of Art. 130, we must consider the loads on the panel MN as replaced by their components at M and N respectively. Draw vertical lines through M and N intersecting the strings oc' and of' , and join the points thus determined. The line thus drawn should replace the corresponding portion of the funicular polygon before drawn (*i.e.*, the strings oc' , od' , oe' , and a part of of'); because it is, in fact, a line of the funicular polygon which will be obtained if $C'D'$, $D'E'$, and $E'F'$ be replaced by their components which are actually applied to the truss at M and N . We now draw through T a vertical line intersecting ot' and the corrected string just determined. The intercept thus determined, multiplied by the pole distance, gives the bending moment at T .

From $X_m Y_m$ as a line of reference draw downward an ordinate at the point T equal to the intercept thus found; this gives a point of the curve of maximum bending moments.

Other points of the curve may be found in the same way. The whole curve is shown in the figure, but the construction is not given except for the section T .

[NOTE. — The condition for maximum moment at a section may sometimes be satisfied for more than one position of the moving load. This is the case for the section at T ; it will be found by trial that the condition is satisfied when the load $C'D''$ is just at the right end of the truss. The bending moment for this position is, however, found to be slightly less than for the position above taken. In most cases, the position for greatest moment can be very nearly predicted by remembering that the truss should be loaded as completely as possible, and that the heavy loads should be as near the section as possible. These principles will also serve as a guide in distinguishing whether the moment is a maximum or a minimum when the condition is satisfied.]

It should be noticed that the value found for the bending moment at any section is a possible value for another section equally distant from the middle point of the truss, since the train may cross the bridge from the left instead of from the right. Hence for two points, as L and N , equally distant from the middle of the truss, the greater of the two moments above determined must be used for both.

151. Shear and Moment Curves for Combined Fixed and Moving Loads. — In Fig. 50 (Pl. IV) the line XY , has been taken as the axis of abscissas for the curves of shear. Positive shear has been laid off downward for fixed loads and upward for moving loads. Hence an ordinate at any point drawn perpendicular to XY , and limited by the two curves (or rather broken lines), represents the greatest positive shear due to combined fixed and moving loads. The shear curves for fixed and moving loads intersect at a point directly opposite the joint N . Hence for sections to the right of this point, the shear is always negative.

Similarly, $X_m Y_m$ is the axis of abscissas for the two moment curves. The bending moment is always negative; in case of the dead load curve, it is laid off upward from $X_m Y_m$, while for the live load curve it is laid off downward. Hence an ordinate between the live and dead load curves at any point of $X_m Y_m$ represents the greatest possible bending moment at the corresponding section of the truss.

We are now prepared to determine maximum stresses in the truss members.

152. Maximum Stresses in Web Members. — The greatest stress in any web member is readily found from the shear curve. By Art. 139, the stress has such a value that its resolved part in the vertical direction is equal to the shear in a section through the member. For example, for the member 14-15 we draw a line in the shear diagram parallel to 14-15 and limited by the two lines which determine the greatest shear

sustained by the member. This gives $14'-15'$ as the stress in the given member. In the same way, $12'-13'$, $13'-14'$, etc., represent stresses in the corresponding truss members.

As to the sign of the stress in any member, we know that for a positive shear any diagonal member has to resist a tendency of the portion of the truss to the left to move upward; hence the stress is a tension for every member sloping downward from left to right (as $13-14$), and a compression for a member sloping downward from right to left (as $14-15$). The reverse will be true if the shear is negative. We may, however, neglect the negative shears given by the curve of Fig. 50, because they are the minimum negative shears. (This is evident because they were determined as maximum positive shears; and since they are found to be really negative, they are the least negative shears that can occur at those sections.) The *maximum* negative shear for this portion of the truss will be found when the train crosses the bridge from left to right; and its value for any section is the same as that of the greatest positive shear for the section equally distant from the middle of the truss but on the other side.

For example, since we have found a negative shear in sections through the member $21-22$, that member sustains a compression which is represented in the figure by $21'-22'$. But if the train is headed to the right, the member $21-22$ may sustain a much greater compression—equal, in fact, to that already found for $14-15$, and represented by $14'-15'$. The latter is therefore the *greatest* compression sustained by $21-22$.

It is evident, therefore, that it is necessary to determine stresses from Fig. 50 for those members only which sustain positive shear; remembering that the stress thus found in any member is a possible value of the stress in the corresponding member on the other side of the center of the truss.

If both maximum and minimum stresses are desired, it must be remembered that the dead-load stresses may occur alone.

It will be seen that a reversal of stress may occur in the

members 16-17, 17-18, 18-19, 19-20; while in the remaining members no reversal is possible.

153. Maximum Chord Stresses. — From the maximum bending moments represented in Fig. 50, we may readily find the greatest stress sustained by any chord member. Consider, for example, the member 15-2. If a section be taken cutting the three members 7-14, 14-15, and 15-2, and the origin of moments be taken at R , it is evident that the sum of the moments of the reaction and loads to the left of R is equal to the moment of the force acting in the member 15-2. But the former is the bending moment in the section through R , and its greatest value is equal to the ordinate between the two moment curves already drawn, multiplied by the pole distance. Hence we have the equation :

Ordinate of moment curve \times pole distance = stress in chord member \times depth of truss.

That is, in the present example, the stress in pounds is equal to the ordinate multiplied by 120000 and divided by 15. The computation may be made graphically as follows: From any point Z (Fig. 50) draw two lines making a convenient angle with each other, say a right angle. Lay off ZZ'' equal to the pole distance on the force scale already adopted, and ZZ' equal to the depth of the truss, and draw $Z'Z''$. Then take $Z2$ equal to the ordinate of the moment curve and draw $2-15$ parallel to $Z'Z''$, intersecting ZZ'' in the point marked 15. The distance $Z-15$ represents the stress in 15-2, to the force scale already adopted.

If the pole distance ZZ'' had been drawn to some other scale, $Z-15$ would represent the required stress to the same scale.

For two chord members symmetrically situated with respect to the middle of the truss, the maximum stresses have the same value, which is to be computed from the greater of the two corresponding values of the bending moment. This is apparent, if it is remembered that when the train is headed to the right,

the two members interchange their conditions. The figure shows all the chord stresses. Evidently, all upper chord members are in compression and all lower ones in tension.

If minimum stresses are desired, they will be found by using the dead-load bending moments alone.

The computation of chord stresses will be facilitated if the number of force units in the pole distance is taken as a simple multiple of the number of linear units in the depth of the truss. For, if H is the pole distance, h the depth of truss, y the ordinate of the moment curve, and x the stress in the chord member, we have

$$Hy = hx; \text{ or } x = \frac{H}{h}y.$$

Now if $\frac{H}{h} = n$, we have only to measure y in linear units, multiply by n , and the result is x in force units.

§ 4. *Parallel Chords — Uniformly Distributed Moving Load.*

154. Distribution of Load. — In designing highway bridges, it is usual to assume the moving load to be uniformly distributed along the bridge. The same assumption is sometimes made for railroad bridges. This simplifies the computation of stresses very materially. In fact, when the chords are parallel, the algebraic method of treating such cases becomes so simple that it is by many preferred to the graphic method. It will be well, however, to indicate the main points in the graphic construction.

Maximum shear. — First it may be noticed that the position of moving load for greatest shear in any panel is readily determined. The conclusion deduced in Art. 147 may be shown to apply to this case; hence we have the principle that the greatest shear in any panel occurs when the portion of the truss to the right is completely loaded, while the load on the panel is the same fraction of the whole load that the panel length is of the whole span. Let XY (Fig. 51) represent a truss of

seven equal panels; and for the greatest shear in a panel CD let Z be the foremost point of the moving load. Then we must have ZD equal to one-seventh of ZY ; or, $ZD = \text{one-sixth } DY$. A similar rule applies to each panel.

Maximum moment.—From the principles deduced in Arts. 129 and 149, it is evident that the greatest bending moment occurs at every section when the moving load covers the whole bridge.

Funicular polygon.—In order to draw the funicular polygon, it is practically necessary to substitute concentrated loads for the uniformly distributed load. In determining shear, we ought strictly to have the true funicular polygon for the distributed load; since without it we cannot graphically determine the amount of load actually carried at each joint. It will, however, be sufficiently correct to subdivide the load into small portions, each being assumed concentrated at its center of gravity.

The student will readily carry out the construction just outlined, every step being similar to the corresponding part of the process shown in Fig. 50 (Pl. IV).

155. Assumption of Equal Panel Loads.—The determination of stresses, whether graphically or algebraically, is simplified by an approximate assumption which will now be explained. This assumption is that the moving load on the truss at any instant consists of equal loads concentrated at the panel joints; each load being equal to the total load on a length equal to half the sum of the two adjacent panels. Thus, in Fig. 51, in computing the shear in the panel AB , we assume full panel loads at B , C , D , E , and F ; and similarly for any other panel. The shear will then be equal to the reaction at X due to the series of loads to the right of the panel considered, and the moment curve will be simply a funicular polygon drawn for a series of full panel loads at all the joints.

It will be seen that the error involved in the above assumption is on the side of safety, so far as the web members are

concerned, since it gives greater values of the shear than the more exact method. In case of the bending moments, the results are correct for all joints of the loaded chord. For the other joints there will be a slight error. This error will be avoided, if, in drawing the funicular polygon, the load be considered as partly supported at points in the same vertical lines with the joints of the unloaded chord; thus, in Fig. 51, equal loads should be assumed to act at all the points A' , A , B' , B , etc.

The construction just indicated will not be here shown, being very similar to that explained in the following articles for the case of a truss with non-parallel chords.

§ 5. *Truss with Curved Chords — Uniform Panel Loads.*

156. General Statement. — If the upper and lower chords of the truss are not parallel, the determination of the stresses is somewhat less simple than in the case of parallel chords. But when the live load is taken as uniformly distributed along the bridge, and applied to the truss in the way explained in Art. 155, the graphic construction for finding the maximum stresses is not difficult; and is much less laborious than the algebraic computation.

In Fig. 52 (Pl. V) is shown a truss with curved chords, divided into equal panels. It will be seen that the method given in the following articles applies equally to the case of unequal panel lengths.

The principle of counterbracing will be employed here, the diagonals being constructed to sustain tension only.

157. Dead Load Stresses. — The dead load stresses may be determined by means of a stress diagram, as in the roof-truss problems already treated. Two points should be observed in drawing this diagram. (1) If dead loads are taken to act at upper as well as at lower joints, the force polygon for the loads and reactions must show these forces in the same order as that in which their points of application occur in the perimeter of

the truss. (2) The diagonal members assumed to act are taken as all sloping in the same direction.

The reason for the first point is the same as already explained in Art. 90, — viz., that unless the forces be taken in the order mentioned, the stress diagram cannot be the true reciprocal of the truss diagram and certain lines will have to be duplicated. The reason for assuming the diagonals as all sloping in the same way is the same as in the case of the roof truss with counterbracing (Arts. 111 and 112).

The dead load stress diagram is not shown, since its construction involves no principle not already fully explained and illustrated.

158. Chord Stresses Due to Live Load.—It can be easily shown that a load at any point of the truss produces tension in every lower chord member and compression in every upper chord member. Thus, referring to Fig. 52 (Pl. V), let a load act at fg , and let us determine the kind of stress caused in the member qq' . Take a section cutting qq' , $q'a'$, $d'd$. Considering the portion of the truss to the right of the section, the only forces acting on it are the reaction at the support and the forces in the three members cut. Apply the principle of moments to this system of forces, taking the origin at the point of intersection of $q'a'$ and $d'd$. It is evident that qq' must be in compression to resist the tendency of the reaction to produce left-handed rotation about the origin. By similar reasoning, assuming a load at any other point, the student will be able without difficulty to verify the general statement above made.

It follows that in order to get the greatest possible stresses in the chord members, the truss should be fully loaded. Hence, to find the live-load chord stresses, a convenient method is to draw a stress-diagram for the truss under all live loads. This diagram is not shown.

159. **Live Load Stresses in Web Members.** — When the diagonals and verticals are considered, it will be found that loads in different positions may cause opposite kinds of stress in any member. Thus, considering the member $f'n'$, it is easy to show that a tension is caused in it by a load at either of the points ab , bc , cd , de , or ef , while a compression is caused by a load at fg , gh , or hi . (This may be shown by taking a section through ff' , $f'n'$, and $n'u$, and taking moments about the point of intersection of the two chord members cut.) Similarly, loads at ab , bc , cd , de , and ef all tend to throw compression on the vertical member $f'm'$, while loads at fg , gh , and hi have the opposite tendency.

Therefore, to produce the greatest tension upon $f'n'$ (and compression on $f'm'$), the live load must act only at ef and all joints to the right; while to cause the greatest compression on $f'n'$ (and tension upon $f'm'$), the live load must act only at fg , gh , and hi . A similar statement will hold regarding any other web member. Since counterbraces are to be used in all panels in which diagonal members would otherwise be thrown into compression, we shall need only to consider the greatest tension in each diagonal and the greatest compression in each vertical. We shall first outline the method to be employed, and then explain the construction.

To determine the greatest tension in a diagonal member, as $g'm'$: Assume the live load to come upon the bridge from the right until there are full loads at the joints ab , bc , cd , de , ef , and fg . Take a section cutting $g'm'$ and the two chord members gg' and $m'm$, and consider the forces acting upon the portion of the truss to the left of the section. These forces are four in number: the reaction at the support and the forces acting in the three members cut. Hence we first determine the reaction, and then determine the three other forces for equilibrium by the method of Art. 42.

The construction is shown in Fig. 52 (Pl. V). $ABCDEFGHI$ is the force polygon for the eight live loads that may come

upon the truss. Choosing a pole O , the funicular polygon for the eight loads is next drawn. Now, turning the attention to the member $g'm'$, the loads gh and hi are assumed not to act. The reactions at the supports for this case of loading are found in the usual way. Prolong oa and og to intersect the lines of action of the two reactions, and join the two points thus determined. This gives the closing line of the funicular polygon (or om). The ray OM is now drawn parallel to the string om , and the two reactions are GM and MA .

Now take a section through mm' , $m'g'$, and $g'g$, and apply the construction of Art. 42 to the determination of the forces acting in the three members cut. The resultant of GM and the force in gg' must act through the point X (the intersection of gg' produced and ij). The resultant of the forces in mm' and $m'g'$ must act through their intersection Y . Hence these two resultants (being in equilibrium with each other) must both act in the line XY . From G draw a line parallel to gg' , and from M a line parallel to XY ; mark their point of intersection G' . Then MG' is the resultant of the forces in mm' and $m'g'$. From M draw a line parallel to mm' , and from G' a line parallel to the member $g'm'$, and mark their point of intersection M' . Then $M'G'$ represents the force in the member $m'g'$. This is also the value of the greatest stress in $m'g'$.

To determine the stress in the vertical member $l'g'$, the same loading must be assumed, and a similar construction is employed. Take a section cutting ll' , $l'g'$, and $g'g$, and determine forces acting in these three lines which shall be in equilibrium with the reaction GM . This reaction is in equilibrium with MG' and $G'G$, the former having the line of action XY . Then MG' is resolved into two forces having the directions of the members $g'l'$ and $l'l$. The stress in $g'l'$ is found to be a compression, represented in the stress diagram by the line $G'L'$.

The maximum live load stress in every web member may be found in the same way. If the above reasoning is understood, there will be no difficulty in applying the same method to the remaining members.

160. **Maximum Stresses.** — By combining the stresses due to live and dead loads, the maximum stresses are easily determined.

Web members. — When the web members are considered, the effect of counterbracing needs careful attention.

The construction above explained gives the greatest live load tension in each diagonal. It may be that for certain members, this tension is wholly counterbalanced by the dead loads. In any panel in which this is the case, the member shown will never act and may be omitted. The counterbrace must then be considered.

Evidently, the algebraic sum of the stresses due to live and dead loads will be the true maximum tension in each of the diagonals shown. For the greatest tension in the other system of diagonals, the load must be brought on the bridge from the left; or, what amounts to the same thing, the tension already found for any one of the diagonals shown is also the greatest tension in the diagonal sloping the opposite way in the panel equally distant from the middle of the truss. (In fact, the stresses in all members due to a movement of the loads from left to right may be obtained from the results already reached, by consideration of symmetry.)

As to the vertical members, two values of the stress must be compared in every case — namely, the greatest compressions corresponding to the two directions of the moving load. But both can be obtained from the above results by considering the symmetry of the truss. For example, the stress found for $l'g'$ is a possible value for the stress in $r'b'$, and must be compared with the value obtained for the latter member when the load moves from right to left. It is possible, also, that certain of the verticals may be in tension when the dead loads act alone.

Maximum chord stresses. — These are found by combining the stresses due to fixed and moving loads, determined as already described.

161. **Example.** — The following example should be carefully solved, following the method outlined in the preceding articles.

Given the span, 120 ft.; lower chord straight; upper chord circular with rise at middle point of 20 ft.; panel length, 15 ft.; diagonals counterbraced to sustain tension only; width of bridge between trusses, 18 ft. Assume dead load from the formula of Art. 135, one-third applied at upper chord and two-thirds at lower. Live load 85 lbs. per square foot. Determine maximum stresses due to live and dead loads.

162. **Parallel Chords.** — It will be noticed that all the methods which have been described for the discussion of trusses with curved chords are applicable to the case of parallel chords. In fact, the determination of stresses in web members is simplified when both chords are horizontal; for, after the reaction is found as in Art. 159, it is only necessary to so determine the stress in the web member that its vertical resolved part shall equal the reaction.

§ 6. *Truss with Curved Chords—Concentrated Loads.*

163. **Comparison of Cases.** — When the moving load consists of a series of unequal weights, the non-parallelism of the chords somewhat complicates the determination of stresses. This case can, however, be treated without great difficulty, as will now be explained.

For the determination of chord stresses the method will be almost exactly the same as in the case of parallel chords already discussed. It is only necessary to determine the greatest bending moment at each joint, just as was done in Art. 150, and then find the chord stresses by the principle of moments.

But for the determination of web stresses the shear curve is not sufficient, since the shear in any section is not borne wholly by the web member, but partly by the inclined chord member. Moreover, the position of the moving load which will produce

the greatest shear in a panel is not generally the position which causes the greatest stress in the web member in that panel.

164. Position of Loads for Greatest Stress in a Web Member.

— We shall now deduce a rule for determining what position of the loads will produce the greatest stress in any web member. Let XY (Fig. 53) represent the truss and the member con-




Fig. 53

sidered. We know in a general way (Art. 159) that for the greatest tension in $B'C$ the truss should be completely loaded on the right of the panel BC .* Let W = total load on truss; W' = load on panel BC ; l = total length of truss; l' = length of panel BC ; x = distance from Y to center of gravity of W ; x' = distance from C to center of gravity of W' . Prolong the two chord members of the panel to intersect at Z , and let $XZ = a$, $ZB = b$. Let R = reaction at X , and P = portion of W' carried at B . Then

$$R = \frac{Wx}{l}; \quad P = \frac{W'x'}{l'}.$$

Now if the truss be separated by a section cutting $B'C$ and the two chord members, it is seen that the moment of the stress in $B'C$ about Z must equal the sum of the moments of R and P about Z . Hence the stress in $B'C$ is greatest when the sum of the moments of R and P about Z is greatest. Let M = that sum, then

$$M = Ra - Pb = \frac{Wa}{l}x - \frac{W'b}{l'}x'.$$

* This statement is true for all forms of truss considered in this work. If the two chord members in any panel intersect between the vertical lines through the ends of the truss, the statement no longer holds. The effect on the web member of a load in any position can be determined very easily, whatever the form of the truss, by reasoning similar to that employed in Art. 159.

If M is a maximum, we must have $\frac{dM}{dx} = 0$. But since $dx' = dx$, we have,

$$\frac{dM}{dx} = \frac{Wa}{l} - \frac{W'b}{l'} = 0; \text{ or } W = \frac{b}{a} \cdot \frac{l}{l'} \cdot W'.$$

The ratio $\frac{b}{a}$ will be known for each panel, and also the ratio $\frac{l}{l'}$; hence the condition expressed by the equation can be easily applied.

It may happen that the condition is satisfied for more than one position of the loads. If this is so, such positions must all be tried and the results compared. This is illustrated in the following article.

Special case. — It will be noticed that if the chords approach parallelism, the point Z moves farther away and the limit approached by $\frac{b}{a}$ is unity. Hence, for the case of parallel chords, the equation becomes $W = \frac{l}{l'} W'$. This is identical with the result already given in Art. 147.

[NOTE. — The remarks made in the note in Art. 147 apply also to the reasoning just given. It is also to be noticed that we have assumed that no load is between B and X . If the condition above deduced cannot be satisfied without carrying the foremost load or loads to the left of B , we may reason thus: Let W'' = load to left of B ; x'' = distance of center of gravity of W'' from B . Then

$$M = Ra - Pb - W''(b - x'') = \frac{Wa}{l}x - \frac{W'b}{l'}x' - W''(b - x'').$$

Differentiating, remembering that $dx'' = dx' = dx$, we have

$$\frac{dM}{dx} = \frac{Wa}{l} - \frac{W'b}{l'} + W''.$$

Placing this equal to zero, we have

$$W = \frac{b}{a} \cdot \frac{l}{l'} W' - \frac{l}{a} W''.$$

Usually W'' will be zero and the equation first deduced will apply, but if necessary the last equation may be used. For the case of parallel chords, the term $\frac{l}{a} W''$ disappears, since $\frac{l}{a}$ approaches zero.]

165. Determination of Web Stresses. — The method of determining web stresses for the case now under consideration is shown in Fig. 54 (Pl. V). The force polygon and funicular polygon for the series of wheel loads is drawn in the usual manner. The span of the truss here taken is 120 ft., divided into eight equal panels, the upper chord being curved, while the lower (supporting the floor system and moving loads) is straight. Half of the truss is shown at XY , drawn to the same scale used in the space diagram for the moving loads. The construction is shown for finding stresses in the two members tu and uv . First consider the latter.

To apply the rule of the preceding article for finding the required position of loads, determine the ratio $\frac{b}{a}$. Prolonging the two chord members ku and vm till they intersect at Z_2 , we find $\frac{Z_2Q}{Z_2X} = \frac{b}{a} = 2$. Also we have $\frac{l}{l'} = 8$. Hence, for the greatest stress in uv , the load on the panel QR must equal one-sixteenth the load on the whole truss. Now it is easily seen that this condition is satisfied when the second load is at the point R . For, in this position, the whole load on the truss is 123750 lbs. If the second load is just at the left of R , the load on the panel is 20000 lbs., which is greater than one-sixteenth of 123750 lbs.; but if the second load is just at the right of R , the load on the panel is 7500 lbs., which is less than one-sixteenth of 123750 lbs.

We are now ready to determine the stress in the member uv . The general method is to cut the truss by a section through ku , uv , and vm ; determine the resultant of all forces on the truss to the left of the section; and then determine three forces in the members cut which shall be in equilibrium with that resultant.

The forces acting on the truss to the left of the section are the reaction at the support and the portion of the foremost load AB carried at the point Q . Their resultant is found as follows: Draw X_uX_u to represent the span when the load BC is

at R ; then draw the closing line of the funicular polygon for the forces now on the truss, and from O draw the ray parallel to this closing line. The end of this ray is marked M_1 , and the left reaction is represented by the line M_1A . Next replace AB by its two components borne at Q and R . These are determined by drawing verticals from Q and R intersecting the strings oa and ob in Q' and R' ; then $Q'R'$ is the string which must replace oa and ob . (The portions of the funicular polygon to the right of R' and to the left of Q' are not changed by thus replacing AB by its two components at Q and R .) Now by drawing from O a ray parallel to $Q'R'$ we find the point (marked K_1) which divides AB into the two components at Q and R .

The resultant of the reaction at X and the load at Q is given in magnitude by M_1K_1 . We need also its line of action, which is found as follows: Prolong $Q'R'$ and om_1 (the closing string of the funicular polygon for all the forces on the truss) until they intersect in z' ; the required line of action is a vertical line through z' . This vertical line intersects X_wX , produced in z . We now locate the point z in the truss diagram by making $Xz = X_wz$ in the diagram above.

We have now to solve the following problem: Determine three forces acting in lines ku , uv , and vm , which shall be in equilibrium with a force equal to the resultant just found and acting upward in a line through z . This is solved by the method of Art. 42. Draw KM equal to the given force acting at z . Draw zQ' , and determine two forces, one parallel to zQ' and the other to ku , which shall be in equilibrium with KM . This gives UK as the force in the line uk and MU as the resultant of the forces in the lines mv and vu . From M and U draw lines parallel to mv and vu respectively, and mark their intersection V ; then MV and VU represent the stresses in the corresponding truss members. The latter is evidently the required stress in the member uv .

Turning next to the member tu , a section through it will cut

the two chord members ku and mt ; these intersect at Z_1 . By measurement we find $\frac{b}{a} = \frac{Z_1Q}{Z_1X} = 6$, and $\frac{l'}{l} \cdot \frac{b}{a} = 8 \times 6 = 48$. Therefore, for the greatest stress in tu we must have the load on the panel QR equal to the whole load on the truss divided by 48. This condition is seen to be satisfied when the foremost load is at R . Since in this case there is no load borne to the left of R , the only force acting on the truss to the left of a section through tu is the reaction at the support. To find this, draw X_1X_2 to represent the length of the truss for the required position of the loads, and find om_1' , the closing string of the funicular polygon for all loads and reactions on the truss. The corresponding ray is OM_1' , and $M_1'A$ represents the reaction at the left support.

Referring now to the truss diagram, we have to determine forces acting in the three lines mt , tu , uk , which shall be in equilibrium with the reaction just determined. Lay off $K'M$ to represent this reaction; draw a line from K' parallel to ku and one from M parallel to $Q'X$, and mark their point of intersection U' ; then $U'K'$ represents the force in uk , and MU' the resultant of the forces in mt and tu . From M draw a line parallel to mt and from U' a line parallel to ut , intersecting at T ; then TU' represents the required stress in tu .

The value just determined is the true maximum stress for the member tu . In case of the member uv , however, further investigation is needed. It will be found by trial that the condition $W = \frac{b}{a} \cdot \frac{l}{l'} \cdot W'$ is satisfied for the member uv , not only when the loads have the position already treated, but also when the foremost load is at R . Hence the stress in uv for this position of the loads must be determined and compared with the one already found, namely UV . For this case of loading the only force acting on the truss to the left of a section through uv is the reaction (already found when considering the member tu) represented by $K'M$. Making this in equilibrium with three forces whose lines of action are ku , uv , vm , we find

$U'V'$ as the stress in uv . Comparison shows that this is slightly greater than UV ; hence the value last found is the true maximum for the member uv .

The construction for each of the other web members is exactly similar. If both chord members in any panel are inclined, the construction requires only slight modification, which the student will readily supply.

In case the intersection of two chord members cannot conveniently be found by prolonging them, the distances a and b can be easily computed from the dimensions of the truss.

Remark. — It will often be found that two web members related as are tu and uv , will not sustain their maximum stresses at the same time. In the case of parallel chords this could not occur.

166. **Minimum Stresses.** — In what precedes, little has been said of minimum stresses in the truss members. If, however, the design is to be made in accordance with the theory of the strength of materials under repeated alternations of stress, the minimum stress sustained by each member becomes important. In all the cases treated in the present chapter, the minimum stresses can be determined without difficulty, without the use of additional principles.

PART III.

CENTROIDS AND MOMENTS OF INERTIA.



CHAPTER VIII. CENTROIDS.

§ 1. *Centroid of Parallel Forces.*

167. **Composition of Parallel Forces.** — The composition of coplanar parallel forces can always be effected by means of the funicular polygon, by the method of Art. 27. It is now necessary to consider parallel systems more at length, as a preliminary to the discussion of graphic methods for determining centers of gravity and moments of inertia.

168. **Resultant of Two Parallel Forces.** — Let ab and bc (Fig. 55) be the lines of action of two parallel forces, their magnitudes being AB and BC (not shown). Let ac be the line of action of their resultant, and AC (not shown) its magnitude. By the principle of moments (Art. 50) the sum of the moments of AB and BC about any point in their plane is equal to the moment




Fig. 55

of AC about the same point. If the origin of moments is on ac , the moment of AC is zero; and therefore the moments of AB and BC are numerically equal (but of opposite signs).

Let any line be drawn perpendicular to the given forces, intersecting their lines of action in P' , Q' , and R' respectively. Then $AB \times P'R' = BC \times Q'R'$.

Let any other line be drawn intersecting the three lines of action in P , Q , and R respectively. Then

$$\frac{PR}{P'R'} = \frac{QR}{Q'R'}$$

and therefore $AB \times PR = BC \times QR$.

That is, PQ is divided by the line ac into segments inversely proportional to AB and BC .

If AB and BC act in opposite directions, the line ac will be outside the space included between ab and bc ; but the above result is true for either case.

169. Centroid of Two Parallel Forces. — If the lines of action ab and bc (Fig. 55) be turned through any angle about the points P and Q respectively, the forces remaining parallel and of unchanged magnitudes, the line of action of their resultant will always pass through the point R . For, by the preceding article, the line of action of the resultant will always intersect PQ in a point which divides PQ into segments inversely proportional to AB and BC . Hence, if AB and BC remain unchanged, and also the points P and Q , the point R must also remain fixed.

If P and Q are taken as the points of application of AB and BC , R may be taken as the point of application of AC , in whatever direction the parallel forces are supposed to act. The point R is called the centroid* of the parallel forces AB and BC for the fixed points of application P and Q .

170. Centroid of Any Number of Parallel Forces. — Let AB , BC , and CD be three parallel forces, and let P , Q , and S (Fig. 56) be their fixed points of application. Let R be the centroid of AB and BC , and AC their resultant. Take R as the fixed point of application of AC , and determine T , the centroid of AC




Fig. 56

* The name *center of parallel forces* has been quite commonly used instead of *centroid* as above defined. The latter term has, however, been adopted by some of the later writers, and seems on the whole a better designation.

and CD . Let AD be the resultant of AC and CD ; then AD is also the resultant of AB , BC , and CD .

Now if AB , BC , and CD have their direction changed, but still remain parallel and unchanged in magnitude, it is evident that the point T , determined as above, will remain fixed and will always be on ad , the line of action of AD . The point T is called the centroid of the three forces AB , BC , and CD .

By an extension of the same method, a *centroid* may be determined for any system of parallel forces having fixed points of application. Hence the following definition may be stated:

The centroid of a system of parallel forces having fixed points of application is a point through which the line of action of their resultant passes, in whatever direction the forces be taken to act.

In determining the centroid by the method just described, the forces may be taken in any order without changing the results. For the centroid must lie on the line of action of the resultant; and since this is a determinate line for each direction in which the forces may be taken to act, there can be but one centroid.

171. Non-complanar Parallel Forces.—The reasoning of the preceding articles is equally true, whether the forces are complanar or not. In what follows we shall deal either with complanar forces, or with forces whose *points of application are complanar*. No more general case will be discussed.

172. Graphic Determination of Centroid of Parallel Forces.—If the line of action of the resultant of any system of parallel forces be found for each of two assumed directions of the forces, the point of intersection of these two lines is the centroid of the system. Moreover, if the points of application are complanar, the two assumed directions may both be such that the forces will be complanar.

Thus, let the plane of the paper be the plane containing the given points of application, and let ab , bc , cd , de , ef . (Fig. 57) be

the points of application of five parallel forces, AB , BC , CD , DE , EF . Draw through these points parallel lines in some chosen direction, and taking them as the lines of action of the given forces, construct the force and funicular polygons corre-




Fig. 57

sponding. The line of action of the resultant is drawn through the intersection of the strings oa and of , and this line contains the centroid of the given forces. Next draw through the given points of application another set of parallel lines, preferably perpendicular to the set first drawn, and draw a funicular polygon for the given forces with these lines of action. (It is unnecessary to draw a new force diagram, since the strings in the second funicular polygon may be drawn respectively perpendicular to those of the first.) This construction determines a second line as the line of action of the resultant corresponding to the second direction of the forces. The required centroid of the system is the point of intersection of the two lines of action of the resultant thus determined, and is the point af in the figure.

Example. — Find graphically the centroid of the following system of parallel forces, and test the result by algebraic computation : A force of 20 lbs. applied at a point whose rectangular coördinates are $(4, 6)$; 12 lbs. at the point $(12, 3)$; 20 lbs. at

the point (10, 10); -10 lbs. at the point (7, -9); -8 lbs. at the point (-5, -10).

173. Centroid of a Couple.—If AB and BC are the magnitudes of any two parallel forces applied at points P and Q , then by Art. 169 their centroid R is on the line PQ and is determined by the equation

$$\frac{PR}{QR} = \frac{BC}{AB}.$$

If AB and BC are equal and opposite forces, PR and QR must be numerically equal, and R must be *outside* the space between the lines of action of AB and BC . These conditions can be satisfied only by making PR and QR infinite. Hence we may say that the centroid of two equal and opposite forces lies on the line joining their points of application and is infinitely distant from these points.

174. Centroid of a System whose Resultant is a Couple.—If a system with fixed points of application is equivalent to a couple, its centroid will be infinitely distant from the given points of application. A line containing this centroid can be determined as follows:

Take the given forces in two groups; the resultants of the two groups will be equal and opposite. Find the centroid of each group, and suppose each partial resultant applied at the corresponding centroid. Then the centroid of the whole system is the same as that of the couple thus formed, and will lie on the line joining the two partial centroids.

If the separation into groups be made in different ways, different couples and different partial centroids will be found. The different couples are, of course, equivalent; and it may be proved that the lines joining the different pairs of partial centroids are all parallel, and intersect in the (infinitely distant) centroid of the whole system.

For, suppose the given system to be equivalent to a couple

Q with points of application A and B , and also to a couple Q' with points of application A' and B' . These two couples must be equivalent to each other, whatever be the direction of the forces. Let AB be taken as this direction. The two equal and opposite forces of the couple Q neutralize each other, since their lines of action are coincident; hence the two forces of the couple Q' must also neutralize each other. Therefore $A'B'$ must be parallel to AB .

175. Moment of a Force about an Axis.—The moment of a force with respect to a given axis, as defined in Art. 47, depends not only upon the point of application of the force, but upon its direction. In dealing with systems of forces whose direction may change but whose points of application are complanar, we shall need to compute moments only for axes lying in the plane of the points of application; and the forces may usually be regarded as acting in lines perpendicular to this plane. Hence we shall compute moments by the following rule:

The moment of a force with reference to any axis is the product of the magnitude of the force into the distance of its point of application from the axis.

§ 2. *Center of Gravity — Definitions and General Principles.*

176. Center of Gravity of Any Body.—Every particle of a terrestrial body is attracted by the earth with a force proportional directly to the mass of the particle. The resultant of such forces upon all the particles of a body is its *weight*; and the point of application of this resultant is called the *center of gravity* of the body. The lines of action of these forces may be assumed parallel without appreciable error. We may therefore define the center of gravity of a body as follows:

If forces be supposed to act in the same direction upon all particles of a body, each force being proportional to the mass

of the particle upon which it acts, the centroid of this system of parallel forces is the center of gravity of the body.

This point is also called *center of mass*, and *center of inertia*, either of which is a better designation than center of gravity. The latter term is, however, in more general use.

177. Centers of Gravity of Areas and Lines. — The term center of gravity, as above defined, has no meaning when applied to lines and areas, since these magnitudes have no mass, and hence are not acted upon by the force of gravity. It is, however, common to use the name center of gravity in the case of lines and areas, with meanings which may be stated as follows :

The *center of gravity of an area* is the center of gravity of its mass, on the supposition that each superficial element has a mass proportional to its area. This point would be better described as the *center of area*.

The *center of gravity of a line* is the center of gravity of its mass, on the assumption that each linear element has a mass proportional to its length. The term *center of length* is preferable, and will often be used in what follows.

Similar statements might be made regarding geometrical solids, but we shall have to deal chiefly with lines and areas.

178. Moments of Areas and Lines. — *Definition.* — The moment of a plane area with reference to an axis lying in its plane is the product of the area by the distance of its center of gravity from the axis.

Proposition. — The moment of any area about a given axis is equal to the sum of the moments of any set of partial areas into which it may be divided. For, by the definition of center of gravity, a force numerically equal to the total area and applied at its center of gravity is the resultant of a system of forces numerically equal to the partial areas and applied at their respective centers of gravity ; and the moment of any

force is equal to the sum of the moments of its components (Art. 50).

A similar definition and proposition may be stated regarding lines.

The moment of an area or line is zero for any axis containing its center of gravity.

179. Symmetry.—Two points are symmetrically situated with respect to a third point if the line joining them is bisected by that point.

Two points are symmetrically situated with respect to a line or plane when the line joining them is perpendicular to the given line or plane and bisected by it.

A body is symmetrical with respect to a point, a line, or a plane, if for every point in the body there is another such that the two are symmetrically situated with respect to the given point, line, or plane. The point, line, or plane is in this case called a point of symmetry, an axis of symmetry, or a plane of symmetry of the body.

180. General Principles.—(1) The center of gravity of two masses taken together is on the line joining the centers of gravity of the separate masses. For it is the point of application of the resultant of two parallel forces applied at those points.

(2) If a body of uniform density has a plane of symmetry, the center of gravity lies in this plane. If there is an axis of symmetry, the center of gravity lies in this axis. If the body is symmetrical with respect to a point, that point is the center of gravity. For the elementary portions of the body may be taken in pairs such that for each pair the center of gravity is in the plane, axis, or point of symmetry.

181. Centroid.—The center of gravity of any body or geometrical magnitude is by definition the same as the centroid of a certain system of parallel forces. It will be convenient,

therefore, to use the word centroid in most cases instead of center of gravity.

§ 3. *Centroids of Lines and of Areas.*

182. General Method of Finding Centroid. — The centroid of any area may be found by the following method: Divide the given area into parts such that the area and centroid of each part are known. Take the centroids of the partial areas as the points of application of forces proportional respectively to those areas. The centroid of this system of forces is the centroid of the total area, and may be found by the method of Art. 172.

The centroid of a line may be found by a similar method.


The method just described is exact if the magnitudes of the partial areas and their centroids are accurately known. If the given area is such that it cannot be divided into known parts, it will still be possible to get an approximate result by this method.

In applying this general method, it is frequently necessary to know the centroids of certain geometrical lines and figures, and also the relative magnitudes of the areas of such figures. Methods of determining these will be given in the following articles.

183. Centroids of Lines. — The centroid of a *straight line* is at its middle point.

Broken line. — The centroid of a broken line is the center of a system of parallel forces, of magnitudes proportional to the lengths of the straight portions of the line, and applied respectively at their middle points. It may be found graphically by the method of Art. 172, or by any other method applicable to parallel forces.

Part of regular polygon. — For the centroid of a part of a regular polygon, a special construction is found useful.



First, the centroid must lie on OC .

Second, to find its distance from O , assume a system of equal and parallel forces applied at the middle points of the sides AB , BC , etc. The required centroid is the point of application of the resultant of these forces. Taking MN as the axis of moments, and letting x = required distance of centroid from MN , and x_1, x_2, x_3, x_4 the distances of the middle points of AB , BC , etc., from MN , we have from the principle of moments,

$$lx_1 + lx_2 + lx_3 + lx_4 = sx.$$

But if Ab and Bb be drawn perpendicular respectively to PQ and MN we have from the similar triangles ABb , POQ .

$$\frac{AB}{Ab} = \frac{PO}{PQ} \text{ or } \frac{l}{Ab} = \frac{r}{x_1}.$$

$$\therefore lx_1 = r \cdot Ab.$$

In the same way,

$$lx_2 = r \cdot bc,$$

$$lx_3 = r \cdot cd,$$

$$lx_4 = r \cdot dE.$$

$$\text{Hence, } s \cdot x = r (Ab + bc + cd + dE) = r \cdot AE,$$

where AE is equal to the projection of the broken line $ABCDE$ on MN .

The centroid G may now be found graphically as follows: Make $Oc' = r$; $ON = \frac{1}{2}s$; $OE' = \frac{1}{2}AE$; draw Nc' . Then G is determined by drawing $E'G$ parallel to Nc' .

Circular arc. — The above construction holds, whatever the length of the side l . If this length be decreased indefinitely, while the number of sides is increased indefinitely, so that the length s remains finite, we reach as the limiting case a circular arc. The same construction therefore applies to the determination of the centroid of such an arc, r denoting the radius of the circle and s the length of the arc.

184. **Centroids of Geometrical Areas.** — *Parallelogram.* — The centroid of a parallelogram is on a line bisecting two opposite sides.

Let $ABCD$ (Fig. 59) be a parallelogram, and EF a line bisecting AD and BC . Divide AB into any even number of equal parts, and through the points of division draw lines parallel to BC . Also divide BC into any even number of equal parts and draw through the points of division lines parallel to AB . The given parallelogram is thus divided into equal elements. Now




Fig. 59

consider a pair of these elements, such as those marked P and Q in the figure, equally distant from AD , and also equally distant from EF , but on opposite sides of it. The centroid of the two elements taken together is at the middle point of the line joining their separate centroids. If the number of divisions of AB and of BC be increased without limit, the elements approach zero in area, and the centroids of P and Q evidently approach two points which are equally distant from EF . Hence in the limit, the centroid of such a pair of elements lies on the line EF . But the whole area $ABCD$ is made up of such pairs; hence the centroid of the whole area is on the line EF . For like reasons it is also on the line bisecting AB and DC ; hence it is at the intersection of the two bisectors.

The point thus determined evidently coincides with the point of intersection of the diagonals AC and BD .

Triangle. — The centroid of a triangle lies on a line drawn from any vertex to the middle of the opposite side; and is, therefore, the point of intersection of the three such lines.

Let ABC (Fig. 60) be any triangle, and D the middle point of BC . Then the centroid of ABC must lie on AD . For AD bisects all lines, such as bc , parallel to BC . Now inscribe in the triangle any number of parallelograms such as $bcc'b'$, with sides parallel respectively to BC and




Fig. 60

AD . The centroid of each parallelogram lies on AD , and, therefore, so also does the centroid of the whole area composed of such parallelograms. If the number of such parallelograms be increased without limit, the altitude of each being diminished without limit, their combined area will approach that of the triangle, and the centroid of this area will approach in position that of the triangle. But since the former point is always on the line AD , its limiting position must be on that line. Therefore the line AD contains the centroid of the triangle.

By the same reasoning, it follows that the centroid of ABC must lie on BE , drawn from B to the middle point of AC . Hence it must be the point of intersection of AD and BE , which point must also lie on the line CF drawn from C to the middle point of AB .

The point G divides each bisector into segments which are to each other as 1 to 2. For, from the similar triangles ABC , EDC , since EC is half of AC , it follows that DE is equal to half of BA . And from the similar triangles AGB , DGE , since DE is half of AB , it follows that GE is half of GB , and GD half of GA .

Quadrilateral. — Let $ABCD$ (Fig. 61) be a quadrilateral of which it is required to find the center of gravity. Draw BD , and let E be its middle point. Make $EG_1 = \frac{1}{3} EA$, and $EG_2 = \frac{1}{3} EC$. Then the centroids of the triangles ABD and BCD are

G_1 and G_2 respectively. Hence the centroid of $ABCD$ is on the line G_1G_2 at a point dividing it into segments inversely proportional to the areas of ABD and BCD . Since these two triangles have a common base, their areas are proportional to their altitudes measured from this base. But these altitudes are proportional to AF and FC , or to G_1H and G_2H ; hence, if G is the required centroid,

$$G_1G : G_2G :: G_2H : G_1H.$$

Therefore G is found by making $G_1G = G_2H$.

Circular sector.—To find the centroid of a circular sector OAB (Fig. 62) we may reason as follows: Draw two radii OM , ON , very near together. Then OMN differs little from a triangle, and its centroid will fall very near the arc $A'B'$, drawn with radius equal to two-thirds of OA . If the whole sector be subdivided into elements such as OMN , their centers of gravity will all fall very near to the arc $A'B'$. If the number of such elements is indefinitely increased, the line joining their centroids approaches as a limit the arc $A'B'$. And since the areas of the elements are proportional to the lengths of the corresponding portions of $A'B'$, the centroid of the total area is the same as that of the arc $A'B'$.




Fig. 62

This point may be found by the method described in Art. 183.

185. Graphic Determination of Areas.—Let there be given any number of geometrical figures, and let it be required to determine the relative magnitudes of their areas.

If a number of rectangles can be found, of areas equal respectively to the areas of the given figures and having one common side, then the remaining sides will be proportional to the areas of the given figures.

An important case is that in which the given figures are such that the area of each is equal to the product of two known lines. In this case a series of equivalent rectangles having one common side can be found by the following construction.

Let ABC (Fig. 63) be a triangle, and let it be required to determine an equivalent rectangle having a side of given length as LM . Let b and h be the base and altitude of the triangle. Make $LN = \frac{1}{2}b$ and $LP = h$, and draw the semicircle PRN . Draw the ordinate LR perpendicular to PN ; then




Fig. 63

$$\overline{LR}^2 = PL \times LN = \frac{1}{2}bh = \text{area } ABC.$$

Draw MR , and perpendicular to it draw RQ . Then

$$\overline{LR}^2 = LM \times LQ = \text{area } ABC.$$

Hence LQ is the required length.

If the given figure is a parallelogram, LN and LP may be its base and altitude. If it be a circular sector, LN and LP may be the length of the arc and half the radius.

186. Centroids of Partial Areas. — It may be required to find the centroid of the part remaining after deducting known parts from a given area. For this case the construction of Art. 182 needs modification. In the case there considered we regarded the partial areas and the total area as proportional to parallel forces acting at their respective centers of gravity. In this case we may also represent the total area, the portions deducted from it, and the remaining portion as forces acting at the respective centers of gravity; but the forces corresponding to the areas deducted must be taken as acting in the opposite direction to that assumed for the forces representing the total area and the area remaining.

Thus, to find the centroid of the area remaining after deduct-

ing from the circle ABD (Fig. 64) a smaller circle EFH and a sector OAB , we may proceed as follows: Find the centroid of




Fig. 64.

three parallel forces proportional to the areas ABD , EFH , and OAB , and applied at their respective centroids O , C , and G ; but the last two must be taken as acting in the direction opposite to that of the first. With this understanding, the force and funicular polygons may be employed as in Art. 172.

187. Moments of Areas. — The moment of an area about any line in its plane may be determined from the funicular polygon employed in finding its center of gravity. Let the parallel forces applied at the centroids of the partial areas be assumed to act parallel to the axis of moments. Then the distance intercepted on the axis by the extreme lines of the funicular polygon, multiplied by the pole distance, is equal to the moment of the total area about the axis. For, by Art. 56, this construction gives the moment of the resultant force about any point in the given axis; and this is equal to the moment of the resultant area about the axis by definition.

A similar rule gives the moments of the partial areas.

CHAPTER IX. MOMENTS OF INERTIA.

§ 1. *Moments of Inertia of Forces.*

188. **Definitions.** — The *moment of inertia of a body* with respect to an axis is the sum of the products obtained by multiplying the mass of every elementary portion of the body by the square of its distance from the given axis.

The *moment of inertia of an area* with respect to an axis is the sum of the products obtained by multiplying each elementary area by the square of its distance from the axis.

The *moment of inertia of a line* may be similarly defined, using elements of length instead of elements of mass or area.

The *moment of inertia of a force* with respect to any axis is the product of the magnitude of the force into the square of the distance of its point of application from the axis. The sum of such products for any system of parallel forces is the moment of inertia of the system with respect to the given axis.

[NOTE. — The term moment of inertia had reference originally to material bodies, the quantity thus designated having especial significance in dynamical problems relating to the rotation of rigid bodies. The quantity above defined as the moment of inertia of an area is of frequent occurrence in the discussion of beams, columns, and shafts in the mechanics of materials. In the graphic discussion of moments of inertia of areas, it is convenient to treat areas as forces, just as in the determination of centers of gravity; it is therefore convenient to use the term *moment of inertia of a force* in the sense above defined. It is only in the case of masses that the term moment of inertia is really appropriate, but it is by analogy convenient to apply it to the other cases.]

The *product of inertia of a mass* with respect to two planes is the sum of the products obtained by multiplying each elementary mass by the product of its distances from the two planes.

The product of inertia of an area, a line, or a force may be defined in a similar manner.

For a *plane area*, the product of inertia with respect to two lines in its plane may be defined as the sum of the products obtained by multiplying each element of area by the product of its distances from the given lines. This is equivalent to the product of inertia of the area with respect to two planes perpendicular to the area and containing the two given lines.

For a *system of forces* with points of application in the same plane, the product of inertia with reference to two axes in that plane may be defined as the sum of the products obtained by multiplying the magnitude of each force by the product of the distances of its point of application from the given axes. It is with such systems and with plane areas that the following pages chiefly deal.

The *radius of gyration* of a body with respect to an axis is the distance from the axis of a point at which, if the whole mass of the body were concentrated, its moment of inertia would be unchanged. The square of the radius of gyration is equal to the quotient obtained by dividing the moment of inertia of the body by its mass.

The radius of gyration of an area may be defined in a similar manner.

The radius of gyration of a system of parallel forces is the distance from the axis of the point at which a force equal in magnitude to their resultant must act in order that its moment of inertia may be the same as that of the system. The square of the radius of gyration may be found by dividing the moment of inertia of the system by the resultant of the forces.

189. Algebraic Expressions for Moment and Product of Inertia. — *Moment of inertia.* — Let m_1, m_2 , etc., represent elementary masses of a body, and r_1, r_2 , etc., their respective

distances from an axis ; then the moment of inertia of the body with respect to that axis is

$$m_1 r_1^2 + m_2 r_2^2 + \dots \equiv \Sigma m r^2,$$

the symbol Σ being a sign of summation, and the second member of the equation being merely an abbreviated expression for the first.

Product of inertia. — Let p_1, p_2 , etc., denote the perpendicular distances of elements m_1, m_2 , etc., from one plane, and q_1, q_2 , etc., their distances from another ; then the product of inertia of the body with respect to the two planes is

$$m_1 p_1 q_1 + m_2 p_2 q_2 + \dots \equiv \Sigma m p q.$$

Radius of gyration. — With the same notation, if k denotes the radius of gyration of the body, we have

$$(m_1 + m_2 + \dots) k^2 = m_1 r_1^2 + m_2 r_2^2 + \dots.$$

Or,

$$k^2 = \frac{m_1 r_1^2 + m_2 r_2^2 + \dots}{m_1 + m_2 + \dots} = \frac{\Sigma m r^2}{\Sigma m}.$$

Here Σm is equal to the whole mass of the body.

Product-radius. — Let c represent a quantity defined by the equation.

$$(m_1 + m_2 + \dots) c^2 = m_1 p_1 q_1 + m_2 p_2 q_2 + \dots.$$

Then if the whole mass were concentrated at the same distance c from two axes, its product of inertia with respect to those axes would be unchanged. This quantity c is thus seen to be analogous to the radius of gyration. It may be called the *product-radius* of the body with respect to the two axes. The value of c is always given by the equation

$$c^2 = \frac{\Sigma m p q}{\Sigma m}.$$

Expressions similar to those just given apply also to plane areas and to systems of parallel forces. In case of an area, m_1, m_2 , etc., denote elements of area ; r_1, r_2 , etc., their distances from the axis of inertia ; and $(p_1, q_1), (p_2, q_2)$, etc., their dis-

tances from the two planes. In case of a system of parallel forces with coplanar points of application, m_1, m_2 , etc., must be replaced by the magnitudes of the forces.

190. Determination of Moment of Inertia of a System of Parallel Forces.— Let the points of application of the forces be in the same plane, which also contains the assumed axis. We shall have to deal only with systems satisfying these conditions. By the definition, the moment of inertia will be the same, whatever the direction of the forces. If we take the moment of any force (as defined in Art. 175) about the given axis, and suppose a force equal in magnitude to this moment to act at the point of application of the original force, and in a direction corresponding to the sign of the moment, then the moment of this new force about the given axis is equal to the moment of inertia of the original force. If this be done for all the forces, the algebraic sum of the results will be the required moment of inertia of the system.

This process can be carried out graphically by methods already described.

Let ab, bc, cd, de (Fig. 65) be the points of application of four parallel forces, and let the axis of inertia be QR . Suppose all the forces to act in lines parallel to QR , passing through the given points of application. Their respective moments with reference to QR may now be found by the method of Art. 55.

Draw the force polygon $ABCDE$ and choose a pole O , taking the pole distance H preferably equal to AE or some simple multiple of AE . (In Fig. 65 H is taken equal to AE .) Draw a funicular polygon and prolong each string to intersect QR . Then the moment of any force with respect to QR is the product of H by the distance intercepted on QR by the two strings corresponding to the force in question. Thus the moment of AB is given by the distance $A'B'$ (Fig. 65) multiplied by H . Also the successive moments of BC, CD, DE are represented by $B'C', C'D', D'E'$, each multiplied by H . It is

seen also that the intercepts, if read in the above order, give a distinction between positive and negative moments; upward distances on QR denoting in this case positive moments, and downward distances negative moments.

We have now to find the sum of the moments of a second system of forces acting in the original lines, but represented in




Fig. 65

magnitude and direction by the intercepts just found. We may take as the force polygon for the second construction the line $A'B'C'D'E'$ (Fig. 65), and choosing any pole distance H' , draw a second funicular polygon and find the distances intercepted by the successive strings on the line QR . But in this case, since only the resultant is desired, we need only find the intercept $A''E''$ between the first and last strings. The product of this intercept by H' gives the sum of the moments of $A'B'$, $B'C'$, $C'D'$, $D'E'$ with respect to QR ; and, if the product be multiplied by H (since $A'B'$, $B'C'$, etc., should each be multiplied by H in order to represent the magnitudes of the forces of the second system), the result will be the required moment of inertia of the given system of forces AB , BC , CD , DE .

It should be noticed that in Fig. 65 (*A*) is a *force diagram*, (*B*) a *space diagram* (Art. 11); that is, every line in (*A*) represents a force, while every line in (*B*) represents a distance. Even $A'B'$, $B'C'$, etc., though used as forces, are actually merely distances; and the moment of any one of them is the product of a *length* by a *length*.

191. **Radius of Gyration.** — The moment of inertia of the given system is $H \times H' \times A''E''$. If H has been taken equal to AB , the product $H' \times A''E''$ must equal the square of the radius of gyration of the system with respect to QR . The length of the radius of gyration can be found as follows (Fig. 65): Draw $LN = H' + A''E''$, and make $LM = H'$. On LN as a diameter draw a semicircle LPN , and from M draw a line perpendicular to LN , intersecting the semicircle in P . Then MP is the length of the required radius of gyration. For by elementary geometry we have $PM^2 = LM \times MN$.

If H is taken equal to $n \times AE$, the moment of inertia is equal to $H' \times A''E'' \times n \times AE$, and the square of the radius of gyration is equal to $nH' \times A''E''$. Hence in Fig. 65 we should put either $LM = nH'$, or $MN = n \times A''E''$.

192. **Central Axis.** — If the axis with reference to which the moment of inertia is found contains the centroid of the given system of forces, it is called a *central axis* of the system.

In many cases it is desired to find the moment of inertia with respect to a central axis whose direction is known while the position of the centroid is at first unknown. It is to be noticed that the method shown in Fig. 65 is applicable in this case; for the first part of the process is identical with that employed in finding the centroid of the system. If, in Fig. 65, the strings oa , oc , of the first funicular polygon be prolonged to intersect, a line through their point of intersection, parallel to the direction of the forces, will contain the centroid of the system. If this line is taken as the inertia-axis, the points A' , B' , C' , D' , E' are the points in which this axis is intersected by

the strings oa , ob , oc , od , oe . No further modification of the process is necessary.

193. Moment of Inertia Determined from Area of Funicular Polygon.—In Fig. 65, the moments of the given forces are represented by the intercepts $A'B'$, $B'C'$, $C'D'$, $D'E'$, each multiplied by the pole distance H . The moment of inertia of any force, as AB , is equal to the moment of a force represented by the corresponding intercept as $A'B'$, supposed to act in the line ab . Now, by definition (Art. 175) the moment about the axis QR of a force equal to $A'B'$ acting in the line ab is equal to double the area of the triangle $A'1B'$; hence the moment of the force $H \times A'B'$ is equal to double the area of that triangle multiplied by H . Similarly, the moment of a force $H \times B'C'$, acting in the line bc , is equal to double the area of the triangle $B'2C'$ multiplied by H . Applying the same reasoning to each force, we see that the sum of the moments of the assumed forces ($H \times A'B'$, $H \times B'C'$, etc.) is equal to $2H$ times the sum of the areas of the triangles $A'1B'$, $B'2C'$, $C'3D'$, $D'4E'$. In adding these triangles, each must be taken with its proper sign, corresponding to the sign of the moment represented by it. Thus, the moments of $A'B'$, $B'C'$, and $D'E'$ all have the same sign, while the moment of $C'D'$ has the opposite sign. Hence we must have for the sum of the moments,

$$\text{area } A'1B' + \text{area } B'2C' - \text{area } C'3D' + \text{area } D'4E',$$

which is equal to the area of the polygon $A'1234E'$. Hence this area, multiplied by $2H$, gives the moment of inertia of the required system of forces.

It may sometimes be convenient to apply this principle in determining moments of inertia, the area being determined by use of a planimeter, or by any other convenient method. It should be noticed that if H is taken equal to the sum of the given forces (AE), twice the area of the funicular polygon is equal to the square of the radius of gyration. If $H = \frac{1}{2} AE$, the

square of the radius of gyration is equal to the area of the polygon.

194. Determination of Product of Inertia of Parallel Forces.

— Assume the points of application of the forces to be in the plane containing the two axes. If the moment of any force with respect to one axis be found, and a force equal in magnitude to this moment be assumed to act at the point of application of the original force, then the moment of this new force with respect to the second axis is equal to the product of inertia of the given force for the two axes.

Thus, let ab, bc, cd, de (Fig. 66) be the points of application of four parallel forces, and let their product of inertia with respect to the axes QR, ST be required. Draw $ABCDE$, the




Fig. 66

force polygon for the given forces, assumed to act parallel to QR . Choose a pole O , the pole distance being preferably taken equal to AE , or some simple multiple of AE , and draw the funicular polygon as shown, prolonging the strings to intersect QR in the points A', B', C', D', E' . Now assume a series

of forces equal to $A'B'$, $B'C'$, etc., each multiplied by H , to act at the points ab , bc , etc., and determine their moments with respect to the axis ST . To find these moments, draw lines through ab , bc , etc., parallel to ST , and draw a funicular polygon for the assumed forces taken to act in these lines. The force polygon is obtained by revolving the line $A'B'C'D'E'$ until parallel with ST , and is the line $A'_1 B'_1 C'_1 D'_1 E'_1$ in the figure. The strings $o'a'$, $o'e'$ of the second funicular polygon intersect ST in the points A'' and E'' . Hence, calling H' the second pole distance, the product of inertia of the given system is equal to $H \times H' \times A''E''$.

195. Product-Radius. — If H be taken equal to AE (Fig. 66), $H' \times A''E''$ is equal to the square of the product-radius (Art. 189). Hence the product-radius can be found by a construction exactly like that employed in finding the radius of gyration. Thus (Fig. 66) take $LM = H'$ and $MN = A''E''$; make LN the diameter of a semicircle, and draw from M a line perpendicular to LN , intersecting the semicircle in P . Then $\overline{MP}^2 = LM \times MN = H' \times A''E''$; hence $MP = c$, the product-radius.

196. Relation between Moments of Inertia for Parallel Axes. — *Proposition.* — The moment of inertia of a system of parallel forces with reference to any axis is equal to its moment of inertia with respect to a parallel axis through the centroid of the system plus the moment of inertia with respect to the given axis of the resultant applied at the centroid of the system.

Let P_1 , P_2 , etc., represent the forces; x_1 , x_2 , etc., the distances of their points of application from the central axis; and a the distance of this central axis from the given axis. Calling the required moment of inertia A , and the moment of inertia with respect to the axis through the center of gravity A' , we have

$$\begin{aligned} A &= P_1 (a + x_1)^2 + P_2 (a + x_2)^2 + \dots \\ &= a^2 (P_1 + P_2 + \dots) + 2a (P_1 x_1 + P_2 x_2 + \dots) + P_1 x_1^2 + P_2 x_2^2 + \dots \end{aligned}$$

Now $P_1x_1 + P_2x_2 + \dots$ is the algebraic sum of the moments of the given forces with respect to the axis through their centroid, and is equal to zero; and $P_1x_1^2 + P_2x_2^2 + \dots = A'$. Hence

$$A = A' + (P_1 + P_2 + \dots) a^2,$$

which proves the proposition.

Radii of gyration.— Let k = radius of gyration of the system with respect to the given axis, and k' the radius of gyration with respect to the central axis, and we have

$$A = (P_1 + P_2 + \dots) k^2.$$

$$A' = (P_1 + P_2 + \dots) k'^2.$$

Hence the equation above deduced may be reduced to the form

$$k^2 = k'^2 + a^2.$$

197. Products of Inertia with Respect to Parallel Axes.—

Proposition.— The product of inertia of a system of parallel forces with reference to any two axes is equal to the product of inertia with reference to a pair of central axes parallel to the given axes, plus the product of inertia of the resultant (acting at the centroid) with reference to the given axes.

Let P_1, P_2 , etc., be the magnitudes of the given forces; $(p_1, q_1), (p_2, q_2)$, etc., the distances of their points of application from the central axes parallel to the two given axes; (a, b) the distances of the centroid of the system from the given axes. Let A and A' be the products of inertia of the system with respect to the given axes and the parallel central axes respectively. Then

$$A' = P_1 p_1 q_1 + P_2 p_2 q_2 + \dots$$

$$A = P_1 (p_1 + a)(q_1 + b) + P_2 (p_2 + a)(q_2 + b) + \dots$$

$$= (P_1 p_1 q_1 + P_2 p_2 q_2 + \dots) + a (P_1 q_1 + P_2 q_2 + \dots)$$

$$+ b (P_1 p_1 + P_2 p_2 + \dots) + ab (P_1 + P_2 + \dots).$$

But $P_1 q_1 + P_2 q_2 + \dots = 0$; and $P_1 p_1 + P_2 p_2 + \dots = 0$; since each of these expressions is the sum of the moments of the given forces

with respect to an axis through the centroid of the system. Hence,

$$A = A' + (P_1 + P_2 + \dots)ab,$$

which proves the proposition.

If $A = (P_1 + P_2 + \dots) c^2$ and $A' = (P_1 + P_2 + \dots) c'^2$, we have

$$c^2 = c'^2 + ab.$$

From the above proposition it follows that if the axes have such directions that the product of inertia with reference to the central axes is zero, the product of inertia with reference to the given axes is the same as if the forces all acted at the centroid. When this condition is known to be satisfied, then for the purpose of finding the product of inertia the system of forces may be replaced by their resultant.

It follows also, in the case when the product of inertia for the central axes is zero, that if one of the given axes coincides with the parallel central axis, the product of inertia for the given axes is zero; for in this case either a or b is zero, and hence $ab(P_1 + P_2 + \dots)$ is zero. Therefore,

If the product of inertia of a system is zero for two axes, A' and A'' , one of which (as A') contains the centroid of a system, then the product of inertia is also zero for A' and any axis parallel to A'' .

§ 2. *Moments of Inertia of Plane Areas.*

198. **Elementary Areas Treated as Forces.** — If any area be divided into small elements, and a force be applied at the centroid of each element numerically equal to its area, the moment of inertia of this system of forces will be approximately equal to that of the given area. The approximation will be closer the smaller the elementary areas are taken. If the elements be made smaller and smaller, so that the area of each approaches zero as a limit, the moment of inertia of the supposed system of forces approaches as a limit the true value of the moment of inertia of the given area.

It is seen, then, that most of the general principles which have been stated regarding moments of inertia of systems of forces are equally applicable to moments of inertia of areas. The practical application of these principles, however, and especially the graphic constructions based upon them, are less simple in the case of areas than of systems of forces such as those already treated. The reason for this is that the system of forces which may be conceived to replace the elements of area consists of an infinite number of infinitely small forces, with which the graphic methods thus far discussed cannot readily deal. Problems of this class are most easily treated by means of the integral calculus, especially when the areas dealt with are in the form of geometrical figures. It is possible, however, by graphic methods to determine approximately the moment of inertia of any plane area; and in many cases exact graphic solutions of such problems are not difficult. The proof of these methods is often most easily affected algebraically.

199. Moments of Inertia of Geometrical Figures. — The application of the integral calculus to the determination of moments of inertia will not be here treated. But the values of the moments of inertia of some of the common geometrical figures are of such frequent use that the more important of them will be given for future reference. The moment of inertia is in each case taken with respect to a central axis, and will be represented by I , while the radius of gyration will be called k .

Rectangle. — Let b and d be the sides, the axis being parallel to the side b . Then

$$I = \frac{bd^3}{12}; \quad k^2 = \frac{d^2}{12}.$$

Triangle. — Let b and d be the base and altitude. Then for an axis parallel to the base,

$$I = \frac{bd^3}{36}; \quad k^2 = \frac{d^2}{18}.$$

For an axis through the vertex, bisecting the base, $k^2 = \frac{b'^2}{24}$, where b' is the projection of the base on a line perpendicular to the axis.

Circle. — Let d be the diameter. Then

$$I = \frac{\pi d^4}{64}; \quad k^2 = \frac{d^2}{16}.$$

For a central axis perpendicular to the plane of the circle,

$$I = \frac{\pi d^4}{32}; \quad k^2 = \frac{d^2}{8}.$$

Ellipse. — Let a and b be the semi-axes. Then for an axis parallel to a ,

$$I = \frac{\pi a b^3}{4}; \quad k^2 = \frac{b^2}{4}.$$

For an axis parallel to b ,

$$I = \frac{\pi a^3 b}{4}; \quad k^2 = \frac{a^2}{4}.$$

For a central axis perpendicular to the plane of the ellipse,

$$I = \frac{\pi a b (a^2 + b^2)}{4}; \quad k^2 = \frac{a^2 + b^2}{4}.$$

Graphic construction for radius of gyration. — Whenever k^2 can be expressed as the product of two known factors, the value of k can be found by the construction already used in Art. 191.

Thus, in case of a rectangle, for which $k^2 = \frac{d^2}{12}$, we may put

$k^2 = \frac{d}{3} \cdot \frac{d}{4}$. Then if in Fig. 65 we take $LM = \frac{d}{4}$, $MN = \frac{d}{3}$, the

construction there shown will give MP as the value of k . For the triangle, the axis being parallel to the base, we have

$k^2 = \frac{d}{3} \cdot \frac{d}{6}$, and the same construction is applicable. For the

axis through the vertex bisecting the base, $k^2 = \frac{b'}{4} \cdot \frac{b'}{6}$.

200. **Product of Inertia.** — *General principles.* — Products of inertia of areas are determined by means of the integral calculus in a manner similar to that employed for moments of inertia. The following fundamental principles regarding products of inertia of geometrical figures will be found useful :

(1) With reference to two *rectangular* axes, one of which is an axis of symmetry (Art. 179), the product of inertia is zero. For it is manifest that the products of inertia of two equal elements, symmetrically placed with reference to one of the axes, are numerically equal but of opposite sign. Hence, if the whole area can be made up of such pairs of elements, the total product of inertia is zero.

(2) If the two axes are not rectangular, but the area can be divided into elements such that for every element whose distances from the axes are p, q , there is an equal element whose distances are $p, -q$, or $-p, q$, the product of inertia is zero. This includes the preceding as a special case.

201. **Products of Inertia of Geometrical Figures.** — In each of the following cases the product of inertia is zero :

A triangle, one axis containing the vertex and the middle point of the base, the other being any line parallel to the base.

A parallelogram, the axes being parallel to the sides and one axis being central. This includes the rectangle as a special case.

An ellipse, the axes being parallel to a pair of conjugate diameters, and one axis being central. This includes, as a special case, that in which one axis is a principal diameter and the other is any line perpendicular to it ; and under this case falls also the circle.

202. **Approximate Method for Finding Moment of Inertia of Any Area.** — To apply the method of Art. 190 to the determination of the moment of inertia of a plane area, we should strictly need to replace the area by an infinite number of parallel forces, proportional to the infinitesimal elements of the given area, and

with points of application in these elements. If, instead, we divide the given figure into finite portions whose several areas are known, and assume forces proportional to those areas to act at their centroids, we may get an approximate value for the moment of inertia, which will be more nearly correct the smaller the elements. This will be illustrated by the area shown in Fig. 67.

Let QR be the axis with reference to which the moment of inertia is to be found, in this case taken as a central axis.




Fig. 67


Divide the figure into four rectangular areas as shown, and assume forces numerically equal to these areas to act at their centroids parallel to QR . The force polygon is $ABCDE$. Draw the funicular polygon corresponding to a pole O , and let the successive strings intersect QR in A', B', C', D', E' . Take this as a new force polygon, and with any convenient pole distance draw a second funicular polygon, using the same lines of action. Let the first and last strings intersect QR in A'' and E'' . Then $A''E''$ multiplied by the product of the two pole distances gives the moment of inertia of the four assumed forces, and approximately the moment of inertia of the given

figure. If the first pole distance is taken equal to AE (as is the case in Fig. 67), the radius of gyration may be found by the construction of Art. 191. Thus in Fig. 67, MP is the radius of gyration as determined by this method.

A more accurate result may be reached by dividing the area into narrower strips by lines parallel to QR ; since the narrower such a strip is, the more nearly will the distance of each small element from the axis coincide with that of the centroid of the strip. If the partial areas are taken as narrow strips of equal width, the forces may be taken proportional to the average lengths of the several strips.

203. Accurate Methods. — If the given figure can be divided into parts, such that the area of each is known, and also its radius of gyration with respect to its central axis parallel to the given axis, the above method may be so modified as to give an accurate result. Two methods will be noticed.

(1) *When the axis is known at the start.* — Let the line of action of the force representing any partial area be taken at a distance from the given axis equal to the radius of gyration of that area with reference to the axis. If this is done, it is evident that the moment of inertia of the system of forces is identical with that of the given area. When the axis is known, the position of the line of action for any force may be found as




follows: Let QR (Fig. 68) be the given axis, and $Q'R'$ a parallel axis through the centroid of any partial area. Draw KL perpendicular to QR , and lay off LM equal to the radius of gyration of the partial area with respect to $Q'R'$. Then KM is the length of the radius of gyration with respect to QR . (Art. 196.) Take KN equal to KM and draw $Q''R''$ through N parallel to $Q'R'$; then $Q''R''$ is to be taken as the line of action of the force representing the partial area in question.

(2) *When the axis is at first unknown.* — The method to be

employed in this case is to let the force representing any partial area act in a line through the centroid of that area; and then assume the force representing its moment to act in such a line that the moment of this second force shall be numerically equal to the moment of inertia of the partial area. This line may be found as follows: Let k represent the radius of gyration of the partial area with respect to its central axis parallel to the given axis, and a the distance between the two axes. Then the moment of inertia of the partial area with respect to the given axis is $A(a^2 + k^2)$, if A represents the area. But $A(a^2 + k^2) = Aa\left(a + \frac{k^2}{a}\right)$. Hence, if a force numerically equal to A is assumed to act with an arm a , then a force equal to its moment Aa must act with an arm $a + \frac{k^2}{a}$ in order that its moment may equal $A(a^2 + k^2)$.

The distance $a + \frac{k^2}{a}$ can be found by a simple construction.

Let QR and $Q'R'$ (Fig. 69) be the given axis and the central axis respectively. Draw KL perpendicular to QR and lay off LM equal to k . From M draw a line perpendicular to KM , intersecting KL produced at N .



Then $KN = a + \frac{k^2}{a}$. For, in the similar triangles KNM , KML , we have

$$\frac{KN}{KM} = \frac{KM}{KL}; \text{ or } KN = \frac{KM^2}{KL}.$$

But $KL = a$, and $KM^2 = a^2 + k^2$; hence

$$KN = \frac{a^2 + k^2}{a} = a + \frac{k^2}{a}.$$

This second method is more useful than the first, because in applying it the first funicular polygon can be drawn before the position of the inertia-axis is known. Thus, a very common

case is that in which the moment of inertia of an area is to be found for a central axis, whose direction is known, while at the outset its position is unknown because the centroid of the area is unknown. If the second method be employed, the first funicular polygon can be drawn at once, and serves to locate the required central axis, as well as to determine the moments of the first set of forces as soon as the axis is known. The central axis and the moment of inertia with respect to it are thus determined by a single construction.

Example. — The method last described is illustrated in Fig. 70. The area shown consists of two rectangles, the centroids of which are marked ab and bc . The moment of inertia is to be found for a central axis parallel to the longer side of the rectangle ab .




Fig. 70

We draw through ab and bc lines parallel to the assumed direction of the axis, and take these for the lines of action of forces AB, BC , proportional to the areas of the two rectangles. ABC is the force polygon, and the pole distance is taken equal

to AC . The intersection of the strings oa , oc , determines a point of the required central axis ac . The moments of the given forces are proportional to $A'B'$, $B'C'$. We now have to find the lines of action for the forces $A'B'$, $B'C'$, in accordance with the method above described.

Take any line perpendicular to the axis ac , as VQ , the side of one of the rectangles. From R , the point in which this line intersects the vertical line through bc , lay off RT equal to the central radius of gyration of the rectangle whose centroid is bc . To find this central radius of gyration, we know that its value is $\sqrt{\frac{d^2}{12}}$ (Art. 199), where d is the length of the side of the rectangle perpendicular to the axis. Hence we take $QR = \frac{d}{3}$, $RS = \frac{d}{4}$, and make QS the diameter of a semicircle, intersecting the vertical line bc in T ; then RT is the required radius of gyration of the rectangle with respect to a central axis. Now draw from T a line perpendicular to VT , intersecting VQ in U ; then the line $b'c'$ drawn through U parallel to the given axis is the line of action of the force $B'C'$.

By a similar construction applied to the other rectangle, $a'b'$ is located as the line of action of the force $A'B'$. The second funicular polygon is now drawn, and the points A'' , C'' are found by the intersection of the strings $o'a'$, $o'c'$ with the axis. Hence the moment of inertia of the given area is equal to $A''C'' \times H \times H'$. In the figure H is made equal to AC , hence the radius of gyration can be determined by the usual construction, and its length is found to be MP .

204. Moment of Inertia of Area Determined from Area of Funicular Polygon. — The method given in Art. 193 for finding the moment of inertia of a system of forces by means of the area of the funicular polygon may be applied with approximate results to the case of a plane figure. If the forces are taken as acting at the centroids of the areas they represent, then to

get good results these partial areas should be taken as narrow strips between lines parallel to the axis.

If the lines of action are determined as in the first method of the preceding article, then the area enclosed by the funicular polygon and the axis represents accurately the required moment of inertia.

205. Product of Inertia Determined Graphically. — To determine the product of inertia of any area, let it be divided into small known parts, and let parallel forces numerically equal to the partial areas be assumed to act at the centroids of these parts. The product of inertia of these forces may then be found as in Art. 194, and its value will represent approximately the product of inertia of the given area.

If the partial areas can be so taken that the product of inertia of each with reference to axes through its centroid parallel to the given axes is zero, the method here given is exact. (Art. 197.)

If the partial areas are taken as narrow strips parallel to one of the axes, the condition just mentioned will be nearly fulfilled; for the product of inertia of each strip for a pair of axes through its centroid, one of which is parallel to its length, will be very small.


CHAPTER X. CURVES OF INERTIA.

§ 1. *General Principles.*

206. **Relation between Moments of Inertia for Different Axes through the Same Point.** — The moment of inertia with respect to any axis through a given point can be expressed in terms of the moments and product of inertia for any two axes through that point. It is necessary here to use algebraic methods, but the results reached form the basis of graphic constructions.

Let OX, OY (Fig. 71) be the two given axes; θ , the angle included between them; P, P_2 , etc., the forces of the system; x', y' , the coördinates of the point of application of any force P , referred to the axes OX, OY ; p, q , the perpendicular distances of the same point from OY and OX respectively, so that

$$p = x' \sin \theta, \quad q = y' \sin \theta.$$



Let $a', b',$ and c' be quantities defined by the equations

$$a' = \frac{P_1 x_1'^2 + P_2 x_2'^2 + \dots}{P + P_2 + \dots} = \frac{\sum P x'^2}{\sum P},$$

$$b'^2 = \frac{\sum P y'^2}{\sum P},$$

$$c'^2 = \frac{\sum P x' y'}{\sum P}$$

Then

$$a'^2 \sin^2 \theta = \frac{\sum P x'^2 \sin^2 \theta}{\sum P} = \frac{\sum P p^2}{\sum P},$$

$$b'^2 \sin^2 \theta = \frac{\sum P y'^2 \sin^2 \theta}{\sum P} = \frac{\sum P q^2}{\sum P},$$

$$c'^2 \sin^2 \theta = \frac{\sum P x' y' \sin^2 \theta}{\sum P} = \frac{\sum P p q}{\sum P};$$

and $a' \sin \theta$, $b' \sin \theta$, $c' \sin \theta$ are respectively the radius of gyration with respect to OY , the radius of gyration with respect to OX , and the product-radius (Art. 189) with respect to OX and OY .

The moment of inertia (I) and radius of gyration (k) of the system for the axis OM , making an angle ϕ with OX , may now be computed as follows :

Let s = perpendicular distance of the point of application of any force P from OM . Then from the geometry of the figure it is seen that

$$s = y' \sin (\theta - \phi) - x' \sin \phi.$$

Hence

$$I = \sum P s^2 = \sum P y'^2 \sin^2 (\theta - \phi) - 2 \sum P x' y' \sin (\theta - \phi) \sin \phi + \sum P x'^2 \sin^2 \phi;$$

or,

$$I = b'^2 \sum P \cdot \sin^2 (\theta - \phi) - 2 c'^2 \sum P \cdot \sin (\theta - \phi) \sin \phi + a'^2 \sum P \cdot \sin^2 \phi,$$

the factors involving θ and ϕ being constant for all terms of the summation. Hence

$$k^2 = \frac{I}{\sum P} = b'^2 \sin^2 (\theta - \phi) - 2 c'^2 \sin (\theta - \phi) \sin \phi + a'^2 \sin^2 \phi \quad \dots (1)$$

From these equations I and k may be computed if a' , b' , and c' are known ; that is, if the moments and product of inertia for the two axes OX and OY are known.

Special case. — If $\theta = 90^\circ$, the equation (1) becomes

$$k^2 = b'^2 \cos^2 \phi - 2 c'^2 \sin \phi \cos \phi + a'^2 \sin^2 \phi \quad \dots \dots \dots (2)$$

207. **Products of Inertia for Different Axes through the Origin.** — The product of inertia with respect to OM and OX may be found as follows :

Let A = the required product of inertia ; then

$$\begin{aligned} A &= \sum Pqs = \sum Py' \sin \theta [y' \sin (\theta - \phi) - x' \sin \phi] \\ &= \sum P [y'^2 \sin \theta \sin (\theta - \phi) - x'y' \sin \theta \sin \phi] \\ &= [b'^2 \sin \theta \sin (\theta - \phi) - c'^2 \sin \theta \sin \phi] \sum P. \end{aligned}$$

Let h = product-radius for axes OM and OX ; then

$$h^2 = \frac{A}{\sum P} = b'^2 \sin \theta \sin (\theta - \phi) - c'^2 \sin \theta \sin \phi.$$

Special case. — The axis OM may be so chosen that $A=0$. This will be the case if

$$b'^2 \sin (\theta - \phi) = c'^2 \sin \phi.$$

208. **Inertia Curve.** — If on OM (Fig. 71) a point M be taken such that the length OM depends in some given way upon the value of k , and if similar points be located for all possible directions of OM , the locus of such points will be a curve which is called a *curve of inertia* of the system for the center O .

The form of the curve will depend upon the assumed law connecting OM with k .

209. **Ellipse or Hyperbola of Inertia.** — The simplest curve is obtained by assuming OM to be inversely proportional to k . Let $OM=r$, and take $r^2 = \frac{d^4 \sin^2 \theta}{k^2}$, where d^2 is a positive quantity, so that d always represents a *real* length, positive or negative.

Equation (1) of Art. 206 then becomes

$$d^4 \sin^2 \theta = b'^2 r^2 \sin^2 (\theta - \phi) - 2 c'^2 r^2 \sin (\theta - \phi) \sin \phi + a'^2 r^2 \sin^2 \phi,$$

which is the polar equation of the inertia-curve, r and ϕ being the variable coördinates. Let x, y be coördinates of the point M referred to the axes OX, OY . Then

$$\frac{r}{\sin \theta} = \frac{x}{\sin (\theta - \phi)} = \frac{y}{\sin \phi},$$

whence

$$\frac{r^2 \sin^2 (\theta - \phi)}{\sin^2 \theta} = x^2,$$

$$\frac{r^2 \sin^2 \phi}{\sin^2 \theta} = y^2,$$

$$\frac{r^2 \sin (\theta - \phi) \sin \phi}{\sin^2 \theta} = xy,$$

and the equation becomes

$$d^4 = b'^2 x^2 - 2 c'^2 xy + a'^2 y^2 \dots \dots \dots (3)$$

The form of this equation shows that it represents a conic section whose center is at the origin of coördinates O . This conic may be either an ellipse or a hyperbola.

The equation will be discussed more fully in a later article. One fact may, however, be here noticed.

If the moment of inertia I is positive for all positions of the axis, the radius of gyration k will be real, whatever the value of ϕ . But r , the radius vector of the curve, will be real when k is real; hence in this case the curve is an ellipse. This is always the case if the given forces have all the same sign.

If the forces have not all the same sign, it is possible that the value of I may have different signs for different directions of the axis. If this is so, certain values of ϕ make k (and therefore r) imaginary. In this case the curve is a hyperbola.

The most important case is that in which the given forces have all the same sign which may be taken as plus, so that the moment of inertia is always positive, and the curve an ellipse; and to this case the discussion will be confined.

§ 2. *Inertia-Ellipses for Systems of Forces.*

210. **Properties of the Ellipse.** — In discussing ellipses of inertia use will be made of certain general properties of the ellipse, which, for convenience of reference, will be here summarized. For the proof of the propositions stated the reader is referred to works on the conic sections.

(1) The equation

$$Ax^2 + Bxy + Cy^2 = D$$

represents an ellipse if $B^2 - AC$ is negative; a hyperbola if $B^2 - AC$ is positive. (Salmon's *Conic Sections*, p. 140.) The coördinate axes may be either rectangular or oblique.

(2) Two diameters of an ellipse are said to be *conjugate* to each other if each bisects all chords parallel to the other. If the axes of coördinates coincide with a pair of conjugate diameters, the lengths of which are $2a'$ and $2b'$, the equation of the curve is

$$\frac{x^2}{a'^2} + \frac{y^2}{b'^2} = 1.$$

A particular case of this equation is that in which the coördinate axes are rectangular, being the principal axes of the curve; in which case we may write a and b instead of a' and b' .

(3) In an ellipse, the product of any semi-diameter and the perpendicular from the center on the tangent parallel to that semi-diameter is constant and equal to ab . That is, if r is any radius vector of the curve drawn from the center, and p the length of the perpendicular from the center to the parallel tangent, we have

$$pr = ab$$

where a and b are the principal semi-axes of the curve.

(4) Let a' and b' be conjugate semi-diameters. Then each is parallel to the tangent at the extremity of the other. Hence the length of the perpendicular from the center to the tangent parallel to a' is $b' \sin \theta$, where θ is the angle included between a' and b' . Therefore from the preceding paragraph,

$$a'b' \sin \theta = ab.$$

(5) An ellipse can be constructed, when a pair of conjugate diameters is known, as follows :

Let AA' , BB' (Fig. 72), be the conjugate diameters, O being the center of the ellipse. Complete the parallelogram $OBCA$.




FIG. 72

Divide OA and CA into parts proportional to each other, beginning at O and C . Through the points of division of OA draw lines radiating from B' , and through the points of division of CA draw lines radiating from B . The points of inter-

section of the corresponding lines in the two sets are points of the ellipse. In a similar way, the other three quadrants may be drawn. (The location of one point is shown in the figure.)

A convenient way to locate the corresponding points of division on OA and CA is to cut these lines by lines parallel to the diagonal OC .

211. Discussion of Equation of Inertia-Curve. — We will now examine the equation of the inertia-curve,

$$b'^2x^2 - 2c'^2xy + a'^2y^2 = d^4$$

with reference to the properties of the ellipse above enumerated.

(1) If $a'^2b'^2 - c'^4$ is positive, the equation denotes an ellipse. This cannot be the case if a'^2 and b'^2 have opposite signs. But from the definitions of a'^2 and b'^2 (Art. 206) it is seen that their signs are the same as those of the moments of inertia for Y and X axes respectively. Hence, if there are any two axes through the assumed center for which the moments of inertia have opposite signs, the inertia-curve is a hyperbola.

If the moment of inertia has the same sign for all axes through the assumed center, the curve is an ellipse. For, since $c'^2 = \frac{\sum Ppq \sin^2 \theta}{\sum P}$ (Art. 206), c' may be made zero by choosing the axes so that the product of inertia with respect to them is zero; and if c' is zero, and a'^2 and b'^2 have the same sign, the quantity $a'^2b'^2 - c'^4$ is positive.

This agrees with the conclusion stated in Art. 209.

We shall here deal only with ellipses of inertia.

(2) If $c'=0$, the coördinate axes are conjugate axes of the curve. But the condition $c'=0$ means that the product of inertia for the two axes is zero. Hence any two axes for which the product of inertia is zero are conjugate axes of the inertia-curve. (This is true whether the curve is an ellipse or a hyperbola.)

(3) By the law of formation of the inertia-conic (Art. 209), the length of the radius vector lying in any line is inversely proportional to the radius of gyration with respect to that line. But by (3) of the last article, the perpendicular from the center on the tangent parallel to any radius vector is inversely proportional to the length of that radius vector. Hence the perpendicular distance between any diameter and the parallel tangent is directly proportional to the radius of gyration with respect to that diameter. The curve may be so constructed that the length of this perpendicular is *equal* to the radius of gyration, as follows :

From Art. 209, we have

$$k = \frac{d^2 \sin \theta}{r}$$

and from (3) and (4) of the last article we have

$$p = \frac{ab}{r} = \frac{a'b' \sin \theta}{r},$$

if a' and b' are *conjugate* semi-diameters. Now take

$$d^2 \sin \theta = ab = a'b' \sin \theta,$$

or

$$d^2 = a'b',$$

and we have

$$k = p,$$

and the equation of the curve becomes (since $c'=0$ when the axes are conjugate)

$$b'^2 x^2 + a'^2 y^2 = a'^2 b'^2.$$

If the equation be written in this form, a' and b' having the meanings assigned in Art. 206, *the radius of gyration about any axis through the center of the ellipse is equal to the perpendicular distance between the axis and the parallel tangent to the ellipse.*

Hereafter we shall mean by *inertia-ellipse* the curve obtained by taking $d^2 = a'b'$ as above described, so that the radius of gyration for any axis can be found by direct measurement when a parallel tangent to the ellipse is known.

212. To Determine Tangents to the Inertia-Ellipse for Any Center. — Let the radius of gyration (k) be found for any assumed axis through the given center by one of the methods already described (Arts. 202 and 203). Then two lines parallel to the axis and distant k from it, on opposite sides, will be tangents to the inertia-ellipse.

213. To Construct the Inertia-Ellipse, a Pair of Conjugate Axes Being Known in Position. — If the positions of two axes conjugate to each other can be found, the ellipse can be drawn by the following method:

Determine the radius of gyration for each of the two axes and draw the corresponding tangents as in the preceding article; then proceed as follows:

Let XX' , YY' (Fig. 73) be the given axes, and let the four tangents determined as above form the parallelogram $PQRS$.




Fig. 73

Let A , A' , B , B' be the points in which these tangents intersect the axes XX' , YY' . Then, since each diameter is parallel to the tangents at the extremities of the conjugate diameter, A , A' , B , B' are the

extremities of the diameters lying in the given axes. The ellipse can now be constructed as explained in Art. 210 (Fig. 72).

This method of constructing the inertia-ellipse is useful

whenever the given system has a pair of conjugate axes which can be located by inspection.

214. Central Ellipse. — It is evident that an inertia-curve can be found with its center at any assumed point. That ellipse whose center is the centroid of the given system is called the *central ellipse* for the system.

Since the central ellipse gives at once the radius of gyration for every axis through the centroid of the system, it enables us to determine readily the radius of gyration for any axis whatever, by means of the known relation between radii of gyration for parallel axes. (Art. 196.)

§ 3. *Inertia-Curves for Plane Areas.*

215. General Principles. — The principles deduced in the treatment of inertia-curves for systems of forces are all true for the case of plane areas. But special difficulties arise in dealing with areas, because of the fact that the system of forces equivalent to any area consists of an infinite number of forces. The principles already developed are, however, sufficient to deal at least approximately with all areas, and accurately with many cases.

216. Inertia-Curve an Ellipse. — Since the forces conceived to replace the elements of area (Art. 198) have all the same sign, the value of k^2 is always positive, and the inertia-curve is always an ellipse. (Arts. 209 and 211.)

217. Cases Admitting Simple Treatment. — Whenever a pair of conjugate diameters can be located, and the radius of gyration determined for each, the inertia-ellipse can be at once drawn as in Art. 213. This will be the case whenever it is possible to locate readily a pair of axes for which the product of inertia is zero.

(1) If there is an axis of symmetry, this and any line perpendicular to it are a pair of conjugate axes (and in fact the principal axes) of the inertia-ellipse whose center is at their intersection. (Art. 200.)

(2) If two axes can be located in such a way that for every element of area whose distances from the axes are p, q , there is an equal element whose distances are $p, -q$, or $-p, q$, the product of inertia is zero for the two axes, and these are therefore a pair of conjugate axes of the inertia-ellipse whose center is at their intersection. This of course includes the case when there is an axis of symmetry. (Art. 200.)

When a pair of conjugate axes is known, the radius of gyration is to be found by one of the methods of Art. 202 or Art. 203; the ellipse can then be drawn exactly as explained in Art. 213.

If a pair of conjugate axes cannot be located by inspection, the inertia-ellipse cannot be so readily constructed. Such cases will not be here treated.

As examples of areas, in which the principal axes of the inertia-curve can be located by inspection, may be mentioned the cross-section of the I-beam, the deck-beam, the channel-bar, and other shapes of structural iron and steel.

Many geometrical figures possess axes of symmetry. In others a pair of conjugate axes can be located by principle (2). Some of these will be discussed in the next article.

Example. — Draw the central ellipse for the deck-beam section shown in Fig. 74.




Fig. 74

[SUGGESTIONS. — Since there is an axis of symmetry, this contains one of the principal axes of the ellipse. The other can be drawn as soon as the centroid of the section is known. Find the radius of gyration for each axis by Art. 202, and then construct the ellipse as explained in Art. 213.]

218. Central Ellipses for Geometrical Figures. — In many of the simple geometrical figures, not only can a pair of conjugate axes be located by inspection, but the radius

of gyration for each of these axes can be found by a simple construction, so that the central ellipse can be readily drawn. Some of these cases will be here summarized.

(1) *Parallelogram*.— Let $ABCD$ (Fig. 75) be the parallelogram; then XX' , YY' , drawn through the centroid parallel to the sides, are a pair of conjugate axes of the central ellipse. Let $AB=b$, $BC=d$, and let h = the perpendicular distance between AB and DC . The moment of inertia of the parallelogram with respect to the axis XX' is




Fig. 75

equal to the moment of inertia of a rectangle of sides b and h . Hence k^2 , the square of the radius of gyration for this axis, is $\frac{h^2}{12}$. The length of k can be found by the construction used in case of the rectangles in Fig. 70. The following modification of the method is, however, more convenient :

Make $EF = \frac{1}{4}BC$, $EG = \frac{3}{4}BC$, and draw a semicircle with FG as a diameter. From E draw a line perpendicular to BC , intersecting the semicircle at I . Lay off $EH = EI$; then a line through H parallel to XX' is a tangent to the central ellipse. For by construction,

$$EH = EI = \frac{BC}{\sqrt{12}}.$$

And since the projection of BC on a line perpendicular to XX' is equal to h , the projection of EH on the same line is equal to $\frac{h}{\sqrt{12}}$, that is to k .

The tangent parallel to the side BC may be found in a similar way. It may, however, be located more simply as follows : It is evident that the distance between YY' and a tangent parallel to it, measured along AB , bears the same ratio to AB that EH does to BC . Hence, the parallelogram formed by the four tangents, two parallel to XX' and two parallel to YY' , is similar to the parallelogram $ABCD$.

Fig. 75 shows this parallelogram and also the ellipse.


(2) *Triangle*. — Let ABC (Fig. 76) be the triangle; b = length of the base BC ; b' = length of projection of BC on a line perpendicular to AD ; d = altitude measured perpendicular to BC . AD and a line through the centroid parallel to BC are a pair of conjugate axes of the central ellipse (Art. 217). From Art. 199, the radius of gyration for a central axis parallel to BC is

$\sqrt{\frac{d^3}{18}} = \sqrt{\frac{d}{3} \cdot \frac{d}{6}}$. Let XX' be this axis, and H the point in which it intersects AC . Then $HC = \frac{1}{3}AC$. Take $HK = \frac{1}{6}AC = \frac{1}{2}HC$, and make KC the diameter of a semicircle. From H draw HI perpendicular to AC , intersecting the semicircle at I . Make $HL = HI$; then the line through L parallel to XX' is a tangent to the central ellipse. For the radius of gyration with respect to XX' is to HL as the altitude d is to AC .

Again, for the axis AD , the radius of gyration is $\sqrt{\frac{b'^3}{24}}$ (Art. 199). Make $DE = \frac{1}{6}BC$ and $DF = \frac{1}{4}BC$, and take EF as a diameter of a semicircle. From D draw a line perpendicular to BC , intersecting the semicircle in M ; and make $DG = DM$; then a line from G parallel to AD is a tangent to the central ellipse.

The figure shows the parallelogram formed by the two tangents parallel to XX' and the two parallel to AD , and also the central ellipse.

(3) *Ellipse*. — From Art. 199, the radii of gyration of an ellipse with respect to the two principal diameters are $\frac{1}{2}a$ and $\frac{1}{2}b$. Hence the central ellipse of inertia is similar to the given ellipse, its semi-axes being $\frac{1}{2}a$ and $\frac{1}{2}b$. A special case of this is a circle, for which the central curve is a circle whose radius is half that of the given circle.



(4) *Semicircle*. — Let ABC (Fig. 77) be the semicircle, O being the centroid. (The point O may be located by the method described in Art. 184.)


From symmetry it is evident that the principal axes of the central ellipse are XX' and YY' , drawn through O , respectively parallel and perpendicular to AB .

With respect to the axis YY' , the radius of gyration is evidently $\frac{1}{2}r$, the same as

for the whole circle. Hence two lines parallel to YY' and distant $\frac{1}{2}r$ from it are tangents to the central ellipse.

Again, the radius of gyration of the semicircle with respect to AB as an axis is also $\frac{1}{2}r$, the same as for the whole circle. To find it for the axis XX' , with D as a center, and radius $\frac{1}{2}r$, draw an arc intersecting XX' at F ; then $\overline{OF}^2 = \overline{DF}^2 - \overline{OD}^2$. But DF is equal to the radius of gyration with respect to AB , and OD is the distance between XX' and AB ; hence (Art. 196) OF is equal to the radius of gyration with respect to XX' . Hence if two lines are drawn parallel to XX' , each at a distance from it equal to OF , they will be tangents to the central ellipse. The ellipse can now be drawn in the usual manner.

Fig. 77





219. **Summary of Results.** — By the principles and methods developed in the present chapter, inertia-curves can be drawn for all the simpler cases that may arise; namely, whenever a pair of conjugate axes can be located by inspection. This will be the case whenever the product of inertia can be seen to be zero for any pair of axes; and it includes every case of an area possessing an axis of symmetry.



It is believed that this chapter contains as complete a discussion as is needed by the student of engineering. Those who desire to pursue the subject further may consult other works.

[illegible]

Scale, 1 inch = 6 feet

Scale, 1 inch = 600 lbs.





Scale, 1 inch = 6,000 lbs.

(C)






Fig. 42






PLATE II.



(D)

Scale: 1 in. = 5,000 lbs.



(E)

Scale: 1 in. = 5,000 lbs.








Fig. 47

8,000	15,000	15,000	15,000	15,000	9,000	9,000	9,000	9,000
9.0	8.1	5.8	4.5	4.5	7.1	4.8	5.7	4.8










PLATE IV.








Fig. 54



Linear Scale, 1 in. = 20 ft.
Force Scale, 1 in. = 80,000 lbs.

Z_2







Fig. 52



MATHEMATICAL TEXT-BOOKS

PUBLISHED BY

MACMILLAN & CO.

Mechanics.

RIGID DYNAMICS.

An Introductory Treatise. By W. STEADMAN ALDIS, M.A. \$1.00.

ELEMENTARY APPLIED MECHANICS.

Part II. Transverse Stress. By T. ALEXANDER and A. W. THOMPSON.
8vo. \$2.75.

EXPERIMENTAL MECHANICS.

A Course of Lectures delivered to the Royal College of Science for Ireland. By Sir R. S. BALL, LL.D., F.R.S. Second Edition. With Illustrations. 12mo. \$1.50.

Teachers of experimental mechanics can have no better assistant than this book, for the lectures are happy in their illustrations, clear in their demonstrations, and admirable in their arrangement. — *Manchester Guardian*.

LESSONS ON THERMODYNAMICS.

By R. E. BAYNES, M.A. 12mo. \$1.90.

WORKS BY W. H. BESANT, D.Sc.,
Lecturer of St. John's College, Cambridge.

A TREATISE ON HYDROMECHANICS.

Fifth Edition, revised. Part I. Hydrostatics. 12mo. \$1.25.

A TREATISE ON DYNAMICS. \$1.75.

ELEMENTARY HYDROSTATICS. 16mo. \$1.00.

ELEMENTS OF DYNAMIC.

An Introduction to the Study of Motion and Rest in Solid and Fluid Bodies. By W. KINGDON CLIFFORD, F.R.S.

Part I. Books I.-III. 12mo. \$1.90.

Part II. Book IV. and Appendix. 12mo. \$1.75.

APPLIED MECHANICS.

An Elementary General Introduction to the Theory of Structures and Machines. By JAMES H. COTTERILL, F.R.S. 8vo. \$5.00.

The book is a valuable one for students. . . . A very admirable feature of the book is the frequent interjecting of practical problems for solution, at the close of the different sections. — *School of Mines Quarterly*.

This work constitutes a manual of applied mechanics which, in its completeness and adaptation to the requirements of the engineer student, is without a rival. — *Academy*.

ELEMENTARY MANUAL OF APPLIED MECHANICS.

By Prof. J. H. COTTERILL, F.R.S., and J. H. SLADE. 12mo. \$1.25.

GRAPHICAL STATICS.

By LUIGI CREMONA. Two Treatises on the Graphical Calculus and Reciprocal Figures in Graphical Calculus. Authorized English Translation by T. HUDSON BEARE. 8vo. \$2.25.

A TREATISE ON ELEMENTARY DYNAMICS.

For the Use of Colleges and Schools. By WILLIAM GARNETT, M.A., D.C.L. Fifth Edition, revised. \$1.50.

ELEMENTARY STATICS.

By H. GOODWIN, D.D., Bishop of Carlisle. Second Edition. 75 cents.

WORKS BY JOHN GREAVES, M.A.

A TREATISE ON ELEMENTARY STATICS.

Second Edition, revised. 12mo. \$1.90.

It can be unreservedly recommended. — *Nature*.

STATICS FOR BEGINNERS. 16mo. 90 cents.

HYDROSTATICS.

By ALFRED GEORGE GREENHILL. *In preparation*.

THE APPLICATIONS OF PHYSICAL FORCES.

By A. GUILLEMIN. Translated and Edited by J. NORMAN LOCKYER, F.R.S. With Colored Plates and Illustrations. Royal 8vo. \$6.50.

ELEMENTARY DYNAMICS OF PARTICLES AND SOLIDS.

By W. M. HICKS. 12mo. \$1.60.

ELEMENTARY MECHANICS.

Stage I. By J. C. HOROBIN, B.A. With Numerous Illustrations. 12mo. Cloth. 50 cents. *Stages II. and III. in preparation.*

THE ELEMENTS OF GRAPHICAL STATICS.

A Text-Book for Students of Engineering. By LEANDER M. HOSKINS, C.E., M.S., Prof. of Applied Mechanics, Leland Stanford Jr. University, Palo Alto, Cal.

A TREATISE ON THE THEORY OF FRICTION.

By J. H. JELLETT, B.D., late Provost of Trinity College, Dublin. \$2.25.

THE MECHANICS OF MACHINERY.

By ALEXANDER B. W. KENNEDY, F.R.S. With Illustrations. 12mo. \$3.50.

HYDRODYNAMICS.

By H. LAMB. A Treatise on the Mathematical Theory of Fluid Motion. 8vo. \$3.00.

WORKS BY THE REV. J. B. LOCK, M.A.

Fellow of Gonville and Caius College, Cambridge.

DYNAMICS FOR BEGINNERS. 16mo. \$1.00.

Mr. Lock writes like one whose heart is in his work. He shows rare ingenuity in smoothing the difficulties in the path of the beginner, and we venture to predict that his book will meet with a wide and hearty welcome among practical teachers. — *Athenæum*.

ELEMENTARY STATICS. 16mo. \$1.10.

The whole subject is made interesting from beginning to end, and the proofs of the various propositions are very simple and clear. We have no doubt that the book will be appreciated by all who have an opportunity of judging of its merits.—*Nature*.

MECHANICS FOR BEGINNERS.

Part I. Mechanics of Solids. 90 cents.

An introductory book, which, it is hoped, may be found useful in schools and by students preparing for the elementary stage of the Science and Art and other public examinations.

ELEMENTARY HYDROSTATICS. *In preparation.*

WORKS BY S. L. LONEY, M.A.,

Fellow of Sidney Sussex College, Cambridge.

A TREATISE ON ELEMENTARY DYNAMICS.

New and Enlarged Edition. 12mo. \$1.90.

Solutions of the Examples contained in the Above. *In the Press.*

THE ELEMENTS OF STATICS AND DYNAMICS.

Part I. Elements of Statics. \$1.25. Part II. Elements of Dynamics. \$1.00. Complete in one volume. 16mo. \$1.90.

AN ELEMENTARY TREATISE ON KINEMATICS AND DYNAMICS.

By JAMES GORDON MACGREGOR, M.A., D.Sc., Munro Professor of Physics, Dalhousie College, Halifax. 12mo. \$2.60.

The problems and exercises seem to be well chosen, and the book is provided with a useful Index. Altogether it will repay a careful study.—*Educational Times*.

WORKS BY G. M. MINCHIN, M.A.,

Professor of Mathematics in the Royal Indian Engineering College.

A TREATISE ON STATICS.

Third Edition, corrected and enlarged. Vol. I. Equilibrium of Coplanar Forces. 8vo. \$2.25. Vol. II. Statics. 8vo. \$4.00.

UNIPLANAR KINEMATICS OF SOLIDS AND FLUIDS. 12mo. \$1.90.

A TREATISE ON ELEMENTARY MECHANICS.

For the use of the Junior Classes at the Universities, and the Higher Classes in Schools. With a collection of examples by S. PARKINSON, F.R.S. Sixth Edition. 12mo. \$2.25.

LESSONS ON RIGID DYNAMICS.

By the Rev. G. PIRIE, M.A. 12mo. \$1.50.

ELEMENTARY STATICS.

By G. RAWLINSON, M.A. Edited by E. STURGES. 8vo. \$1.10.

WORKS BY E. J. ROUTH, LL.D., F.R.S.,

Fellow of the Senate of the University of London.

A TREATISE ON THE DYNAMICS OF A SYSTEM OF RIGID BODIES.

With Examples. New Edition Revised and Enlarged. 8vo.

Part I. Elementary. Fifth Edition Revised and Enlarged. \$3.75.

Part II. Advanced. \$3.75.

STABILITY OF A GIVEN STATE OF MOTION,

Particularly Steady Motion. 8vo. \$2.25.

HYDROSTATICS FOR BEGINNERS.

By F. W. SANDERSON, M.A. 16mo. \$1.10. *New edition preparing.*

Mr. Sanderson's work has many merits, and is evidently a valuable text-book, being the work of a practical and successful teacher. — *Canada Educational Monthly.*

SYLLABUS OF ELEMENTARY DYNAMICS.

Part I. Linear Dynamics. With an Appendix on the Meanings of the Symbols in Physical Equations. Prepared by the Association for the Improvement of Geometrical Teaching. 4to. 30 cents.

A TREATISE ON DYNAMICS OF A PARTICLE.

By P. G. TART, M.A., and W. J. STEELE. Sixth Edition, Revised. \$3.00.

WORKS BY ISAAC TODHUNTER, F.R.S.

Late Fellow and Principal Mathematical Lecturer of St. John's College.

MECHANICS FOR BEGINNERS.

With Numerous Examples. New Edition. 18mo. \$1.10. KEY. \$1.75.

A TREATISE ON ANALYTICAL STATICS.

Fifth Edition. Edited by Prof. J. D. EVERETT, F.R.S. 12mo. \$2.60.

A COLLECTION OF PROBLEMS IN ELEMENTARY MECHANICS.

By W. WALTON, M.A. Second Edition. \$1.50.

PROBLEMS IN THEORETICAL MECHANICS.

Third Edition, Revised. With the addition of many fresh Problems.
By W. WALTON, M.A. 8vo. \$4.00.

Higher Pure Mathematics.

WORKS BY SIR G. B. AIRY, K.C.B., formerly Astronomer-Royal.

ELEMENTARY TREATISE ON PARTIAL DIFFERENTIAL EQUATIONS.

With Diagrams. Second Edition. 12mo. \$1.50.

ON THE ALGEBRAICAL AND NUMERICAL THEORY OF ERRORS

of Observations and the Combination of Observations. Second Edition, revised. 12mo. \$1.75.

NOTES ON ROULETTES AND GLISSETTES.

By W. H. BESANT, D.Sc., F.R.S. Second Edition, Enlarged. \$1.25.

A TREATISE ON THE CALCULUS OF FINITE DIFFERENCES.

By the late GEORGE BOOLE. Edited by J. F. MOULTON. Third Edition. 12mo. \$2.60.

ELEMENTARY TREATISE ON ELLIPTIC FUNCTIONS.

By ARTHUR CAYLEY, D.Sc., F.R.S. *New Edition preparing.*

DIFFERENTIAL CALCULUS.

With Applications and Numerous Examples. An Elementary Treatise.

By JOSEPH EDWARDS, M.A. 12mo. \$2.75.

A useful text-book both on account of the arrangement, the illustrations, and applications and the exercises, which contain more easy examples than are usually given. — *Educational Times*.

AN ELEMENTARY TREATISE ON SPHERICAL HARMONICS

And Subjects Connected with Them. By Rev. N. M. FERRERS, D.D., F.R.S. 12mo. \$1.90.

WORKS BY ANDREW RUSSELL FORSYTH, M.A.

A TREATISE ON DIFFERENTIAL EQUATIONS. 8vo. \$3.75.

As Boole's "Treatise on Different Equations" was to its predecessor, Wymer's, this treatise is to Boole's. It is more methodical and more complete, as far as it goes, than any that have preceded it. — *Educational Times*.

THEORY OF DIFFERENTIAL EQUATIONS.

Part I. Exact Equations and Pfaff's Problems. 8vo. \$3.75.

AN ELEMENTARY TREATISE ON CURVE TRACING.

By PERCIVAL FROST, M.A. 8vo. \$3.00.

DIFFERENTIAL AND INTEGRAL CALCULUS.

With Applications. By ALFRED GEORGE GREENHILL, M.A. 12mo. \$2.00.

APPLICATION OF ELLIPTIC FUNCTIONS.

By ALFRED GEORGE GREENHILL, M.A. 12mo. \$3.50.

AN ELEMENTARY TREATISE ON THE DIFFERENTIAL AND INTEGRAL CALCULUS.

By G. W. HEMMING, M.A. 8vo. \$2.50.

THEORY OF FUNCTIONS.

By JAMES HARKNESS, M.A., Professor of Mathematics, Bryn Mawr College, and FRANK MORLEY, A.M., Professor of Mathematics, Haverford College, Pa. *In preparation*.

INTRODUCTION TO QUATERNIONS.

With Examples. By P. KELLAND, M.A., and P. G. TAIT, M.A. Second Edition. 12mo. \$2.00.

HOW TO DRAW A STRAIGHT LINE.

A Lecture on Linkages. By A. B. KEMPE, B.A. With Illustrations. *Nature Series*. 12mo. 50 cents.

DIFFERENTIAL CALCULUS FOR BEGINNERS.

With Examples. By ALEXANDER KNOX, B.A. 16mo. 90 cents.

MESSENGER OF MATHEMATICS.

Edited by J. W. L. GLAISHER. Published Monthly. 35 cents each number.

WORKS BY THOMAS MUIR,
Mathematical Master in the High School, Glasgow.

A TREATISE ON THE THEORY OF DETERMINANTS.

With Examples. 12mo. *New Edition in Preparation*.

THE THEORY OF DETERMINANTS

In the Historical Order of its Development. Part I. Determinants in General. Leibnitz (1693) to Cayley (1841). 8vo. \$2.50.

TREATISE ON INFINITESIMAL CALCULUS.

By BARTHOLOMEW PRICE, M.A., F.R.S., Professor of Natural Philosophy, Oxford.

Vol. I. Differential Calculus. Second Edition. 8vo. \$3.75.

Vol. II. Integral Calculus, Calculus of Variations, and Differential Equations. 8vo. *Reprinting*.

Vol. III. Statics, including Attractions; Dynamics of a Material Particle. 8vo. \$4.00.

Vol. IV. Dynamics of Material Systems. Together with a Chapter on Theoretical Dynamics, by W. F. DONKIN, M.A. 8vo. \$4.50.

A TREATISE ON THE THEORY OF DETERMINANTS,

And their Applications in Analysis and Geometry. By ROBERT SCOTT, M.A. 8vo. \$3.50.

FACTS AND FORMULÆ IN PURE MATHEMATICS

And Natural Philosophy. Containing Facts, Formulæ, Symbols, and Definitions. By the late G. R. SMALLEY, B.A., F.R.A.S. New Edition by J. M'DOWELL, M.A., F.R.A.S. 16mo. 70 cents.

MATHEMATICAL PAPERS OF THE LATE REV. J. S. SMITH.

Savilian Professor of Geometry in the University of Oxford. With Portrait and Memoir. 2 vols. 4to. *In preparation*.

AN ELEMENTARY TREATISE ON QUATERNIONS.

By P. G. TAIT, M.A., Professor of Natural Philosophy in the University of Edinburgh. Third Edition, Much Enlarged. 8vo. \$5.50.

WORKS BY ISAAC TODHUNTER, F.R.S.,

Late Principal Lecturer on Mathematics in St. John's College, Cambridge.

AN ELEMENTARY TREATISE ON THE THEORY OF EQUATIONS.

12mo. \$1.80.

A TREATISE ON THE DIFFERENTIAL CALCULUS.

12mo. \$2.60. KEY. \$2.60.

A TREATISE ON THE INTEGRAL CALCULUS

And its Applications. 12mo. \$2.60. KEY. \$2.60.

AN ELEMENTARY TREATISE ON LAPLACE'S,

Lamé's and Bessel's Functions. 12mo. \$2.60.

TRILINEAR CO-ORDINATES,

And Other Methods of Modern Analytical Geometry of Two Dimensions. An Elementary Treatise. By W. ALLEN WHITWORTH, M.A. 8vo. \$4.00.

